A Database Publication

ATARI USER

Vol. 1 No. 6 October 1985 £1

JACK TRAMIEL:
The man behind the myth

Computer Art

Unlock your Atari's graphics potential

Try your hand at

Professional displays – those vital secrets

Examine memory – the FAST way

An Atari 130XE + other prizes must be won

WELC
TO ATAR
MAGA

(IF YOU'RE NOT YET AN

Pack 1
800XL, 1050 Disk Drive,
Home Filing Manager, The Payoff,
Demonstration Software £269.99. (Normal cost £364.96)

The only way to make full use of ATARI USER is to become one. And the easiest way to do that is with ATARI Personal Computer Packs.

There isn't a better way to get into computers. There isn't a more comprehensive starter pack.

Only ATARI could give you a 64 Ram memory, cassette 'soundthrough' capabilities, a maximum of 256 colours on the screen at one time and 4 'sound' voices.

ATARI 800XL PERSO

COME
RI USER
AZINE.

ATARI USER, STOP HERE.)

A choice of a 1050 Disk Drive or a 1010 Cassette Programmer Recorder and additional software.

No one else could offer you all this power at these prices.

And, as everything comes together, you can make the most of the unbeatable ATARI 800XL straight away.

Without doubt, ATARI Personal Computer Packs are the easiest way to get into computers.

The only difficulty is deciding which one. Now read on.

Pack 2. 800XL
1010 Cassette Programme Recorder
Invitation to Programming, Pole Position,
Demonstration Software £129.99 (Normal cost £194.96)

NRL COMPUTER PACKS

Vol. 1 No. 6 October 1985

Managing Editor: **Derek Meakin**
Features Editors: **Cliff McKnight**
Mike Bibby
Editorial Team: **Alan McLachlan**
Kevin Edwards
Pete Bibby
Roland Waddilove
Technical Editor: **André Willey**
Production Editor: **Peter Glover**
Layout Design: **Heather Sheldrick**
News editor: **Mike Cowley**
Advertisement Manager: **John Riding**
Advertising Sales: **John Snowden**
Editor in Chief: **Peter Brameld**

Editorial: 081-456 8835
Administration: 081-456 8383
Advertising: 081-456 8500
Subscriptions: 081-480 0173
Telecom Gold. 79:MAG001
Telex: 285871 MONREF G
Quoting Ref. 79:MAG001
Prestel Mailbox 614568383

Published by:
Database Publications Ltd,
Europa House, 68 Chester Road,
Hazel Grove, Stockport SK7 5NY.

Subscription rates for
12 issues, post free:
£12 – UK
£15 – Eire (Sterling only)
£20 – Rest of world (surface)
£40 – Rest of world (airmail)

"Atari User" welcomes program listings and articles for publication. Material should be typed or computer-printed, and preferably double-spaced. Program listings should be accompanied by cassette tape or disc. Please enclose a stamped, self-addressed envelope, otherwise the return of material cannot be guaranteed. Contributions accepted for publication by Database Publications Ltd will be on an all-rights basis.

© 1985 Database Publications Ltd. No material may be reproduced in whole or in part without written permission. While every care is taken, the publishers cannot be held legally responsible for any errors in articles, listings or advertisements.

"Atari User" is an independent publication and Atari Corp (UK) Ltd are not responsible for any of the articles in this issue or for any of the opinions expressed.

News trade distribution:
Europress Sales and Distribution Limited, 11 Brighton Road, Crewley, West Sussex RH10 6AF. Tel: 0293 27053.

News
Read all about it. All the latest developments in the world of Atari computing. 7

First Edition
The first ST book to hit the book-stalls is on special offer this month. 12

Hardware
Mike Cook explores the operating environment which the 68000 presents to the user. 15



Game
If you fancy your chances as a card-sharp then pit your wits against this fast-dealing Pontoon game. 19

Assembler
The latest updates for *Atari User's* 6502 RAW assembler. 22

Utility
Extend your Atari toolkit with Roland Waddilove's hexadecimal/Ascii memory dump utility. 22

Contents

Graphics 27
Dave Russell gets to grips with Mode 8 – with some colourful results.

Software 29
The long-awaited Rescue on Fractalus is featured this month, along with A Day at the Races and Strip Poker.



Canvas 32
Are you e micro Monet or a computer Constable? Unleesh those artistic instincts with Stephen Williamson's painting progrem.

Display List 36
Page flipping and smooth vertical scrolling get the Mike Rowe treetment this month.

Bit Wise 40
Say, just who is that masked strenger? It must be Mike Bibby with more binary bytes.



Game 42
Timothy Harrington's Wraptrap game will have you tied in knots.



Beginners 44
This month Mike Bibby goes loopy as he continues to take the brain-ache out of Basic programming.

Contest 47
There's a 130XE super bundle up for grabs, and all you have to do is . . . read the rest of this megazine.

130 XE Utility 48
Use that extra memory as e RAM-disc with the aid of Michael King's handy program.

Adventuring 51
Brillig's beady eye turns on the incredible Infocom range.

MicroLink 53
This month's update on news from Britain's electronic mail service.

Mailbag 55
This could be where YOU feeture – but not if you haven't written to us!

Order Form 60
Binders, back issues, disc doublers, dust covers – order them ell in one fell swoop.

INTERNATIONAL

KARATE

..And you thought you'd seen a Karate game

As you know, like the Martial Arts, Perfection is the only accepted standard, so play nothing until you play — SYSTEM 3's — INTERNATIONAL KARATE

For the Spectrum, C.64, Amstrad and all 48k Ataris at ONLY

£6.50

SYSTEM 3 SOFTWARE. SOUTHBANK HOUSE, BLACK PRINCE ROAD. LONDON SE1 TEL: 01-735 8171. Ex. 68

Two budget packages launched

ATARI UK has launched new budget packages for both the 800XL end the 130XE which effectively slash the prices of both machines in the run up to Christmas.

The 800XL – voted "Home Micro of the Year" in the British Microcomputing Awards 1985 – has been bundled with a joystick and game cartridge at £70

This combintion would previously have cost in excess of £100.

Even bigger savings can be realised with an offer which links the 800XL with a dete recorder, joystick and software peck.

Although the usual price would heve been in the region of £150, this is now being offered et £99.

"You can't find better value for money enywhere ', insisted a leading dealer. "It will be a runaway winner at Christmes.

"However it all points to Atari wanting to get rid of ell their beck stock of 800XLs, cease production end then concentrete on the 130XE".

A company spokesman was quick to deny this suggestion. "We just want it to be the most competitive in the marketplace this Christmes", he said.

On the 130XE front, there ere also two new low-cost packages.

The first involves the machine, the 1050 disc drive and four pieces of software for £231, involving e saving of eround £70.

But the ster package of all sees the 130XE, 1027 letter quality printer and word processing software, together with three other pieces of software for £305.

In all the saving here would be in the region of £250.

"It is our intention to make this product the top-selling 128k computer this Christmes", says Rob Herding, Atari UK's sales and marketing manager.

Atari's aiming to clean up at Christmas

ATARI is already dreeming of e bonenze Chrietmes with the ST renge twinkling brightly otop the corporete tree.

The company is forecasting that it will sell up to 30,000 of its letest mechines in the UK alone before the end of 1985.

And it is reporting "significantly increased demend' here in Britein for tha 800XL and 130XE models.

"We thought the season would stert late this year but we've been proved wrong". Max Bambridge, Ateri UK's generel maneger told *Atari User*.

"According to our deelers, the run up to Christmas is well under wey with some excellent results.

"It ell edds up to an extremely bullish market for Atari".

Of tha 50,000 ST mechines shipped by Atari world-wide by early September the UK received less than 3,000 machines, and e large percentage of these went to software houses.

However the month saw the arrival of 5,000 STe in Britain and this month's delivery will be in the region of 10,000.

"Nor will they be on the shelves too long", seid Max Bambridge, "for even though the ST is not e seasonel machine, it just heppens to have arrived here at this particuler time of year.

"As a result it will prove to be an even better Christmas than we otherwise would heve expected".

Germeny is currently the number one merket for the ST range outside the United Stetes, followed by the UK, France then the Benelux countries end Italy.

Howaver the UK is expected soon to overtake Germeny which is only ehead because of the earlier launch of the ST there.

To ensure this, Atari's UK sales force ere currently vigorously targetting sectors of the market for the ST.

It is known they heve considerable interest in tha 1.2 million shopkeepers on Britain's high streets who have e weekly turnover of between £1,000 and £3,000.

"We now find ourselves in the position with the ST of being able to offer them something really worthwhile they heve never been eble to afford before", says Mex Bambridge.

"The UK has always been known as a nation of smell shopkeepers, but now we intend to make it e netion of small shopkeepers equipped with an ST computer.

"That's the best Christmes present they – and we – could possibly have".

Low key arrival for baby

ALMOST unnoticed in the excitement surrounding the consumer launch of the 520ST et the PCW Show, its baby brother – the 260ST – slipped quietly onto the scene.

The model was on displey but behind gless doors, so preventing the possibility of hends-on testing.

And the only informetion available about the 260ST was thet it has 256k of memory and a built-in half megebyte disc drive.

While revealing thet the machine will be on sale in the UK shortly – meinly through high street cheins – an Atari official was not prepered to put a price tag on it.

It was up to a leading dealer to indicete that he believed it would sell for less than £500.

Meanwhile the 520ST, mouse controller, half megabyte disc drive and black and white high resolution monitor will retail for £652, before VAT is edded.

ST software comes flooding in

SOFTWARE houses both sides of the Atlantic have rallied round the Atari banner in the impending battle for market dominance by the new ST machines.

It is now estimated that by Christmas there will be more than 300 titles available for both the 520ST and its baby brother, the 260ST.

"Never before has a new machine had so much software available", claimed Rob Harding, sales and marketing manager for Atari UK.

"With this level of support we are confident the ST will become the leading 16 bit machine in the UK".

The ST range received a major shot in the arm when leading business software giant TOI revealed that some 150 of its titles are now available for the machines.

Yet another boost came with the news that the BOS operating language will now enable the ST to run more than 80 BOS business oriented packages.

At the same time, it is now known that 30 UK software houses are currently nearing completion of almost 100 additional titles for the ST.

The PCW Show in London provided the first public showcase for much of the new software, some completed, some still only in prototype form.

"We have been delighted with the response from the software houses", says Max Bambridge, Atari UK's general manager.

"It has been said that the ST would rise or fall depending on the amount of good software available for it. Well we certainly know which way we are going now".

UK software houses are currently number one in the world as far as production of programs for the ST range are concerned.

At the consumer launch of the ST in London it was revealed that three times more British software than American is available for the machines.

"It's very impressive", observed Jack Tramiel, chairman of the Atari Corporation, "but you do have the best software people in the world, thanks to being the most computer minded nation".

On the ST software front at the PCW Show Atari User saw:

- A CP/M emulator from GST running a number of programs including dBase II, Microsoft Basic and Wordstar.
- Three spreadsheets, five databases and three word processors.
- The full range of Infocom advanture packages, including The Hitch-hikers Guide to the Galaxy.
- An Elite type package being developed for the ST from British Telecom's software house, Firebird.
- Lands of Havoc from Microdeal, which has the distinction of being the first software package to be converted for the ST here in the UK.
- The much praised small business package from Quest International, Cash Trader. This has been nominated for a major newspaper award.
- K-Spread from Kuma Computers, a blend of mouse and keyboard driven functions providing a spreadsheet.
- A complete cross development environment for programmers wishing to transfer IBM PC software from Metecomco. This will allow both new and existing application programs to be developed using the PC and then downloaded to the ST.

BBAS..link between ST and BBC

A 20-year-old student at the University of Kent has achieved a technological breakthrough to enable the ST range to run almost all programs written in BBC Basic.

Tristran Mabba, who is studying computing, was called in by Atari because he is considered to be an expert on the BBC Micro.

Although a prototype of his BBAS Basic Interpreter was on display at the PCW Show, Tristran is currently ironing out the bugs prior to its anticipated release later this month.

"It provides an environment that has deliberately been made as close as possible to that of a BBC computer", he told *Atari User*.

"Thus programs written for the BBC Micro should run directly on the ST, provided that they do not use machine code routines other than those provided by the operating system".

Despite the close likeness to the BBC environment, the user of BBAS still has access to special features of the ST, including windows and the mouse.

"These features are integrated into the pseudo operating system so that existing programs may easily be modified", explained Tristran.

"Naturally, though, this means that these modified programs will not run correctly if copied back to BBC machines".

A GREAT deal has already been written about Jack Tramiel, chairman of the Atari Corporation. And as so often happens with coverage of such larger than life celebrities, fiction has often tended to taint the facts.

So when Mike Cowley was granted an exclusive interview with Jack Tramiel he set out to discover the man behind the myth.

TO some, he's the saviour of the world computer industry by providing people with what they want – at a price they can afford.

After all, the ex-inmate of Auschwitz built Commodore into a billion dollar business by offering value for money.

Now he's doing the same for Atari.

But to others he is little more than a ruthless opportunist with all the niceties of a contemporary Attila the Hun.

However it was simply a balding, rotund middle aged man who rose to greet me in a private room behind the Atari stand at the PCW Show in London.

The success of the ST launch ballyhoo going on outside had obviously permeated the inner sanctum. Jack Tramiel was beaming as he extended a pudgy hand in welcome.

It is difficult to imagine that here is a man who can axe two thirds of the Atari workforce within days of taking over without batting an eyelid.

Or that he has been locked in some of the bloodiest board room battles the industry has ever seen, walking away from most the undisputed winner.

But on closer inspection it's the eyes that seem to hold the key to Jack Tramiel. Heavily hooded, piercingly shrewd, the danger signs are there for all to see.

The Atari boss has never dropped his guard in public, preferring to foster the hit man image for the benefit of the media.

So in order to get a glimpse of the private Jack Tramiel, I asked him to describe a typical

Jack Tramiel

The man behind the myth

day in his life.

Here, with a few asides, is how he described it.

Each morning he sleeps in late – or so he sees it – until around 8am. "That's one luxury I allow myself", he says.

Surprisingly he could be at any one of four addresses and still qualify to be getting up at home.

The reason for this is that he is a self confessed house collector, owning three homes in the United States and a condominium in Toronto, Canada.

More likely than not he'll be at his sumptuous Lake Tahoe home some 7,500 feet above sea level.

Or there again, he could be at his residences in either Saratoga, just 20 minutes drive from his office, or Santa Cruz, overlooking the Pacific Ocean.

"I choose the home I'm at on the basis of who I have to see on business", he confided.

But does that not get rather confusing for his wife?

"Not really", he replied. "My children have grown up, so my wife Helen, who is also my partner, travels with me wherever I go".

He usually breakfasts simply on half a grapefruit, yoghurt and coffee.

"I travel an awful lot so when I'm at home, I'm always trying to diet", he admits.

The Atari chief also uses his breakfast period to catch up on the business world by reading the Wall Street Journal. However he always puts half an hour aside to talk to Helen.

From Lake Tahoe he is flown by private plane to Santa Fe airport and then drives himself to the Atari headquarters.

Once in his office he is brought up to date on what the current problems are and decides which one to tackle that day.

"It could be anything from purchasing to designing, production to distribution", he says. "I like to be involved in the total business.

"You see I'm a generalist, not a specialist. Although I understand the engineering from the layman's viewpoint, I could not design a computer myself.

"That's why I'm lucky to have three sons who are specialists. And it's very nice to have the family involved".

Having arrived at the office at around 9.30am he goes through matters raised by his secretary, then starts to contact the outposts of his empire by phone or computer.

"I do not believe in mail", he insists, "after all, we are in the communications and information world".

Each day when at the office he usually holds a working lunch with his management team – but only when they are free of potential customers.

They drive some five minutes from the office to eat always at the same place, a seafood restaurant.

Jack Tramiel again dines sparingly at lunch – usually a piece of halibut – does not allow himself alcohol, not even a glass of wine.

"I do not drink most of the time because I suffer from gout", he says.

Back in the office he spends up until 7pm making phone calls out to the Far East to his manufacturing facilities.

Most days he will dine with a customer in the evening before returning to one of his homes.

It is only then that Jack Tramiel insists on having some time alone, relaxing by reading computer magazines, including his own copy of *Atari User*.

Although he admits he never really turns off as far as business is concerned, he does have one hobby, deep sea fishing. And he's proud of his biggest catch ever, a seven foot Blue Marlin.

But does his wife not get irritated by his strict working regime?

"I always try to have her around me to make up for it", he admits, "but I still get heat from her every now and again. That's only natural".

Jack Tramiel admits to two real loves in his life, his business and his family.

But he provided a fascinating insight into his true character the day he fired his eldest son Sam, now president of Atari.

"He felt money grew on trees, so I fired him", he recalls. "So he went into business on his own.

"One day he went to write a cheque to pay his payroll but found he had nothing in the bank.

"So he found out that money doesn't grow on trees. Now he is back working for me".

Now that is the real Jack Tramiel talking.

ATARI

EUROPES LEADING 'ATARI' MAIL ORDER SPECIALISTS

SOFTWARE EXPRESS
INTERNATIONAL

HARDWARE

130 XE CDMPUTER 128K	169.99
130XE/1050 PACK including software	299.99
800XL/1050 PACK including Software	249.99
1029 DDT MATRIX PRINTER	199.99
WS2000 MDDEM	149.55
MDDEM INTERFACE c/w Viewterm software	59.95
JDYSTICKS	
PADDLES	

BDDKS

De Re Atari	17.00
Atari Collection Vol. 1	11.95
Mapping the Atari	12.60
Atari Basic Tutorial	11.95
Atari XL Handbook	5.95
Technical Reference Notes	17.00
Arcade & Graphics Design	12.80
Hackers Handbook	4.95
Exploring Adventures	6.95

+ 75p post & packing

ADVENTURE

Adventure Quest		9.95
Ultima III-Exodus		19.95
Cut Throats	(D)	29.95
Deadline	(D)	37.95
Dungeon Adventure	(C)	9.95
Emerald Isle	(C)	6.95
Enchanter	(D)	37.95
Hitch-hikers Guide to the Galaxy	(D)	29.95
The Hulk	(C/D)	9.95 / 17.95
Infidel	(D)	39.95
Lords of Time	(C)	9.95
Mask of the Sun	(D)	43.95
Midwinter	(C)	7.95
Saga 1 5	(D)	17.95
Seastalker	(D)	32.95
Sorcerer	(D)	39.95
Starcross	(D)	32.95
Suspect	(D)	37.95
Suspended	(D)	37.95
Wishbringer (Infocom)		29.95
Witness	(D)	37.95
Zork 1, 11, 111		29.95

MAGAZINES

ATARI USER 1.00 PAGE 6 90
ANTIC 3.50 ANALOG 3.00

SIMULATIDN

Sublogic F.S. 11	(D)	43.95
F 15 Strike Eagle	(D)	14.95
Solo Flight	(C/D)	9.95/14.95
Space Shuttle	(R)	19.95
Spitfire Ace	(C/D)	9.95/14.95

NEW US IMPORTS

Paperclip	59.95	Seven Cities of Gold	32.95
Homepack	49.95	Crusade of Europe	35.95
B-Graph	69.95	Mindwheel	39.95
Printshop	39.95	Rescue from Fractulas	34.95
Kennedy Approach	35.95	Bellblaser	34.95

STRATEGY

Broadsides	(D)	33.95
Colosuss Chess 3.0	(C/D)	9.95 / 12.95
Operation Market Garden		55.95
Computer Ambush	(D)	49.95
Cosmic Balance	(D)	33.95
Cosmic Balance II	(D)	33.95
Eagles	(D)	33.95
Field of Fire	(D)	33.95
Fortress	(D)	29.50
Gemstone Warrior		36.95
Kampfergruppe		55.95
Rails West	(D)	62.75
Reforger 88"	(D)	45.95
Market Forces	(D)	19.95

ENTERTAINMENT

Zone Ranger	(R)	19.95	Bounty Bob	(C)	9.95
Mig Alley Ace	(C/D)	9.95/14.95	Miner 2049'er	(R)	12.95
Pinball Constructor Kit		Phone	Mr Do	(C)	9.95
Bruce Lee	(C/D)	14.95	Pac Man	(C)	9.95
Conan	(D)	14.95	Pitfall II	(R)	19.95
Music Constructor Kit		Phone	Quasimodo	(C/D)	9.95/14.95
Dropzone	(C/D)	9.95 / 14.95	Smash Hits 1	C/D	14.95 / 17.95
Decathlon	(C)	9.95	Smash Hits 11	C/D	14.95 / 17.95
One on One	(C/D)	9.95/12.95	Smash Hits 111	C/D	14.95 / 17.95
Chop Suey	(C)	8.95	Hijack	(C/D)	7.95/10.95
Kissin' Kousins	(C)	6.95	Summer Games	(D)	33.70

INFOCOMS INVISICLUES

Hitch Hikers Guide	6.95
Cut Throats	6.95
Suspect	6.95

Available Now
ALL OTHER TITLES ALSO AVAILABLE AT THE SAME PRICE

520 ST
C/w Disc Drive
B/W Hi-Res Monitor 749.99

Colonial Conquest
Blue Max 2001
Dambusters
Electrician
Kennedy Approach
New York City
Monday Morning Manager
Gt. American Road Race Disk

UTILITY

Magniprint II	(D)	25.95
Action	(R)	75.00
Action Tool Kit	(D)	27.95
Basic XL	(R)	60.00
Basic XL Tool Kit	(D)	27.95
DOS XL		27.95
MAC/65	(R)	75.00
MAC/65 Tool Kit	(D)	27.95
Sparta DOS	(D)	39.95
Basic XE	(R)	75.00

NEW SERVICE

Custom software programming. We can write software tailored to your needs, at very competitive retes.
PHDNE US NDW

SEND SAE FOR OUR PRICE LIST.
31 STONEYHURST ROAD
ERDINGTON, BIRMINGHAM B24 8HA

HOTLINE
(021) 384 5080

Atari keeps family together

FIONA Simmons' sea captain husband Tony is nearing the end of a seven month voyage to the other side of the world and back.

But all the while his ship has been sailing round the Pacific Ocean he has been only seconds away from his wife and children in Derbyshire.

This remarkable feat of communications is made possible by Mrs Simmons' Atari 800XL and modem, the MicroLink electronic mail service and the international satellite system.

She has been able to send and receive weekly telex messages that have kept the family in touch and eased the heartache of the long seperation.

Before MicroLink, Mrs Simmons had to contact her husband – a Merchant Navy officer for 22 years – via the marine radio station at Portishead, near Bristol.

And although the technicians there were always very helpful this meant having to telephone her telex and have it taken down manually and sometimes having to queue to get onto the system, never being sure when the information would reach her husband on the high seas.

"With MicroLink I can do the job all by myself", Mrs Simmons told *Atari User*. "The message is transmitted in seconds to anywhere in the world Tony might be.

"The system lets us be in contact with each other much more than before and that is very important to me living in an isoleted pert of the country with my three young children.

"Not only do I feel closer to my husband while he's away, if eny problem crops up here I know I can heve the benefit of his advice within e short time via his ship's telex fecility".

Mrs Simmons said she had been pleasantly surprised to find out how easy it wes to use her Atari to send telex messages.

"I'm by no means e computer expert", she said. "In many ways I have been having to learn from my mistekes, such as occesionally truncating a message unintentionally and somewhat exceeding my telephone budget.

"But I can't speak too highly of the MicroLink help line team. They have been absolutely super, teking a lot of time and trouble to put me on the right treck when I wes heving teething troubles with the system.

"I believe e lot of women are frightened of computers, possibly because they are afraid of making embarrassing mistakes. But my advice to them is not to be – femeles should be just as involved in the world of computers as meles.

"It was because of this belief that I bought the Atari for my daughters, so they wouldn't get left behind by the boys at their school.

"Now I'm learning along with them and loving every minute – particularly thet part of computing that keeps me in such close contact with Tony".

Keeping in touch with Dad . . . Mrs Simmons and her children

32 bit launch at Comdex?

THE long-awaited 32 bit machine from Atari is almost certain to take its bow at a major American computer show in November.

Comdex in Las Vegas is being touted as the launching pad for the new computer.

Asked when it would be unveiled, Max Bembridge, Atari UK's general manager told Atari User: "Just make sure you are at Comdex in Las Vegas. There's going to be a lot happening there . . ."

Game 'breakthrough' for the ST

A TRIO of top UK software authors who have known both overnight success and overnight failure have got together again to write for the 520ST.

David Lawson, Ian Hetherington and Eugene Evans believe the megagame they have developed – Brataccas – will reestablish them at the pinnacle of the computer games world.

Once the driving force behind the Liverpool based Imagine software house, all three saw fame and fortune snatched from them when the company spectacularly crashed with staggering debts last year.

"We are on our way back with this", David Lawson, who claims to have personally lost £350,000 in his company's cresh, told *Atari User*.

In all, it has taken the authors some four months to write the 400,000 lines of machine code needed for Brataccas.

An adventure game, it is being hailed as a technological breakthrough in that it allows the players to become characters in a seemingly infinite number of cinema type roles.

"We always wanted to create our own movies", says David Lawson. "So we've done just thet and put it on a computer. We just drop the player into it".

But will success once again spoil the lads from Liverpool if Bratecca goes as well as they believe it will. After all, they are the first to admit thet back in the days of Imagine, the money simply went to their heads.

This time it looks unlikely. For the software house for which they now work, Psygnosis, is firmly in the control of Talbot Smith, a hard headed Merseyside entrepreneur.

His empire stretches from steel stockholding to haulage.

"This time when success comes the lads' way courtesy of the 520ST, I'll be holding on to the purse strings", he told *Atari User* meaningfully.

More on the way

ATARI has three more computers in the pipeline to follow the successful launch of the 520ST and 260ST machines. This was revealed by chairman Jack Tramiel during his recent visit to London. "We are already working on three new machines that will be better than the ST", he told *Atari User*. "We will not allow ourselves to get stale".

Understanding the ST

Following the launch of tha Atari 520ST we can expect to see many books devoted to every aspact of the machine. Here we present extracts from the first such book – "The Atari ST Companion" by Jeramy Vine, publishad by Sunshine Books.

The exciting ST

WHERE do you start when describing a machine that has been hailed by the press in the most glowing terms? Rarely has one machine caught the imagination of so many people, both within the computer industry and externally.

The Atari ST has been described in superlatives since it was announced and the chances are if you're reading these words, you agree too!

What makes the ST exciting, beyond all else that has gone before and for that matter for the future, as far as one can tell, is the sheer range of applications the machine can

A guided tour of the hardware

THE ST has been heiled ee the "power without the price", but whet exactly ie that power? This section ie designed to guide you around the ineidee of your ST eystem.

Understanding how a computer works is not essential to using a machine – you could quite happily never know what's inside 'that box' and still make the most of your micro.

However, understending the workings of a micro is not as horrific an idea es it seems and can go a long way to enhencing the user's understanding of and interaction with the machine.

Many users new to computing find it hard to imagine what is actually happening when they press a keyboerd button (or mouse!) and feel they are communicating with an alien presence. What we aim to do is give you an idea of what each component part does end how it interacts with the rest of the machine.

The ST series of micros is based around the Motorola MC68000 microprocessor, which can be considered es the heart of the mechine.

Much is made of whether these chips are 32 or 16 bit in size. The 68000 has an internal structure of 32 bits but externally the errangement is 16 bit. The 68000 in the ST contains a 24-bit address bus and a 16-bit data bus.

The chip is very fast, running et e clock speed of 8MHz. This speed is especially impressive when compared with other systems.

The MC68000 CPU (Central Processing Unit) chip has eight 32 bit data registers, nine 32 bit eddress registers, 14 addressing modes, memory mepped I/O and a 56 word instruction set. In addition, the chip can address 16 mbytes of memory directly without any need of bank switching.

Supporting the CPU is the MK68901 MFP (Multi Function Peripherel), which sorts out verious interrupt control meesures (Interrrupt tables are shown later in this section).

Ateri have designed their own custom built microprocessors, of which there ere four. These chips are e DMA (Dynamic Memory Access) controller for use with a hard disc.

The purpose of the DMA is to look after mass storage end this directly interfaces with a very fest parallel port for the herd disc. The transfer rates will be up to 8 megabits a



A global view of the ST's components, taken from The Atari ST Companion

encompass.

Because of its price, the ST has a vast appeal matched only by its power. At long last there is a machine which offers state-of-the-art technology at a price which transcends the home/business market barrier which has eluded micro manufacturers until now.

The ST is as true a business machine as any on the market and with the GEM operating system as standard offers the latest in icon-based mouse control.

The Atari ST Companion is intended for a varied readership. For those new to the concepts of GEM, or indeed new to the concept of computing, this book sets out to provide you, the user, with information that will help and guide you through the first stages of using your ST.

For the more experienced enthusiast who wishes to delve deeper, the ST system is looked at in great detail including TOS, the Intelligent Keyboard Controller and a guided tour around the ST hardware. Even if you're a beginner the text has, I hope, been presented in such a way as to give you an idea of what goes on inside 'that box'.

I've called this book the 'ST Companion' because that's what I hope it will become to you. The first section covers all that is necessary to get your ST up and running. Even if you're acquainted with the idea of using a mouse, section 1 contains all the information needed for the everyday tasks of maintaining a computer system.

The rest of the book looks in detail at specific parts of the ST and provides in the first instance a library of reference material, and secondly what I hope is a better understanding of the different component parts that go towards making the ST the machine it is.

I have intended since the inception of this book that the 'Companion' should be a book that serves both as a comprehensive introduction to the ST and its workings, and as a source of reference.



You can buy this book direct from *Atari User* for £9.95 (post free). Please use the order form on Page 61.

second.

The DMA is also interfaced to the floppy disc drives through the WD177D/1772 FDC (Floppy Disc Controller).

The DMA removes the need for data to be moved through the main processor when it is being transferred between the main memory and a peripheral device. The main memory (RAM) access channel is shared to allow for both slow speed (250 to 500 kbits a second) and high speed (which can be up to 8 megabits a second) 8 bit device controllers.

The second custom built chip is a Memory Controller unit. It can be considered as a management system for the ST's memory and some timing functions. This unit runs at a very fast 16MHz and this is put to good use.

The memory controller can use memory for both the CPU and the video, without the former being slowed.

The output to video is put through the third custom chip, a Video Shifter, which is, in effect, a video controller for the screen modes provided by the ST. This chip handles all the information about graphics.

Finally, the fourth custom chip is the Control Logic. Its task is to put in order and watch over everything in the machine. The Control Logic manages the jobs that would normally be handled by TTL's, except in the case of the ST this would be a tremendous amount.

The control logic chip is in communication with almost every part of the machine and is a key element in the structure of the ST.

. . . with the Multi-Viewterm/Datatari modem serial interface plus software package from Miracle Technology.

This unique comms package gives ATARI* users full Prestel* facilities, including graphics, and allows access to Micronet*, Viewdata systems, telex, electronic mail, bulletin boards and databases. Datatari handles baud rates of 1200/75, 75/1200, 1200/1200, 300/300 B60 interface not required

For models 400, 800, 600XL, 800XL, 65XE, 65XEM and 130XE used with suitable modems

To get your ATARI on-line, all the way, clip the coupon today

Please send me
☐ Multi-Viewterm/Datatari packages @ £59.93 inc VAT + £1.15 UK P/P
☐ I enclose cheque/postal order
☐ charge my Access/Visa card no

expiry date / /

Name

Address

Postcode

send to
Atari Support 3, Miracle Technology (UK) Ltd, St Peters Street, Ipswich IP1 1XB
Tel 0473-21614

*reg'd trade marks of the companies concerned

FULL PRESTEL FOR ATARI USERS!

MIRACLE TECHNOLOGY

DATASCAPE

ATARI SOFTWARE SPECIALISTS

ARCADE

	cart	
Oils Well	14.95	
BC's Quest	14.95	
Miner 2049er	9.96	
Jungle Hunt	9.96	
Pacmen	9.96	
Centipede	9.95	
Donkey Kong Jnr.	14.95	
	cass	**disk**
Archon	9.95	12.95
Realm of Impossibility	9.95	12.95
Bruce Lee	14.95	14.95
Decathlon	9.95	N/A
Pitfall II	9.95	N/A
Murder on the Zinderneuf	N/A	14.95
Mr Robot	N/A	14.95
Dropzone	9.95	14.95
Bounty Bob	9.95	14.95
F-15 Strike Eagle	14.95	14.95
Mig Alley Ace	9.95	14.95
Conan	N/A	14.95
Pole Position	9.95	14.95
Beach Head	N/A	14.95
Mercenary	9.95	12.95
Encounter	9.95	12.95

ADVENTURES

	cass	disk
Cutthroats	N/A	29.96
Hitch Hikers	N/A	29.95
Wishbringer	N/A	29.95
Red Moon	6.95	N/A
Emerald Isle	6.95	N/A
Dungeon Adv	9.95	N/A
Snowball	9.95	N/A
Return to Eden	9.95	N/A
The Hulk	8.95	17.95
Saastalker	N/A	29.95

UTILITIES

	cart
Basic XL	75.00
Action	75.00
	cass **disk**
M.M.G. Basic Compiler	N/A 59.95
Megaprint II	N/A 25.95
Homeword	N/A 48.95
Data Manager II	N/A 29.95
Typesetter	N/A 34.95
The Page Designer	N/A 29.95
U.S. Doubler	H/W 79.95

SIMULATIONS

	cass	disk
Field of Fire	N/A	36.95
Broadsides	N/A	38.95
Objective Kursk	N/A	38.95
Eagles	N/A	36.95
50 Mission Crush	N/A	36.95
Rails West	N/A	36.95
Colonial Conquest	N/A	38.95
Gemstone Warrior	N/A	36.95
Six Gun Shootout	N/A	36.95
Cosmic Balance	N/A	36.95
Cosmic Balance II	N/A	36.95
War in Russia	N/A	74.95
Kampfgruppe	N/A	55.95
Operation Market Garden	N/A	55.95
Break through in the Ardennes	N/A	55.95
Carrier Force	N/A	56.95
Computer Ambush	N/A	55.96
Reforger 88	N/A	55.95
Questron	N/A	55.95
Galactic Adventure	N/A	55.95
Computer Quarterback	N/A	36.95
Computer Baseball	N/A	36.95
Flight Simulator II	N/A	43.95

SPECIAL OFFER
US No 1 Hit Boulder Dash
cass 8.45 (N.R.P. 9.95)
disk 12.95 (N.R.P. 14.95)

For FREE Catalogue send a loose stamp. Send cheques P/D to:

DATASCAPE
46, Huntsworth Mews,
London NW1 6DB
Tel: 01-723 0662



The 68000 Operating environment

In Part III of his series examining the powerful 68000 chip at the heart of the Atari ST, MIKE COOK explores the operating environment presented to the user

SO fer we heve looked at the instruction set end the eddressing modes of the 68000 microprocessor. Now we'll teke a look et its third significent espect: the opereting environment preaented to the user.

In most other microprocessors this is so simple that it can be ignored. But in the 68000 there are so meny different ways the processor can act that the design and operetion of a computer is a very sophisticated affair.

Basically the 68000 can run in two modes, e supervisor mode end a user mode. In the supervisor mode there are certain privileged instructions allowed that cannot be executed in the user mode. The usual arrangement is to have the operating system run in the supervisor mode with the programs or lenguages running in the user mode.

It is even possible to arrange true multi-user operation using these modes. The key to understanding the usefulness of these two modes lies in the interrupt structure.

An interrupt is something which changes the normel flow of a program. All microprocessors will respond to two or three different interrupting conditions but the 68000 greatly enlarges this concept – so much so that the conventional interrupts become just a special case of the much wider concept of exceptions.

An exception means an event – that is, something happening. This triggers off the execution of a program that is said to perform exception processing. The majority of the time an exception is something which should not have happened. Exception processing can correct this or at least prevent the situation getting out of hand.

For each exception condition there is a vector. A vector is a memory locetion that contains the address of the exception processing routine

Each vector has a unique address depending upon the exception There are so many of these that they occupy the first 1k of memory in the microprocessor, each vector occupying four bytes.

The first is the reset vector, so in memory location 0 you will find the address of where to start when the machine is powered up or the reset line is pulled. This needs to be in ROM because it has to be available on power-up.

However it would be somewhat limiting to have all the exception vectors frozen in ROM where, committed to a task, they can't be changed. Therefore most computers designed with the 68000 have to switch this eree of the memory mep between ROM and RAM as part of the reset procedure. This makes the designing of the memory address decoding more complex then the average computer.

Exceptions can be divided into two types, internal and external. An

internal exception is one that has been generated by the program being run, and an external exception is one genereted by a signal from outside the microprocessor.

All exception processing takes place in the supervisor mode. In fact the only way to enter the supervisor mode from the user mode is by an exception occurring.

Let's look at internal exceptions. If you try to access a word or long word quantity at an odd address this generates an *addressing error* exception. This is usually a result of your pointers getting out of alignment and the normal course of exception processing is to inform the user and then return to the user mode.

With a *privilege violation* exception, the processor has attempted to execute an instruction which can only be used in the supervisor mode.

There is also an *illegal op-code* exception which occurs if you try to execute something which is not an instruction. This is very useful for catching programs which have gone out of control and started executing your data.

A closely allied exception is the *unimplemented op-code*. This is caused when you try to execute an instruction starting with a hexadecimal value of A or F, as no instructions actually start with these values. You can use this to write your own macro instructions.

The Apple Macintosh computer makes extensive use of this exception to allow user programs to tap into the operating system ROM. The value following the A is looked at by the exception processing routine and the appropriate operating system call is made. In this way you never need to know the address of a routine and so the same programs can work with different revisions of the operating system ROM.

There is a trace flag in the status register which, if set, causes a *trace* exception to occur after each instruction has been executed in the user mode. This makes the implementation of single stepping debuggers very simple. It will even single step through ROM, something that other microprocessors need special hardware to do.

There are also exceptions that occur when something goes wrong with an instruction. For example, if you try to divide by zero an exception will occur. Also, some overflow conditions (when the result of an operation is too big to fit in the register) will trigger exception processing.

There is, however, one set of instructions whose sole function is to cause exception processing – the TRAP instructions. There are sixteen of these, each with its own vector that can be used by the operating system for many reasons. For example, one computer uses TRAP instructions to perform all the inputs and outputs,



thus providing a consistent interface for all programs.

Of the external exceptions perhaps the simplest is the *reset signal*. When this is triggered, the processor vectors through memory location zero and enters the supervisor mode. This is used on power-up or as a panic button, hopefully situated at some remote piece on the computer.

The *interrupt request* will be familiar to those acquainted with other processors. However the 68000 has three of these lines. All three are involved with the request, thus giving seven different kinds of interrupt. Each kind is given a number or level depending upon the state of these lines.

Every level has its own priority, the higher levels having higher priority. The processor can mask out levels it does not want to respond to by the use of its status register, an extension of the normal single maskable interrupt. Again each interrupt level has its own vector.

The final external exception is the *bus error* input. This is a single input to the processor and despite its name can be used for any purpose. The most common use is the detection of non-existent memory.

Most microprocessors give the external memory a certain time to respond to eny request for access. If the memory device is slow it can send a signal back saying that it wants longer.

The 68000, however, works the other way round. It requests memory access and then waits for the memory to say that it is ready. This carries the disadvantage that if memory is accessed which does not exist then the whole system hangs up. So to prevent this, most 68000 based computers have a timer and if memory has not responded within (for example) one second the bus error line is triggered causing an exception.

This is not the only use of this line. There are outputs on the 68000 which reflect the type of process going on. They will, for example, indicate whether deta or an instruction is being fetched from memory and whether the processor is in the user or supervisor mode.

The Sage computer uses these signals together with the address bus to trigger a bus error exception if access is made to a certain area of memory from the user mode. This area of memory contains all the input/output devices. Thus the only way to interact with the outside world is through the supervisor mode, forcing user programs to use the appropriate TRAP vectors to perform input/output operations.

As you can see, the exceptions allow e considerable degree of sophistication to be built into the operating system of any computer containing the 68000 microprocessor. It offers facilities more like a mini-computer than a microcomputer. In these three articles I have only been able to outline this complex device but I hope you now have a picture which will allow you to make sense of any book written about the 68000. It truly gives power to the programmer.

Compumart

Mega Deals

ATARI HARDWARE

Atari 800XL Computer & Atari 1050 Disk Drive
(Inc. Home Filing Manager & Pay off Adventure & Atari Demo) **£234.95** + £3 p&p

Atari 800XL Computer **£79.95** + £3 p&p

Atari 1050 Disk Drive (With FREE DOS 2.5) **£169.95** + £3 p&p

★NEW★ Atari 130XE Computer
(With 2yr. Warranty) **£149.95** + £3 p&p

★NEW★ Atari 130XE Computer & Atari 1050 Disk
Drive (with 10 Blank Disks FREE) ~~£289.95~~ + £3 p&p
Now 259.99 + £3 P&P

BLANK DISKS

Top Quality 5¼" Single Sided/Double Density Blank Disks
Buying in bulk has enabled us to supply these disks at the

Best Prices in the U.K.
With a LIFETIME WARRANTY

Box of 10 5¼" SS/DD Blank Disks including labels and write protect tabs

ONLY £9.95 + £1 p&p

Buy 5 Boxes and get a **FREE** Storage Case worth over £10!!!

50 5¼" SS/DD Blank Disks in a **FREE** Perspex Storage Case

ONLY £49.95 + £2 p&p

Goods despatched same day . . . . Disks 1st class post, Hardware – parcel post
Please send cheques/postal orders to:-
Compumart,(Dept. AU6)
71 Gracedieu Road, Loughborough,
Leics. LE11 0QF Tel: (0509) 262259

VISA Access

You bought the wrong computer

...or did you?

Well on Sept 13th you can find out. The first issue of **Computing Age** will be available on the newstand. On the front will be a FREE 32 page booklet assessing the seven best new generation micros... how does your computer stack up with the best?

Computing Age is a brand new monthly magazine aimed at the serious computer enthusiast.

With the emphasis firmly on applications, new developments and strong communications coverage, the first issue explains how to log onto Telecom Gold; the incredible speed and storage possibilities of compact discs; blowing your EPROM on the BBC; a comparison of new 16 bit machines and what *NOT* to buy this Christmas.

If you're serious about computing, get **Computing Age**, on sale Sept 13th.

PONTOON

Try your hand at STEPHEN BOXLEY's challenging Atari card game

IF you've ever played card games the chances are that you've played Pontoon at one time or another. Maybe you called it 21, but the game remains the same. This program lets you play the game against your Atari.

After the title screen has been displayed you'll have to wait just under half a minute while the lower case alphabet is redefined to show the multicoloured numbers displayed on the cards.

Once you've entered your name you're ready to play, so roll up your sleeves and pull down the eyeshield.

The first two cards are displayed and you are asked to bet. You cannot bet a negative amount because if you lost, your score would increase – think about it!

Once you've entered your bet you have the options of twisting – getting another card – or sticking – accepting your present total. The T and S keys are used to select your choice of action.

In the version of the game played by the program, a five card trick beats everything except Pontoon itself. As is customary in gambling dens, if you and the dealer have the same hand, including Pontoon, the dealer wins.

The computer doesn't cheat – it decides whether it should twist or stick without looking at your cards.

The program was written on an Atari 800 and has been tried successfully on a 600XL, 800XL and 130XE. It runs in 16k.

MAJOR VARIABLES

OFCT	Has human got five card trick?
FCT	Computer five card trick.
C	Card.
S	Suit.
Q	Horizontal position of card.
O	Vertical position of card.
DL	Display list.
TOTAL	Computer's score.
SCORE	Human's score.
BET	Amount bet.
MONEY	Amount of money left.

SUBROUTINES

590	Prints cards on screen
650	Chooses a card and stores it so it won't be used again in this game.
1000	Adds up score and checks to see if you've busted.
1018	Human has lost.
2000	Computer's go
3000	Prints computer's score.
3020	Computer busted.
3025	Computer has lost.
5000	Bet entered.
5500	Who's won?

```
0 REO'N PONTOON N
6 MEM *   by    *
7 OEO * Stephen N
0 OEM * Ooxley  *
10 P=54279:0=10R:5=559:6=53277:N=53240
:PC=764:DL=PEEK(560)+256*PEEK(561):A=P
EEK(0)-0:0=1:600PHICS 0:NP=196
20 POGE P,A:N=256*A:POGE 5,46:POKE 6,I
:POKE N,HP:Y=17:POKE 01,1:MONEY=10
30 FOR I=N+512 TO N+1024:POKE I,0:NEXT
 I:FOR I=512+Y+0 TO N+510+Y:REOR A:POK
E I,0:NEXT I:POKE PC,65
40 OOTO 0,17,35,256,I2,16,0
60 FOR T=6 TO 20:POKE DL+T,4:NEXT T:PO
KE DL+3,69:POKE 709,2I:SETCOLOR 2,16,1
5:SETCOLOO 0,10,15
0R OI0 I$(46):I$="---(OEOICATEO TO NAR
OIET OIOLEY)        ":SOUNO 0,256,4,16
70 FOO K=1 TO I7:NP=NP-4:POSITIOO 0,0:
? "?":POSITIOK 39,0:? I$(N,K):POKE N,N
P:NENT N:POSITIOR 0,0:T "        "
0R POGE N,0:SOUND 0,6,0,0:POSITIOK I4,
0:? " ":FOR K=1 TO 255:SETCOLOR 2,N,12
:SETCOLOO 0,K,12:NEKT N
90 POGE DL+7,6:POGE 6L+0,6:POSITIOR 1,
2:? "sprokkley presents":FOO I=N+612+Y
 TO N+610+Y:POGE I,0:0EXT I
90 Y=04:POGE N,40:FOO I=N+Y+612 TO N+Y
+519:0EAO A:POGE I,A:0EXT I:OOTA 0,0,6
6,124,256,256,102,0
100 POKE PC,71:SOOND 0,210,12,10:FOO T
=40 TO 123:PORE N,T:FOO Y=1 TO 11:6EXT
 Y:NEXT T
105 FOR T=8 TO 16:SOUBO 0,200,6,T:N=2^
2:NENT T:POGE 0+1,123:POKE 70R,51
110 FOR Y=90 TO 0I STEP -1:0EAO A:POGE
 N+640+Y,0:NEKT Y:OOTA 06,36,24,24,266
,24,0R,24
120 SOUUD 0,0,0,0:FOR T=123 TO 240:POR
E N,T:NENT T
130 PORE DL+12,7:POKE OL+1I,7:FOR T=1
TO 3:POSITIOO 6,6:T "Pontoon":SOUND 0
,06,0,11:FOR I=10R TO 1 STEP -1
140 SOUNO 0,I/10,0,Z/14:NEKT Z:SOUNO 0
,0,0,0:POSITIOR 6,6:? "          ":N=2
^2:N=2^2:NENT T:POSITIOR 6,6
150 ? "Pontoon":PORE DL+15,6:PORE DL+
16,6:POSITIOH 0,0:? "written by: S.Box
ley              1985":Y=0I
160 OIN A$(24),8$(24),C$(24),0$(24),E$
(24):A$="0240R0024126024016066066":0$=
"024060193126024211129OR0"
170 C$="024109090000R0240I60R6129":0$="
0240601621260200I60R0038":E$="02406602
41090900240I6102":HP=12I
180 NESTOOE 200:FOO T=1 TO 64:NEAG A:S
ORNO 0,A,10,15:SORNO 1,A*2,10,16:I=)NT
(RUB(0)*5):6OSUB 191+Z:S=1:J=I
190 FOO I=640+N+Y TO 647+N+Y:POKE I,VO
L(I$(S,J)):S=S+3:J=J+I:NEKT I:0RUNO 0,
0,0,0:56UN0 1,0,0,0:NEKT T:6OTO 260
191 I$=A$:0ETORN
192 Z$=0$:RETORN
193 Z$=C$:RETORN
194 I$=0$:RETOON
196 I$=E$:RETHON
20R ORTA 01,01,01,72,64,72,01,64,72,72
,01,0,0,01,01,01,72,98,72,01,64,72,72,
01,0,0,72,72,72,72,47,47,0,0,72
210 OGTA 01,42,47,0R,0,0,01,01,61,72,6
4,72,01,64,72,72,01.0,0
200 FOO T=1 TO 90 STEP 4:NP=NP+4:RESTO
RE 280+(INT(RND(0)*4)*10):FOR I=N+Y+64
0 TO N+Y+647:REOR A
270 POKE I,0:NEKT I:POKE 63249,NP:SOU0
0 0,255,10,15:SOUND 0,0,0,0:NEKT T:0OT
0 320
20R ORTA 24,0R,24,20,20,24,20,36
290 ORTA 24,00,24,30,24,24,20.26
300 OATO 24,00,24,24,62,00,24,20
310 OATA 24,0R,24,24,62,00,36,34
320 POKE N,0:POKE N+1,0:FO0 T=6 TO 20:
POKE DL+T,4:NEKT T:T "KWANT INSTRUCTIO
NS??":OPEN #1,4,0,"K:":POKE 709,0
3I0 POKE 700.55:PORE 710,66:GET #1,A:I
F C60$(A)="N" THEO ORTO I90
340 IF CHR$(A)<>"Y" THEN ? "TRY PRESSI
6G Y or N":6OTO 330
30R ? "NINSTRNCTIONS:":? "THIS GAME IS
 EKACTLY LIKE BLACKJACK.":T "YOU KOVE
TO SCORE A MAKIMUM OF 21."
366 ? "JACKS,QUEENS ANO KIN6S ALL COUN
T AS    TEN.IF AN ACE COMES UP YAN NAV
E TO  "
370 ? "OECIOE TKERE 000 THEN WHOT YOU
WANT IT TO OE:1 or 11 OY PRESSIN6 0 or
 0":T
380 T "NOPE YOK ENJOY PLAYING POOTOO6.
":0E0
390 ? :? "POESS 60Y 6EY TO STAOT":GET
01,A:FOR T=6 TO 20:POKE OL+T,4:0ENT T:
? "N        PLEOSE WAIT-INITIALIZIOR"
400 NESTORE 420
405 CH=PEEK(106):C0=(CH-0)*266:FO0 L=0
 TO 1023:OYTE=PEEK(67344+L):POKE CH+L,
OYTE:NEXT L:? "NEARLY FINISHEO!!"
410 POKE 712,48:FOO T=97 TO 122:C=T:C=
CN6:FOO L=0 TO 7:REOR BYTE:POKE CH+C+L
,BYTE:NEXT L:NEXT T:POKE 756,CH/256
419 REM CHARACTER SET
420 ORTA 60,196,195,190,255,190,195,19
6,202,3,I,I,12,48,192,255,255,3,3,256,
3,3,3,255
430 DATO 0,00,204,204,204,255,12,12,20
6,192,192,255,3,3,195,0R,0R,192,192,20
2,195,195,195,0R
440 6ATA 0,256,255,I,16,0R,40,40.0R,19
6,190,60,00,195,195,00,60,190,196,63,I
,I,12,240
460 OOTO 207,207,207,207,207,207,207,2
07,255,12,12,12,12,12,204,262,0R,195,1
90,190,190,190,204,61
460 ORTA 195,195,204,240,240,204,195,1
90,20,65,65,65,06,66,66,66
470 ORTA 64,1,1,1,4,16,64,06,05,1,1,0R
,1,1,1,07,0,20,60,0R,0R,0R,4,4,05,64,6
4,06,1,1,66,20
460 OATA 20,64,64,64,65,65,65,20,0,05,
05,1,6,20,16,16,20,65,65,20,20,65,65,2
0
490 ORTO 20,66,66,21,1,1,4,00,69,69,69
,69,69,69,69,69,85,4,4,4,4,4,60,04,20,
65,65,65,65,65,60,64
499 OOTA 66,65,60,00,00,00,65,65
50R OESTOOE 510:FOO T=2 TO 9:C=T:C=C*0
:FOO L=0 TO 7:0EOR OYTE:POKE CH+L+C,OY
TE:NEXT L:NEXT T
610 ORTA 255,205,255,255,255,256,255,2
56,06,06,05,06,05,06,05,06,170,170,170
,170,170,170,170,170,05,170,05,170
620 ORTA 0R,170,06,170,20,20,0R,05,02,
20,20,05,4,4,17,17,0,4,21,21,61,63,63,
63,63,12,12,0,12,12,63,63,63,6I,12,12
540 POKE 700,0:POKE 709,10:POKE 710,62
:POKE 712,265:POKE 712,0:0)M N$(16):?
"NPLEASE ORTE:"
550 ? :? "& =SPADES":? :? "' =CLUBS":?
 :T "( =NEAOTS":T :? ") =OIAMONOS":? :
? "j 00 w =T6E NUMBEO TE0(10)"
556 ? :? "YOK 6AVE THE TOP 0ON OF CAUO
S":T :? "YOR NAVE 10 CHIPS(MONEY) TO P
LAY WITH"
656 ? :? "IF A 0OAN,REALEO(TOE COMPKTE
0!')NIOS!!"
560 T :T :? "POESS A 6EY":6ET #1,A:T "
KWHAT IS YOUO NAME??":IOPOT N$
070 ? "N":POSITIO0 2,0:? "HELCOME TO P
ORTORN ";N$:? :T "POESS A 6EY":6ET #1,
0:? "K"
600 POSIT)ON 2,0:? "  ":POKE 02,1:? :T
 :6OTO 6I0
690 ? "$$$$$$  $$$$$$  $$$$$$  $$$$$$
 $$$$$$":? "$    $  $    $  $    $  $
   $  $    $":OFCT=0:FCT=0
0R6 T "$    $  $    $  $    $  $    $
 $    $":T "$    $  $    $  $    $  $
   $  $    $"
610 ? "$    $  $    $  $    $  $    $
 $    $":T "$    $  $    $  $    $  $
   $  $    $"
620 T "$    $  $    $  $    $  $    $
 $    $":T "$$$$$$  $$$$$$  $$$$$$  $$
$$$$  $$$$$$":NETO00
630 0RSUB 690:T :? :0RSUB 690:0IM 55(5
4),CC(64):N=0:N=0
640 0RTO 800
656 C=INT(0N0(0)*1I)+1:V=C:5=IOT(RND(0
)*4)+1:N=N+1:CC(N)=C:55(N)=5:IF N=1 TO
EN 800
660 FOR D=1 TO (N-1):IF CC(N)=C AND 55
(D)=5 THEN N=N-1:GOTO 650
670 NEXT 0
0R0 IF S<I THEN C=C+109:GOTO 700
690 C=C+96
700 POSITIOR 2+0,4+0:? CHR$(C):POSITIO
N 6+0,4+0:? CHR$(C):POSITIOR 2+0,9+0:?
 C60$(C):POSITIOR 6+0,9+0:? CHO$(C1
710 POSITION 3+0,6+0:T CHR$(5+I7);CHR$
(5+I7):POSITION I+0,0+0:T COO$(5+I7);C
HR$(5+37)
720 IF V=1 OUB 0=0 THEN GOSU0 2100:0ET
URN
730 IF V=1 THEO 0RSUB I10R
740 0ETKON
800 0=0:SCOOE=0:GOSUB 650:60SUB 10R0:0
=0+0:6OSU0 660:0RSU0 1000:GOSUB 50R0:P
OSITION 0,1:PORE OL+6,2
610 ? "       TWIST OR STIC6??":GET #1,
```



```
G:IF CHR$(A)="Y" THEN 0=0+6:POKE DL+0,
4:GOSUB 650:GOSUB 1000:GOTO 840
810 IF CH0$(G)="S" THEN GOTO 900
830 POSITION 0,1:GOTO 810
840 POKE DL+6,2:POSITION 0,1:? "
PRESS 00 STICK?":GET #1,G
850 IF CHR$(A)="Y" THEN POKE DL+6,4:0=
0+0:GOSUB 660:GOSUB 1000:GOTO 800
860 IF C0R$(G)="S" T0EN 900
870 GOTO 840
880 POKE DL+6,2:POSITION 0,1:? "
PRESS 00 STICK?":GET 01,A:IF CH0$(A)="
S" T0EN 900
890 IF C00$(G)="Y" T0EN POKE DL+G,4:0=
0+0:GOSUB 650:GOSUB 1000:POSITION 0,1:
? "FIVE CARDS IS Y000 LOT!!":GOTO 89G
891 GOTO 888
895 F00 T=1 TO 400:NEXT T:0FCT=1
900 POKE DL+6,4:POSITION 0,I:? "OKAY,Y
ON STICK ON ";SCORE;"            ";? "C
0MPUTE0S G0!!!          ":POSITION 0,I:
? " "
905 F00 T=1 TO 200:NEXT T:AZ=0
910 POSITION 0,2:? "
                    ":GOTO 2000
999 E00
1000 IF 0=11 00 V=11 00 V=1I THEN V=10
1005 IF V=14 THEN V=11
1010 SCONE=SCONE+V:POSITI0N 0,I:? "SCO
NE=";SCO0E;" MONEY=";MONEY;" 0ET=";0ET
;"      ";IF SCO0E<22 T0E0 NET000
1015 ? "%Y00 0AVE BUSTE0!!"
1010 S0000 0,255,10,1G
1020 ? "MONEY NECREGSE0 BY ";0ET;"!!!!
";? "MONEY=";MONEY:IF MONEY)0 THEN 104
0
1010 F00 T=1 TO 600:NEXT T:? "NNO MONE
 00NEY":T "SUGGEST YOU SEE G LOAN SHAR
K!!!":? :? :SOUND 0,0,0,0:GOTO 1140
1040 F00 T=1 TO 550:NEXT T:SOUN0 0,0,0
,0:0=0:0=0:N=0:SCORE=0:TOTAL=0:FOR T=1
 TO G2:S5(T)=0:CC(T)=0:NENT T
1R50 ? "%    ";? :? :GO500 G50:? :? :G
0500 590:0ET=0:GOTO 000
1100 POSIII00 0,2:? "IS THIS ACE GOING
 IO ME (@)1  (@)11"
1110 P00E DL+7,2:GET #1,0:IF CHR$(A)="
G" THE0 0=1:POKE OL+7,4:POSITI0O 0,I:?
 "                                ":0ETO
00
11I0 IF CRR$(G)="0" THEN P00E DL+7,4:0
=14:POSITI0O 0,2:? "
                ":RETURN
11I0 GOTO 1100
1140 ? "PLAY AGAINIY 00 NI":GET #1,G:I
F CHR$(A)="Y" THEN ? "%OKAY!!":GOTO 11
70
11G0 IF CHR$(A)="N" THEN ? "%GAME E00E
0!!":END
1160 ? "++":GOTO 1140
1170 SOUNO 0,0,0,0:0=0:0=0:N=0:SCORE=0
:TOTAL=0:F00 T=1 TO G2:S5(T)=0:CC(T)=0
:NEXT T:MONEY=10:0ET=0
1100 ? "%  ";? :? :GO500 G50:? :? :GO5
00 G50:GOTO 000
2000 0=0:0=10:GOSUB 050:GO500 I000:0=0
+0:GOSUO 650:GOSUB 3000:IF TOTAL)1G T0
E0 GOTO 5500
I010 0=0+0:GO500 GG0:GOSUB I000:IF TOT
AL)10 THE0 GOTO 5500
I020 0=0+0:GO500 GG0:GO500 I000:IF TOT
AL)10 THE0 GOTO 5500
2030 0=0+0:GOSUB 650:GOSUB I000:FCT=1:
GOTO GG00
I000 IF V=11 00 V=1I 00 V=1I THEN V=10
:REM KINGS AND THINGS!!
I005 IF V=14 THE0 V=11
I010 TOTAL=TOTAL+V:POSITI0O 2,21:? "CO
MPUTE0S SCORE=";TOTOL:IF TOTAL<II T0E0
 FOR T=1 TO I50:NEXT T:0ETURO
I0I0 F00 T=1 TO 190:NEXT T:? "%COMPOIE
0'S 00STE0!"
I0IG ? "MONEY 00S INCREGSE0 0Y ";0ET:?
 "000EY=";MONEY+(2*BET):0ONEY=M00EY+(2
*0ET)
I0I0 S00ND 0,50,10,1G:F00 T=1 TO G00:0
EXT T:0=0:0=0:0=0:G0000 0,0,0,0:F00 T=
1 TO 52:S5(T)=0:CC(T)=0:NEXT T:TOTAL=0
:SC00E=0
I040 ? "%   ":? :? :GOG00 G90:? :? :GO
SUB G90:0ET=0:GOTO 000
I100 IF 0=0 THE0 0=14:RETURN
I110 IF TOTAL+11(SCORE 00 IOTAL+11)21
THE0 V=1:RETURO
I110 V=14:RET000
5000 POSITI0O 1,11:? "WN6T IS THE 0ET?
";:TRAP S000:INPUT NET:T0AP 40000
5001 IF BET()T0T(NET) THE0 GOTO G000
G00G IF BET)MONEY T0E0 SOUNO 0,2GG,10,
1G:? "Y00 0AVE 00T E0OUG0 TO 0ET ";0ET
;"!!":F00 T=1 TO G00:0EXT T
5006 IF 0ET)MONEY T0E0 POSITI00 1,1I:?
 "
";SOUND 0,0,0,0:GOTO G000
G010 IF NET(1 THE0 G0000 0.2GG,10,1G:?
 "CNEGT!!":F00 T=1 TO 200:0EXT T:G0000
 0,0,0,0:POSITI0O 1,1I:? "       "
G01G IF NET(1 THEN GOTO 5000
G0I0 POSITI0O 1,11:? "
                        ":POSITI00 17,I:?
" NET=";NET:MONEY=MONEY-0ET:RETORN
5500 POSITTOX I,I1:? "THE COMPUTE0 STI
CKS 00 ";TOTAL:F00 T=1 TO 190:NEXT T
G510 IF TOTAL=21 000 0=0 THE0 ? "%I HA
VE P00TOO0,00-00!!":GOTO 1010
GG20 IF SCORE=21 000 AZ=0 T0E0 ? "%Y00
 06VE G P00TOON!!0EGTS ME!!":GOTO I0IG
5G30 IF OFCT=1 TRE0 ? "%Y00 0GNE G FIV
E CG00 T0ICK*I L05T.":GOTO 30IG:NE0
5540 IF FCI=1 THE0 ? "%I HAVE G FINE C
AR0 T0ICK-T00G5WE0 Y00!":GOTO 1010
G550 IF SCORE(TOTAL THEN ? "%I GN JUST
 TOO G00D F00 Y00!!YOO LOST!":GOTO 101
0
55G0 IF TOTGL(SCORE THE0 ? "%Y00'VE BE
0TEN ME,I TRI0K YOU C0EGTE0!":GOTO I0I
G
5570 IF SCORE=TOTGL T0E0 ? "%A 0RG0!!0
UT THE 0EGLE0 ALWAYS WI05!!":GOTO 1010
55G0 ? "0N 0E00 TNE0E'S 00 E0000":STAP
```


Tired of typing?
Take advantage of our finger-saving offer on Page 61

Keeping track of the memory situation

UPDATE

SINCE writing RAW, the 6502 assembler which appeared in the August issue of *Atari User*, I've made a few modifications which greatly improve its performance.

An extra variable has been added, *SHOW*. This indicates whether a listing is required. If *SHOW* is zero then nothing is printed on the screen. If it is not zero then a listing is given.

When the listing is disabled it assembles the code 25 per cent faster. Place it at the start of the assembly listing like this:

```
10 SHOW=0
```

The other major change is that it no longer uses any of page 6 for its workspace. This leaves an extra 55 bytes free for your own routines. The machine code subroutine it uses is placed in a string and the start of the string is called.

To convert the assembler, load it and enter Listing I then save the modified form.

```
0017 ? "Assembling..."
5030 REM Deleted
0090 IF SHOW THEN POKE 85,20:? A$:X=IN
T(P/256):GOSUB 6500:O=P-256*X:GOSUB 65
00:? ":";
0110 IF A$="END" THEN ? :GOTO 5400
5410 ? "Start=";START;"  Length=";P-ST
ART;"  End=";P-1
0130 X=USR(ADR(CODE$),ADR(T$),ADR(L$))
6500 IF  NOT SHOW THEN RETURN
7190 BYTE=USR(ADR(CODE$),ADR(A$),ADR(M
$))
7320 GOSUB 6810
7330 IF X=3 THEN BYTE2=INT(X/256):BYTE
1=X-256*BYTE2:X=BYTE1:GOSUB 6500:X=BYT
E2:GOSUB 6500:RETURN
9010 DIM A$(15),T$(5),H$(10),L$(1024),
O(255),Z(3),CODE$(60)
9080 RESTORE 9090:FOR I=0 TO 54:READ J
:POKE ADR(CODE$)+I,J:NEXT I
```

Listing I

ROLAND WADDILOVE presents a hexadecimal/Ascii memory dump utility

REGULAR readers of *Atari User* should by now have quite a powerful toolkit consisting of an assembler, disassembler and data maker. To complement these, here is a hexadecimal/Ascii memory dump utility written entirely in machine code.

Although memory dump utilities are fairly common, this little routine is far from standard. The program is written in machine code and resides in page 6. This area of memory is not used by Basic or the operating system, so is free for utilities such as this.

The machine code is unaffected by LOAD, SAVE or NEW. This makes it possible to run Basic programs at the same time and examine how they are stored in the memory. The operating system can be examined and the system variables can also be monitored.

The routine displays 192 memory locations on a Graphics 0 screen in both hexadecimal and Ascii. When it has completed this task it goes back and displays the same 192 locations again. This is repeated until one of the cursor keys is pressed.

You might imagine that printing 192 memory locations in hex and Ascii would take a long time. However, remember that this is machine code. The routine updates the screen 30 or 40 times a second.

The advantage of constantly displaying the same area of memory over and over again is that locations that change are instantly updated and can be seen quite easily. The system clock, for instance, can be seen rapidly ticking away in page zero.

To monitor any section of memory enter:

```
X=USR(1536,n)
```

where *n* is the address from which to start displaying. To return to Basic press the space bar.

Pressing the cursor up key will increment the start address by 8 and the display scrolls up. Cursor down decrements the start address by 8, scrolling the screen down. The screen continues scrolling until any other key is pressed. Return is the most

```
10 REM Memory Monitor
20 REM By R.A.Waddilove
30 REM (c) Atari User
40 REM X=USR(1536,n)
50 FOR I=0 TO 235
60 READ J:POKE 1536+I,J
70 NEXT I
600 DATA 104,201,1,240,1,96,160,89,72,
169,0,168,102,A,140,00,136,208,251,230
610 DATA 89,202,208,246,104,133,89,104
,133,213,104,133,212,165,88,141,226,6,
141,202
520 DATA 6,165,89,141,229,6,141,203,6,
100,212,141,68,6,165,213,141,89,6,169
530 DATA 24,133,214,169,1,133,216,169,
31,133,216,173,89,0,32,267,6,173,00,0
540 DATA 32,207,6,230,216,162,0,109,21
```

Program I

convenient key to stop.

The scrolling is very fast. The routine takes about three seconds to whizz through 1k of memory, so it's very easy to move beckwards or forwards through RAM or ROM.

There's quite a lot to be learned by scanning the memory using the monitor. Try looking at page 0 first. The clock can be seen ticking away at $12-$14. Every time $14 reaches 0 $4E is incremented. Press a key and $4E is reset to zero.

Page 1 is the 6502 stack. This can be seen to be flashing quite rapidly as data is pushed on and pulled off.

$22B is interesting. When a key is pressed the delay before auto repeat comes into operation is placed here. This counts down to zero, and if the key is still being pressed the auto repeat delay is placed here. Again this counts down to zero.

The Basic line buffer is around $580. You can see here what you've just typed in.

Basic programs are stored at around $1F30 on my Atari 800 XL with disc drive. It may be different on other Ataris.

If you went to use RAW to enter the assembly listing you'll need to use the modified version. An alternative is to assemble the routine at a different memory location.

The routine is quite complicated and needs entering with care. Program I will poke the data into page 6 and set up the routine. Program II is an assembly listing for anyone with an assembler

> **"The golden rule of machine code programming – always save it twice before running it until you know it's bug-free"**

Remember the golden rule of machine code programming – always save it twice before running it until you know it's bug-free. After setting up the routine you can type NEW and load a Basic program.

```
0,4,32,191,6,230,216,232,224,8,208,243
550 DATA 24,173,88,6,105,8,141,88,6,17
3,89,6,105,0,141,89,6,24,173,228
560 DATA 6,105,40,141,228,6,141,202,6,
173,229,6,105,0,141,229,6,141,203,6
570 DATA 198,214,208,175,173,252,2,201
,14,208,16,24,165,212,105,8,133,212,16
5,213
580 DATA 105,0,133,213,76,33,6,201,15,
208,15,165,212,233,8,133,212,165,213,2
33
590 DATA 0,133,213,76,33,6,201,33,208,
249,96,72,201,96,176,3,88,233,32,104
600 DATA 216,153,218,4,230,216,104,72,
74,74,74,74,32,216,6,104,164,216,41,15
610 DATA 248,24,105,144,105,32,216,153
,218,4,230,216,96,0,0,0,0,0,0,0
```

```
1 SROW=0
10 DATA ORA $600
20 REM
30 DATA .mal=$D4,.mah=$D5
32 DATA .line=$DA
33 DATA .pp1=$D7
34 DATA .pp2=$DD
40 DATA .add1=$65A,.addh=$A59
50 DATA .chr1=$6CA,.chrh=$ACD
60 DATA .p1=$6E4,.ph=$6E5
65 REM
70 DATA PLA,CMP #1,BEA ok,RTS
73 DATA .ok,LDA D9,PRA
78 DATA LDA #8,TAY,LDX #4
77 DATA .wipe,STA (88).Y,DEY,BNE wipe
80 DATA IRC D9,DEX,BNE wipe
83 DATA PLD,STA 89
100 DATA PLA,STA mah,PLA,STA mal
105 DATA .strt
110 DATA LDA AA,STA p1,STA chr1
120 DATA LDA A9,STA ph,STA chrh
130 DATA LDA mal,STA add1
140 DATA LDA mah,STA addh
150 DATA LDA #14,STA line
160 DATA .here
165 DATA LDA R1,STA PP2,LAA #31,STA PP
1
170 DATA LDA addh,JSR prnt
180 DATA LDA add1,JSR prnt
192 DATA IRC pp2
190 DATA LDX #8
200 DATA .loop
210 DATA LDA 1234.X,JSR prin
215 DATA INC pp2
220 DATA INX,CPX #8,BNE loop
225 DATA CLC
230 DATA LDA add1,ADC #8,STA add1
240 DATA LDA addh,ADC #8,STA addh
244 DATA CLC,LDA p1,ADC #40,STA p1,STA
 chr1
246 DATA LDA ph,ADC #8,STA ph,STA chrh
250 DATA DEC line,BNE here
260 DATA LDA 764,CMP #14,BNE k1
290 DATA CLC,LDA mal,ADC #8,STA mal
300 DATA LDA mah,ADC #8,STA mah
310 DATA JMP strt
320 DATA .k1
330 DATA CMP #15,ADE k2
340 DATA LDA mal,SBC #8,STA mal
350 DATA LDA mah,SBC #8,STA mah
355 DATA .k3
360 DATA JMP strt
370 DATA .k2
380 DATA CMP #33,ANE k3,RTS
390 REM
400 DATA .prin
401 DATA PHA
402 DATA CMP #9A,BCS ok1,SEC,SBC #32
404 DATA .ok1,LDY pp1,STA 1234.Y,IRC p
p1,PLA
410 DATA .prnt
419 DATA PHA
420 DATA LSR A,LSR A,LSR A,LSR A
430 DATA JSA pr
440 DATA PLA
450 DATA .pr
455 DATA LDY pp2
460 DATA AND #$0F
470 DATA SEA,CLC,ADC #$30,ADC #$20,CLD
490 DATA STA 1234.Y
495 DATA INC pp2
500 DATA RTS
590 REM
600 DATA END
```

Tired of typing?
Take advantage of our finger-saving offer on Page 61.

Program II

THE NEW

ATARI 520ST NOW AVAILABLE!

Now In Stock!

only £749.99

THE ATARI 520ST

COMPUTER SYSTEM
COMES COMPLETE WITH
3½" 500K DISK DRIVE
HI-RES MONOCHROME MONITOR
MOUSE, TOS, LOGO
BASIC, GEM WRITE GEM PAINT
GEM DESK TOP, DEMO

DISKS

3½" SS/DD £4.60
3½" DS/DD £6.95
3½" HEADCLEANER £14.95
ALL MAKES IN STOCK

SOFTWARE

HABA CHEQUE KEEPER
Personnel Finance Program
HABA COM
Communication Software
HABA HIPPO 'C'
Powerful 'C' Language
HABA CALC
&
HABA WORD
Coming Soon
Call for more Software

520ST LEADS

520ST to Centronics Printer £24.99

MIDI to MIDI LEADS £19.95

MOUSE EXTENSION LEADS £14.99

520ST to MODEM LEAD £19.95

TO ORDER YOUR 520ST WRITE OR PHONE TO

SOFTWARE EXPRESS INTERNATIONAL
31 STONEYHURST ROAD, ERDINGTON, BIRMINGHAM
TELEPHONE (021) 384 5080

TELEPHONE ORDERS NOW BEING TAKEN

'ST' HOTLINE (021) 384 5080

PLEASE NOTE ALL ORDERS TAKEN WITH EITHER FULL PAYMENT OR DEPOSIT WILL **NOT** BE CLEARED UNTIL YOUR ORDER IS READY TO BE DESPATCHED

ATARI IS THE REG. TRADEMARK OF ATARI CORP. LTD
ALL IMFORMATION CORRECT AT TIME OF GOING TO PRESS

MicroLink

What it offers

Give your micro mainframe power

With MicroLink your micro becomes a terminal linked directly to the Telecom Gold mainframe computer, and able to tap its tremendous power and versatility. Right away you'll be able to use giant number crunching programs that can only run on a mainframe. You can set up your own computerised filing systems, store and update statistics and other information, cross reference material between files, selectively extract the information you want, perform massive calculations and design reports to display information from any of the files and in any format you choose.

The biggest bulletin board of them all

The number of bulletin boards is growing rapidly. New ones are springing up in all parts of Britain and all over the world, with people of like minds chatting to each other on all manner of subjects. The only snag is that the vast majority are single-user boards – which means lots of other people are also trying to make contact and all too often all you get is the engaged tone. But with the MicroLink bulletin board there is no limit to the number of people using it at the same time. And no limit to the number of categories that can be displayed on the board.

We're only a local phone call away

More than 96 per cent of MicoLink subscribers can connect to our mainframe computer in London by making a local phone call. This is possible because they use British Telecom's PSS system, which has access points all over Britain. A local phone call is all you need, too, for access to the international Dialcom system through MicroLink.

Telemessages – at a third of the cost

The modern equivalent of the telegram is the telemessage, which if sent before 8pm is delivered by first post the following day (except Sunday). Originally designed for people to phone their message via the operator, the service costs £3.50 for 50 words. Now it's available via MicroLink – and costs only £1.25 for up to 350 words!

Send and receive telex messages

With MicroLink you can turn your micro into a telex machine, and can send and receive telex messages of any length. You will be able to communicate directly to 96,000 telex subscribers in the UK, 1½ million worldwide – and even with ships at sea via the telex satellite network. Business people can now send and receive telexes after office hours, from home or when travelling. You can key in a telex during the day and instruct MicroLink not to transmit it until after 8pm – and save 10 per cent off the cost!

The mailbox that is always open

MicroLink is in operation 24 hours a day, every day. That means you can access your mailbox whenever you want, and from wherever you are – home, office, airport – even a hotel bedroom or golf club! No one needs to know where you are when you send your message.

What does it all cost?

Considering all the services you have on tap, MicroLink is remarkably inexpensive. You pay a once only registration fee of £5, and then a standing charge of just £3 a month. On line costs are 3.5p a minute (between 7pm and 8am) or 10.5p a minute during office hours. There is an additional 2p a minute PSS charge if you are calling from outside the 01- London call area. Charges for telex, tele-messages and storage of files are given on the next page.

How much it costs to use MicroLink

Initial registration fee: £5

Standing charge: £3 per calendar month or part

Connect charge: 3 5p per minute or part – cheap rate, 10 5p per minute or part – standard rate

Applicable for duration of connection to the Service
Minimum charge 1 minute
Cheap rate is from 7pm to 8am, Monday to Friday all day Saturday and Sunday and public holidays. Standard rate is from 8am to 7pm, Monday to Friday excluding public holidays

Filing charge: 20p per unit of 2,048 characters per month.

Applicable for storage of information, such a telex short codes and mail files. The number of units used is an average calculated by reference to a daily sample

Information Databases: Various charges.

Any charges that may be applicable are shown to you before you obtain access to the database

MicroLink PSS service: 2p per minute or part (300 baud), 2 5p per minute or part (1200/75 baud)

Only applies to users outside the 01 London call area.

Telex registration: £10.

Outgoing telex: 5.5p per 100 characters (UK); 11p per 100 (Europe); 16.5p per 100 (N. America); £1 15 per 400 (Rest of world); £2 75 per 400 (Ships at sea)

Deferred messages sent on the night service are subject to a 10 per cent discount

Incoming telex: 50p for each correctly addressed telex delivered to your mailbox. Obtaining a mailbox reference from the sender incurs a further charge of 50p

It is not possible to deliver a telex without a mailbox reference. If a telex is received without a mailbox reference the sender will be advised of non delivery and asked to provide a mailbox address.
Each user validated for telex and using the facility will incur a charge of 6 storage units a month. Further storage charges could be incurred depending on the amount of telex storage and the use made of short code and message file facilities.

Telemessages: £1 25 for up to 350 words

Radiopaging: No charge.

If you have a BT Radiopager you can be paged automatically whenever a message is waiting in your mailbox.

International Mail: For the first 2,048 characters – 20p to Germany and Denmark, 30p to USA, Australia, Canada, Singapore, Hong Kong and Israel. For additional 1,024 characters – 10p, 15p.

These charges relate to the transmission of information by the Dialcom service to other Dialcom services outside the UK and the Isle of Man. Multiple copies to addresses on the same system host incur only one transmission charge

Billing and Payment: All charges quoted are exclusive of VAT. Currently all bills are rendered monthly

Software over the telephone

MicroLink is setting up a central store of software programs which you'll be able to download directly into your micro. The range will include games, utilities, educational and business programs, and will cover all the most popular makes of micros

Talk to the world – by satellite

MicroLink is part of the International Dialcom network. In the USA, Australia and a growing number of other countries there are many thousands of users with electronic mailboxes just like yours. You can contact them just as easily as you do users in Britain – the only difference is that the messages from your keyboard go speeding around the world via satellite

What you need to access MicroLink

You must have three things in order to use MicroLink: a computer (it can be any make of micro, hand held device or even an electronic typewriter provided it has communications facilities), a modem (it can be a simple Prestel type using 1200/75 baud, or a more sophisticated one operating at 300/300 or 1200/1200 baud), and appropriate communications software

MicroLink

in association with

TELECOM GOLD*

Application Form

AT 10

I/We hereby apply to join MicroLink

(✓) ☐ I enclose my cheque for £5 payable to Database Publications as registration fee to MicroLink.

(✓) ☐ I also wish to use Telex. I authorise you to charge an additional £10 to my initial bill for validation.

☐ I confirm that I am over 18 years of age

Signature _____

Date _____

I intend to use the following computer _____

FOR OFFICE USE ONLY:

Mailbox assigned _____

Start date _____

Password _____

SEND TO:
MicroLink
Database Publications
Europa House
68 Chester Road
Hazel Grove
Stockport SK7 5NY.

Name

Position

Company

Address

Postcode

Daytime telephone

Commencement of Service
Please indicate month of commencement ☐☐ 19 ☐☐
Allow 10 days for validation of mailbox

Payment
Whilst Database Publications Ltd is the supplier of all the services to you, the commission and billing thereof will be handled by Telecom Gold as agents for Database Publications Ltd
Date of first payment to be on 15th of month following commencement
Please complete billing authorisation form A, B or C below

A. Direct Debiting Mandate *(Enter full postal address of Bank Branch)*
To

I/We authorise you until further notice in writing to charge to my/our account with you on or immediately after 15th day of each month unspecified amounts which may be debited thereto at the instance of British Telecommunications plc – TELECOM GOLD by Direct Debit. Bills are issued 10 days before debit is processed

Name of Account to be debited

Account Number

B Please debit my/our Access/Visa account number

I/We authorise you until further notice in writing to charge to my/our account with you on or immediately after 15th day of each month unspecified amounts which may be debited thereto at the instance of British Telecommunications plc – TELECOM GOLD. Bills are issued 10 days before charge is applied to your account.

C Please invoice the company/authority

(✓) ☐ If you select this option, which is ONLY AVAILABLE to government establishments and public limited companies, you will be sent an authorisation form for completion which will require an official order number to accept unspecified amounts.

* *Telecom Gold is a trademark of British Telecommunications plc.*

Mode 8 offers superb detail, but it really is a right little memory muncher

THIS month we're going to look at Mode 8, which has the highest resolution of all the modes. In its full-screen form, Mode 8 offers 192 rows x 320 columns – or, to put it another way, 61440 pixels.

With this many pixels, we can't "afford" any memory to hold colour information, so we can only display a single colour, although the border and background can be different colours

Plotted points are the same colour as the background, but we can set the luminence of the plotted points – just as well really, otherwise we'd never see them . . .

Colour register 2 controls the colour and luminance of the background. Type GR.8 to get to an empty Mode 8 screen. It looks like a regular Mode 0 screen but the word Ready is positioned close to the bottom. Now enter:

SETCOLOR 2,4,6

and the screen will turn purple.

To demonstrate that you *do* have Mode 8 and not Mode 0, press Return three times. All text has now disappeared out of the text window, leaving only the cursor on the bottom line.

The colour and luminance of the border are controlled by register 4. We can demonstrate this by entering:

SETCOLOR 4,8,2

which should yield a blue – colour 8 – border with luminance value of 2 around the purple screan.

If we want to plot to the screen, we still need to precede the PLOT command with a COLOR 1 command. In Mode 8 this gives the same colour as the background but takes the luminance from colour register 1.

Try entering:

COLOR 1: PLOT 20,20: DRAWTO 100,100

This should produce a thin sloping line which is a bit faint and therefore difficult to see.

To improve visibility, we need to make the line's luminence either much lighter or much darker. That is, we need to increase the contrast between the line and the background.

The luminance of plotted points is taken from the information in register 1, so to get a darker line we can either:

SETCOLOR 1,1,2

and to get a lighter line we can enter:

SETCOLOR 1,1,14

Notice that the text in the text window is the same luminance as the plotted points. It goes dark and light as the line goes dark and light

You'll remember that the second parameter in the SETCOLOR command specifies the colour to be used. However in Mode 8 the colour specified in register 1 is ignored. Only the luminance parameter is used.

This means that you can use any number. Try:

SETCOLOR 1,12,14

and you shouldn't see any difference. Hence, I tend to use a 1 as the colour parameter because my fingers are already at the 1 key in order to specify the register. Lazy, aren't I?

```
10 GRAPHICS 8
20 SETCOLOR 2,0,0
30 COLOR 1
40 FOR A=100 TO 200 STEP 2
50 FOR B=0 TO 100 STEP 2
50 PLOT 0,0
70 PLOT A+1,B+1
80 NEXT B:NEXT A
```

Program I

The COLOR 2 command has the same hue and luminance as the background so it can be used to erase a section of the display as we saw last month.

For example, enter:

COLOR 2: PLOT 20,20: DRAWTO 50,50

and you should see the upper section of the line disappear.

Mode 8 has at least one interesting effect that you might not predict and we can demonstrate it with the aid of Program I. Enter the listing and then Run it.

This simple program does nothing

→

Part Six of DAVE RUSSELL's Atari graphics modes series

Keep telling yourself that 8 is a single colour mode

more than draw a series of vertical lines. However, you should see an effect which you might not expect to see in a single-colour mode.

In fact, it is a well-documented effect called "artifacting" and is a result of the way in which televisions handle colour.

You may have noticed the effect if you entered the Mandala program from the Microscope article in the August issue of *Atari User* since it used Mode 8 to draw the patterns. You can experiment with it by inserting a line 25 to alter registers 1 and 2.

The effect can be even more dramatic on an American television because of the different system used to produce a coloured image.

```
10 GRAPHICS 8+16
20 SETCOLOR 1,1,14:SETCOLOR 2,0,0
30 FOR X=0 TO 310 STEP 3
40 COLOR 1:PLOT 159,0:DRAWTO 0,191
60 COLOR 0:PLOT 159,0:DRAWTO 0+1,191
60 NEXT 0
70 GOTO 70
```

Program II

Program II gives one of the best demonstrations of the effect I've seen on a UK set, but I can't take any credit because it was written by Judson Pewther for Compute! magazine. While you're looking at it, keep telling yourself that Mode 8 is a single colour mode . . .

Incidentally, line 70 may confuse you if you've not used a full-screen mode before.

Normally, Mode 8 has a Mode 0 text window at the bottom. For any of the split-screen modes we can display a full screen by adding 16 to the GRAPHICS statement, as in line 10. This could have been written as GR.24 with the same result.

The problem with removing the text window in this way is that the system will revert to Mode 0 when the program finishes. You can see the effect by typing GR 24 when you're in Mode 0. The screen flashes as Mode 8 is displayed, but then you're back in Mode 0.

All line 70 does, then, is stop the program from ending by creating an endless loop. Press Break or Reset to get out of the loop.

Mode 8 has another characteristic which can also be used to advantage.

As a map mode, writing text is not all that easy. However, by one of those happy accidents that occur now and then, the pixel size in Mode 8 just happens to be the same as in Mode 0.

You can't "write" direct to the Mode 8 screen as you can in Mode 0, but all the data required to generate the Mode 0 characters are held in ROM.

If you've been following this series you'll remember that in the July issue we copied the data down into RAM in order to redefine some of it.

Program III uses this fact in order to put Mode 0 characters on a Mode 8 screen.

It does this by converting each character in STRING$ into internal code, finding that character in the ROM character set and then poking the data for that character directly into the screen area of RAM.

In fact, if you run Program III as listed, it suffers from exactly the problem that we discussed in July's article. We could combine the redefining program from July with Program III, but as a temporary "kludge" try adding line 145 as follows:

145 IF X=64 THEN POKE LOC+BYTE*40,0:GOTO 160

Dave Russell doesn't just *talk* about bad programming – he shows you how to do it . . .

This technique of writing the Mode 0 character data to the screen will only work with Mode 8 because the two modes have the same pixel size. However, if you're adventurous you might like to devise ways of writing text to other map modes.

After all, the data for 8×8 matrix characters are already in ROM and it seems a shame to waste them. Maybe there's a way of using them in a modified form for other modes. If you find a way, I'm sure the folks at *Atari User* would love to hear from you.

Mode 8, then, offers you the best possible resolution of your Atari modes at the cost of about 8k of RAM memory. Therefore, applications that use it will be those which need the resolution for fine drawing but don't need a lot of memory for calculations.

If you think this is an unlikely combination, look back at Ken Ward's Tablet-8 program in the August issue of *Atari User*. It's a fine example of just such an application.

```
10 REM MANDALA
20 GRAPHICS 8+16
30 COLOR 1:PLOT 150,90
40 FOR X=0 TO 100 STEP INT(RND(0)*10+1
)
50 DRAWTO 150,190-X
60 DRAWTO 150-X,100
70 DRAWTO 150,X
80 DRAWTO 150+X,100
90 NEXT X
100 FOR DELAY=1 TO 750:NEXT DELAY
110 RUN
```

The Mandala program illustrates the artifacting effect

```
10 DIM STRING$(10),B$(1)
20 STRING$="ATARI USER"
30 B=15:Y=BR
40 GRAPHICS 8
50 SCREEN=PEEK(88)+256*PEEK(89)
60 LOC=SCREEN+Y*40+B
70 FOR CHAR=1 TO LEN(STRING$)
80 X$=STRING$(CHAR,CHAR)
90 B=ASC(X$)
100 IF B>127 THEN X=B-128
110 IF B>31 AND B<96 THEN X=X-32
120 IF B<32 THEN X=X+64
130 CHARLOC=57344+X*8
140 FOR BYTE=0 TO 7
150 POKE LOC+BYTE*40,PEEK(CHARLOC+BYTE
)
160 NEXT BYTE
170 LOC=LOC+1
180 NEXT CHAR
```

Program III

Odds-on favourite?

JUST opposite the factory where I served my apprenticeship were two of the three "hallowed halls" Right next door to the pub was the betting shop, and many a lunch hour was spent sliding between the two.

I was never wildly successful as you can tell from the fact that I'm writing this review from sunny Stockport and not my yacht on the Med.

Of course, the rigours of mortgages put paid to my gambling career so I was filled with nostalgia when **A Day At The Races** arrived from Anvil Software.

The game allows up to five punters to place bets on horses which then race from one side of the screen to the other.

Although that may not seem very far, the animation is such that each race takes about 90 seconds with the horses appearing to have galloped all the way.

There are 10 races on each day's card For each race the program randomly picks five horses from its database and gives the starting prices

The odds are the only indication of form that you have, although the instruction sheet advises you to "pay careful attention to the race results to pick up hints and clues that might be useful to your future forecasts"

Once you've placed your bets, the race starts and you can do nothing more than watch Well, that's not quite true because, like in the real thing, you can jump up and down shouting 'come on', groan, and generally get involved.

Another realistic element is the fact that you can't get credit When your money runs out, you just have to sit and watch

A Day At The Races costs £7 99 for the cassette version and only £1 more for the disc version. I wish more software houses had a similar small difference between the two prices



Although you could play the game on your own, I'd recommend getting a few crates of brown ale in – purely to sit on, of course – inviting a few mates round and having a bit of fun.

Cliff McKnight

IT'S A SHOOT-EM-UP HUMDINGER

HOT from the good ol' USA comes **Reecue On Fractalue,** a superb new space shoot-em-up from Epyx and Lucasfilm Games

The game has long been awaited – in its early form it was called Behind Jaggi Lines – but had been held up for release owing to legal problems

Since I had heard many superlatives being bandied around about its quality, I was anxious to secure a copy as soon as it became available.

Thanks to the fast and efficient services of Software Express of Birmingham a review copy thudded on to my doormat within hours of the game's release for the UK Rumours of its excellence are well-founded – Fractalus is a humdinger.

The Jaggies, with whom you are at galactic war, have dug themselves in on an inhospitable planet called Fractalus. The war is not going well for you. Many of your Ethercorps pilots, including some ace officers, have found Fractalus a little beyond their capabilities and have crashed on to the planet

You can't blame them The terrain on Fractalus consists of wild, rugged mountains craggy peaks and ridges, and deep canyons The atmosphere is no less harsh – thick cyanitric acid which will dissolve a standard issue flight suit within minutes

And as if that weren't enough, Fractalus rotates so fast that daylight only lasts for nine minutes. Barely worth getting the deck-chairs out

Your mission is to rescue as many of your stranded colleagues as possible As long as they stay inside their marooned single-manned fighters, they are safe Once they venture out into the atmosphere they have only seconds to live

The game begins with a breathtaking title screen of your mothership, one of the most impressive introductory screens I have ever seen

Incidentelly, there is a Commodore 64 version of the game available with a different title screen The Atari screen leaves the Commodore version standing, thus confirming what we always knew about Atari software – only the best for the best!

You start inside your fighter, aboard the mothership The display shows the forward view through the main window of your cockpit and

below it e detailed instrument panel.

The panel gives helpful visual and aural information and warnings on such things as compass bearing, wingtip clearance from solid rock – handy for canyon flying – attitude, thrust, artificial horizon, energy, shield and air lock activation, range to stranded pilot, number of enemies destroyed and number of pilots you are expected to rescue and have actually rescued.

There's more. An altimeter shows both the altitude of the terrain and your altitude above it. A long range scanner will pick up a pilot's emergency beacon and display its position.

An enemy lock-on indicator lets you know how near you are to getting blasted by alien fire while a targetting scope helps you to draw an accurate bead on enemies and downed pilots.

This whole array appears daunting at first but it is very clearly and neatly set out and turns out to be quite simple to assimilate and interpret.

So much for the technical stuff, now to the action. Under automatic control, your ship is hurled along a tunnel at hyperspeed and descends towards Fractalus. From then on, you're in control.

Through your cockpit window you'll see a bright yellow heaven (must be all that cyanitric acid) and a skyline of ominous brown crags.

Controlling your ship is mainly a matter of joystick movement, while increases and decreases in speed are handled by the left and right arrow keys.

Any Jaggi gun emplacement shows up as a small green dome on top of a peak, firing bursts of green rays at you. You can take evasive action or try to knock it out.

A cross-hair sight will be overlaid on the scene whenever the enemy is near. To blow a Jaggi stronghold off the mountain, you must line up the cross-hair and fire one of your torpedoes.

A standard pilot is shown as a flashing green beacon on the surface of Fractalus. Watch for a blip on your long range scanner and fly low towards the pilot. Once near enough, you have to land your craft by pressing L. When down, pressing S turns your systems off and you will be told whether or not you are close enough to rescue the pilot.

If you are not, you'll just have to take off again and land a bit closer. When you're near enough, you'll see the pilot leave his ship and toddle towards you. When you hear him knocking on the door, you must open the airlock – press A – and you'll be rewarded by the sound of him stumping up the stairs.

Should you be in a malicious mood, try leaving the pilot outside. He'll start to knock more urgently, then more weakly until at last you hear him topple over. The cyanitric air has got him, you rotter!

From time to time, a beeping sound will alert you to the presence of the mothership. Pressing B fires your boosters and returns you there where you'll receive replenishment and, if you've rescued your quota of pilots, move to the next level.

When you begin a game, you can elect to start at any of 16 levels, although the game progresses way beyond these. When you complete a level, you continue at the next higher one but if you're really feeling tough or want more bonus points you can skip up to three levels at a time.

Levels 1 to 3 are for training – no sign of the Jaggies on level 1 and just a handful on levels 2 and 3. On levels 4 and above, the Jeggies are more numerous, pugnacious and accurate, and are joined by kamikaze flying saucers.

Level 16 has the Fractalus nine-minute day coming into play so prepare for some night flying. You won't see anything out of the window and must use just your instruments and nerves.

A demo mode is provided and there are some other interesting little wrinkles to the game, including one where you inadvertently pick up an alien instead of a pilot. I'll leave the pleasure of discovering these to you.

Sound effects, including the stirring theme tune, are first rate. The graphics are clean and clear and although the solid mountainous terrain is all coloured the same (brown with black ridges), the exceptionally fast, multidirectional scrolling more than compensates.

Rescue On Fractalus with its mixture of simulation and arcade elements is a top-notch game, packed with action and excitement. It will hook you from the word go and keep you coming back for more. Cost of the disc is £34.95.

Bob Chappell

Get down to the bare essentials

I'M sitting here shivering in my underwear while the young lady opposite grins smugly at me. Just a minute while I switch her off.

There, now I can concentrate. I've just been playing **Strip Poker,** the latest import from US Gold, and I'm not doing too well this time.

The program is a conversion from the Artworx classic which I first encountered on the Apple II a couple of years ago.

You have a choice of two opponents, Melissa or Suzi. On the cassette version, one is on each side of the tape. Since the loading time is about 15 minutes, I tended not to switch from one opponent to the other.

The two girls play different strategies and I'm not going to spoil your fun by revealing their styles. Both play a good game of Poker.

Although the graphics are good, only a real wierdo would buy the package to see naked ladies. Having managed to strip both opponents, I have to say that the magazines next to the computer mags in the average newsagent's leave less to the imagination.

The cassette will only run on a 64k machine and costs £9.95. It will not work on an Atari 400 or old series 800. The loading instructions tell you to press Start while you switch on, but in fact XL owners will need to press Start and Option. The disc version costs £14.95.

Otherwise the instructions are clear and the terminology used and relative values of the hands are explained adequately.

Ultimately, it's the quality of the game played that determines the value of a program. In this respect, I can recommend the game.

As far as I can tell it doesn't cheat, although you can cheat by not removing your clothes when you lose. But you wouldn't do that, would you?

Pat Cookson

ZOOMSOFT

HOMEWORD

The personal WORD PROCESSOR 1984 outstanding software AWARD

5imple versetile effective. HOMEWORD is a writing tool designed for the home. It offers the power of a sophisticated word processor without the complications. Use HOMEWORD to write school assignments, shopping lists, letters, business memos and reports. HOMEWORD mekes putting your idees on paper e snap.

An easy to follow audio cassette will introduce you to HOMEWORD and take you step by step through its operation No complicated commands to memorise. so anyone in your family cen leern to use HOMEWORD in a matter of minutes. The menu features ICONS (pictures).

These ICONS make HOMEWORD a joy to use.

Other features include MOVE TEXT/ COPY TEXT/ ERASE TEXT/ INSERT ERA5ED TEXT/ FIND/ FIND and REPLACE/ INSERT DOCUMENT/ INCLUDE DOCUMENT/ UNDERLINE TEXT and JU5TIFICATION. A full 80 characters per line enables you to view your documents as they will appear in printed format. Use with any printer. Meny other fine feetures meke HOMEWORD e great WORD PROCESSOR

DISK £48.95

M.M.G. BASIC COMPILER	**£59.95**

ARCADE

BOULDER DASH *C/D*	**14.95**
OIL'S WELL *CART*	**14.95**
BC'S OUEST *CART*	**14.95**
MR ROBOT *DISK*	**14.95**
MINER 2049er *CART*	**9.95**
SUBLOGIC	
Flight Simulator II	**48.95**

WE'LL INCREASE YOUR STORAGE AND TRIPLE YOUR SPEED!

Introducing the U5 DOUBLER. US DOUBLER increases your storege to 1BDK, and is totally compatible with other double-density disks, all DOS for ATARI, end all ATARI 105D disk drives.

New SPARTA DO5 CONSTRUCTION 5ET will triple your speed.True double-density. ATARI 105D (one and e half times density) and single density. Time/ Day/ Date on your files Ram Disk for XE models.

FREE SPARTA DO5 CONSTRUCTION 5ET when you buy the US DOUBLER!

e herdware/software combination, installation required, complete instructions provided.

£79.95

THE ULTIMATE WAR GAME SIMULATIONS!

STRATEGIC SIMULATIONS

Galactic Adventures	**£62.35**
Broadsides	**£41.65**
Eagles	**£41.65**
Field of Fire	**£41.65**
Objective Kursk	**£41.65**
50 Mission Crush	**£41.65**
Coloniel Conquest	**£41.65**
Computer Quarterbeck	**£41.65**
Gemstone Warrior	**£41.65**
5ix Gun Shootout	**£41.65**
Rails West	**£41.65**
The Cosmic Balance	**£41.65**
Cosmic Belance II	**£41.65**
B/through in Ardennes	**£62.35**
Operation Market Garden	**£62.35**
Carrier Force	**£62.35**
Kampfgruppe	**£62.35**
Reforger BB	**£62.35**
Computer Ambush	**£62.35**
War in Russia	**£62.35**

MAGNIPRINTII

THE ULTIMATE GRAPHICS PRINTING PACKAGE

Print your ATARI graphics like you've never seen before! MAGNIPRINT II is the most powerful print utility available for your computer. It is the only software that can accurately print GTIA modes with 16 shades. Prints ell graphic modes. Can blow up your pictures to wall sized posters. Speciel option lets you centre the picture on the page. Accepts your own graphic creations or those created with MICROPAINTER, FUN with ART, PAINT, SUPER SKETCH, ATARI TOUCH TABLET, KOALA PAD, ATARI LIGHT PEN GRAPHIC5, B/GRAPH, GRAPHIC5 MAGICIAN, and many others. Includes many beautiful sample pictures. Add text to your pictures. Allows you to print the whole screen or any selected portion of the screen.

FREE with every MAGNIPRINT II PRINTALL. PRINTALL prints your programs end files just as they appear on your screen. It clearly prints all ATARI graphic cheracters including INVER5E characters. This alone is worth the price.

Disk £25.95

SEE YOUR LOCAL DEALER *NOW!*

TRADE ENQUIRIES
Tel: 01-482 1755

All products are available from:

SILICA SHOP 01-309 1111, SOFTWARE EXPRESS 021-384 5080, SILICON CHIP 0753 70639, A.S. WOTTON & SONS 0270 214118, PEATS ELECTRONICS IRELAND 01-749972/3/4, RADFORD HI-FI Ltd. 0272 428247 MICROBYTE 051-630 6933, THE AMV SHOP SUNARO SOFTWARE and other good computer shops.

If you have problems in obtaining any of these products then you can order direct. All cheques/P.O.s should be made payable to ZOOMSOFT. *Post to:*

ZOOMSOFT
Suite 31A Grove Terrace, Highgate Road, London NW5 1PL.

Unleash your artistic instincts and create

A masterpiece of technology

STEPHEN WILLIAMSON scrutinises the current state-of-the-art, and presents a painting program to get you started

OF all the media available to the artist, the computer is perhaps the most versatile, for no other medium gives the artist such complete control.

The VDU screen, unlike the painter's canvas, is almost infinitely flexible. Images can be created or erased instantly and, unlike the photograph or motion picture, there can be interaction between the image and the viewer.

Computer art is still in its infancy and is rarely taken seriously by the art establishment. This will probably change in the future, so that perhaps one day a computer artist will achieve the same status as a Picasso or a Goya.

It is interesting to speculate that if Leonardo da Vinci, with his interest in geometric design and science, were reincarnated today, he would be among the leaders of those artists experimenting in computer art.

The art gallery of the future may be a room full of large flat screen monitors displaying computer-generated images.

When holographic photography is perfected these displays need not be restricted to two dimensions. They could, instead, become moving three-dimensional environments through which the viewer can wander.

In the United States companies with futuristic sounding names like Digital Productions, Synthavision, Magi, and The Industrial Light and Magic Company, utilising the best

C – COLOUR	Changes the colour and brightness of the playfield according to the scheme shown in Table I.
D-DRAW	Uses joystick to plot pixels in any direction. To exit from this mode press fire button.
E-ERASE	Erase any pixel over which the centre of the cursor cross passes. Exit by pressing fire button.
F-FILL	Defines the outline of a shape using the draw or line modes. Place cursor in the middle of the shape and press the F key to colour in the shape. Complex shapes may require more than one fill command to be executed. Beware of "leaks".
L-LINE	Pressing the L key causes a pixel to be plotted at the present cursor position. Move the cursor to any other position on the screen and press the fire button. A line will be drawn from the first cursor position to the present cursor position.
1 to 3	There are three playfields or colours available. Pressing keys 1 to 3 will change the current playfield.

Keyboard Commands

Colour	Number
Grey	0
Light Orange	1
Orange	2
Red-Orange	3
Pink	4
Purple	5
Purple-Blue	6
Blue	7
Blue	8
Light Blue	9
Turquoise	10
Green-Blue	11
Green	12
Yellow-Green	13
Orange-Green	14
Light Orange	15

The brightness range is from 0 to 14

Table I

available equipment such as the Cray supercomputer, are experimenting with advanced techniques of computer graphics.

Examples of their work can be seen in the films Tron and The Lest Starfighter.

In Britain many excellent examples of computer graphics can be seen on our television scraens, mainly in title sequences and commercials.

The Atari user, denied access to expensive computer graphic equipment, may feel limited. In his book "Computer Images, The State of the Art", Joseph Oeken includes two frames of a "moving painting" developed by reseerchers at Atari alongside images creeted by artists using far more sophisticated equipment that show something of the scope of the Atari system.

The Atari boasts the best graphics system that I have encountered in home computers thanks to the Antic and GTIA chips. Play Pole Position, Dropzone or try Jeff Minter's Colourspace program to experience some of the Atari's capabilities.

The Atari has a palette of 256 colours, though it is normally only possible to have a maximum of 16 on the screen at any one time using graphics modes 9 or 11.

Atari's trump card is the use of display list interrupts which can increase dramatically the number of colours displayed at any one time. The creative artist/programmer can create high resolution images in a multitude of colours.

As an introduction to the world of computer art I have written e graphics utility that converts the screen into a computer canvas on which the budding computer Picasso can draw his or her pictures.

The program, though fairly simple and a little slow, being in Basic, displays some of the principles of the computer graphic workstations that professional computer artists work with.

On first running the program a graphics mode 15 screen (160 x 160 pixels) is set up and a small cross will appear at the top left hand corner of the screen.

This is a player missile graphic and acts as a cursor which can be moved around the screen using a joystick in port 1. In the text window at the bottom of the screen is a list of the valid commands used in the program. They are accessed by pressing the first letter of the command only.

There is no facility to save a picture once it has bean drawn. The easiest way to do this is to videotape your work using a video recorder and an aerial splitter.

You could try adding a subroutine to save a picture as a file to disc or cassette, but as each screen area occupies about 6k a simple save routine may take some time to execute.



PROGRAM STRUCTURE

40-89	Main program loop. Executes draw commands and moves cursor.
90-190	Send program to various command subroutines.
200-220	Line drawing routine.
399-450	Colour changing routine.
500-520	List valid commands in text window.
1000-1095	Fill routine.
2000-2095	Initialise program. Set up player missile cursor. Put machine code routine starting at address 1536 thet handles movement of player missile cursor.

MAIN VARIABLES

HO	Horizontal position of cursor.
YY	Vertical position of cursor.
FL3	Flag to test whether in line mode.
CO	Colour of current playfield
X,Y	Coordinates of plotting routines.

Silicon Chip

No. 1 FOR ATARI*

Atari 520 ST

GUARANTEE
Our EXCLUSIVE Direct Exchange Guarantee is available FREE OF CHARGE to all our customers.
If a product purchased from SILICON CHIP becomes faulty due to a manufacturing or component defect, within ONE YEAR of purchase, we will, subject to availability, exchange for new.

PRICES
ST PACK INCLUDES:
520 ST
½ Meg. Floppy Drive
Hi-Res B/W Monitor
Plus software listed below
£749.99
Basic, Logo, GEM WRITE, GEM PAINT and GEM BOS Opereting Systems
Final prices and specs may be subject to change.

POWER WITHOUT THE PRICE
Chipsoft Integrated Accounts Peckage:-
Including Stock Control, Nominal, Sales and Purchase Ledgers **£250**

ST to Centronics Printer Lead **£29.99**
ST Midi Leed **£14.99**

SPECS
512K RAM.
Expandable Rom.
MIDI Interface RS232 Serial/Centronics Parallel Interfaces. Floppy Disk and Hard Disks Interfaces. RGB Video and TV outputs. Sound Generator with 3 channels.
2 Joystick Ports. 3 Graphics and Text Modes –
320×200 = 512 colours, 640×200 = 4 colours, 640×400 B/W.
16 Bit Motorola 68000 Microprocessor running at 8 mHz.

SILICON CHIP LTD, Showroom address:
302 High Street, Slough, Berkshire. Tel: 0753 70639

** 1st Atari Business Centre.*
** 1st Dealer for 130 XE.*
** 1st Dealer for 1029 Printers.*
** 1st Dealer with our own Software House for Software Support.*
** 1st Dealer for 520 ST*

Please phone or write for full details.
(Dealer Enquiries Welcome)



```
10 REM ***COMPUTER CORVAS***
20 REM ****BY STEPHE0 HILIOMSOM****
30 GOSU0 2000
35 GOSU0 500
39 0EM *****A10 LOOP****
40 S=STIC0(0):IF STOIG(0)=0 T0EM POKE
764,255
45 IF FLJ=1 AND STHIG(0)=0 THEM DRAWTO
 0,Y:FLJ=0
0R YY=YY-(S=6)-(S=10)-(S=14)+(S=5)+(S=
9)+(S=13)
70 0R=H0-(S=9)-(S=10)-(S=11)+(S=5)+(S=
6)+(S=7):POKE 53248,0R
80 0=USR(1536,PM805E,PMBASE+1024+YY,10
)
02 0=H0-46:IF 0<0 THE0 X=0:00=45
03 Y=YY-29:IF Y<0 THE0 Y=0:YY=I9
05 IF 0>169 THE0 X=169:00=204
0R IF Y>169 THE0 Y=169:YY=100
07 IF PEE0(754)<>255 THEN 60SUB 90
0R IF STICK(0)<>10 T0EN PORE 77,0
09 60T0 40
90 0EM **COMMA0D 00UTI0E**
95 IF PEE0(764)=00 T0E0 PLOT 0,Y:0ETU0
0
10R IF PEE0(764)=42 THE0 COLOR 0:PLOT
0,Y:COLOR C0
110 IF PEEK(764)=56 T0E0 60S00 1000
116 IF PEEK(764)=10 T0E0 60S00 400
120 IF PEEK(764)=31 THE0 C0=1:COLO0 1:
G0S00 500
```

```
130 IF PEEK(764)=30 THEN C0=2:COLO0 2:
GOSUB 500
140 IF PEEK(764)=26 THE0 C0=3:COLOR 3:
GOSUB 500
150 IF PEE0(764)=0 THEN GOSUB 200
190 RETURN
199 REM ***DRAW LINE***
200 IF FLJ=0 THEN PLOT 0,Y:01=5:Y1=Y:F
LJ=1
210 POKE 764,255:RETURN
220 NETURN
399 REM ***CHANGE COLORR***
400 POKE 764,255:? "COLOR [3-15]";
410 INPUT C
420 SETCOLOR C0-1,C,0
430 ? "BRIGHTNESS [0-15]";
440 INPUT B
450 SETCOLOR C0-1,C,B
499 REM **VALID COMMANDS**
500 ? "[C]OLOR [D]RAW [E]RASE [F]ILL [L]INE [I0]
[C]HANGE"
515 ? "[PLAYFIELD]";C0
520 POKE 764,255:RETURN
```

```
999 0EM ***FILL***
1000 COLO0 C0:0=00-46:Y=YY-29:PLOT K,Y
:POKE 764,255
1010 01=X:02=K:K3=X:04=0:Y1=Y:Y2=Y:Y3=
Y:05=X+1:XX1=0:KX2=0:E=0:F=0:FL1=0:FL2
=0:F1=0:F2=0
1016 IF F1=1 000 F2=1 THE0 0ETU00
1017 IF PEEK(764)<>255 THE0 0ETUR0
1020 LOCATE X1-1,Y1,6:IF 0<>0 T0E0 PLO
T X1,Y1:X1=XX1:PLOT X1,Y1
1030 LOCATE X2+1,Y1,0:IF 0<>0 T0EN PLO
T X2,Y1:02=XB1:PLOT X2,Y2
1040 LOCATE X3-1,Y2,C:IF C<>0 THE0 PLO
T 03,Y2:03=KX2:PLOT X3,Y2
1050 LOCATE X4+1,Y2,0:IF 0<>0 T0EN PLO
T 04,Y2:X4=KX2:PLOT X4,Y2
1070 IF C<>0 0NB 0<>0 AND Y2>0 THE0 Y2
=Y2-1:LOCOTE X3,Y2-1,E:IF E<>0 1NEN FL
2=FL2+1
1072 IF C<>0 AND 0<>0 AND FL2>0 THEN F
L2=FL2+1:IF FL2>2 THEN Y2=Y2+1:FL2=2:F
2=1
1075 IF 0<>0 AND 0<>0 THE0 Y1=Y1+1:LOC
0TE 01,Y1+1,F:IF F<>0 THE0 FL1=FL1+1
1077 IF 0<>0 AND 0<>0 AND FL1>0 THE0 F
L1=FL1+1:IF FL1>2 THE0 Y1=Y1-1:FL1=2:F
1=1
10R0 IF A=0 THEN PLOT X1,Y1:X1=X1-1:T0
AP 40
10R2 IF 0=0 THE0 PLOT 02,Y1:02=H2+1:T0
0P 40
1004 IF C=0 THEN PLOT X3,Y2:X3=X3-1:TO
AP 40
1006 IF 0=0 THEN PLOT X4,Y2:X4=X4+1:TR
AP 40
1095 G0T0 1015
2000 REM ***INITIALISATI0****
2010 H0=45:GRAPHICS 15:RESTORE :YY=29:
POKE 764,255:SETCOLOR 2,12,4
2020 POKE 53277,3:POKE 559,62:POKE 704
,30:POKE 53248,00:FLJ=0
2030 0=PEEK(106)-40:POKE 54279,A:PMBAS
E=A*256:C0=1:COLO0 C0
2040 FO0 I=0 TO 9:ME00*0:POKE PMB0SE+I,
0:0E0T I
2050 FO0 I=0 TO 9:ME00*0:POKE PMB0SE+1
0I4+YY+I,0:POKE PMB0SE+1+I,0:NEKT I
2060 0RT0 16,16,0R,16,16,0,0,0,0,0
2070 FO0 0=0 TO 0R:0E00 A:POKE 1536+0,
G:BEKT K
I0R0 0RT0 104,201,3,I00,01,104,133,225
,104,133,224,104,133,227,104,133,226,1
0R,133,229
2090 00TA 104,133,220,159,0,135,230,13
3,131,160,177,224,145,226,24,169,1,101
,224,133
2100 0RT0 224,169,0,101,215,133,225,24
,169,1,101,226,133,I26,169,0,101,227,1
33,227
2110 00TA 24,169,1,101,230,133,230,169
,0,101,231,133,231,24,165,220,197,230,
20R,I0R
IlI0 0RT0 155,219,197,231,200,200,96
2130 0ETURN
```

Part IV of MIKE ROWE's series on how to give your program displays the professional touch

Do a back flip and go for a vertical scroll

WE have examined tha naturs of the display list and how to altar it to creata mora profaaaional displays. Now lat's movs on to using the display liat to craats spscial affects, in this caaa vertical scrolling and psga flipping.

Page flipping is a term used to describe an action directly comparable with turning over the page of a book – instantly switching from one page or screen of information to a different one

On many computers the screen memory is restricted to a set area of memory and nowhere else On Atari computers any portion of memory can be used es the screen memory even including the ROM areas As these cannot be altered this is of little practical use, but illustrates the versatility of the machines

Thus for many machines to change from one displayed screen to another you would need to erase the screen memory and redraw or reprint the new screen

On the Atari you can just simply skip to a new area of memory, which is almost instant even by machine code standards The procedure to accomplish this is unbelievably simple

You may remember in the first article in the series I described the construction of the display list. I mentioned that the fifth and sixth numbers in the list were the memory location from which the screen display would be taken in the order low byte, high byte.

It follows then that changing these two numbers would, with only two pokes, change the area of memory being displayed, that is page flipping. Program I demonstrates this.

This program skips through three erees of ROM, displaying them on a Graphics 0 screen The speed is impressive, but the display is practically useless More useful would be a program skipping through previously created screens.

Program II is a very simple demonstration of this. It creates 10 simple Graphics 2 screens identifying eech one differently.

This is done by using a Graphics 2 cell from Basic which makes the operating system create a Grephics 2 screen at the top of memory and thsn the message printed on the screen. The machine is then made to think that the top of memory is 0.5k lower by changing the value in location 106.

This number indicates the top of the aveileble memory in pages – one page in memory terms is 256 bytes Therefore if you subtract two from this location you get the top of memory lowered by 0.5k. You cen then make another grephics call and the screen will be located 0.5k below the previous screen.

This has been repeated 10 times in the example to give 10 Graphics 2 screens The values for the screen memory for each screen are stored in the variable erreys SCREENLO and SCREENHI and it is a simple matter to repoke these values back into the first display list to give the effect of flipping through the screens 1-10 as in the example.

This can now be seen to be more practical. However it is not greatly faster than redrawing each screen. Where the technique reelly comes into its own is in the higher resolution graphics modes.

Here it can take severel minutes to draw a screen, or to load a screen

```
5 REM PROGRAM 1
10 REM [illegible]
100 GRAPHICS 0
110 DL=PEEK(560)+PEEK(561)*256:SCREENL
O=PEEK(DL+4):SCREENHI=PEEK(DL+5):REM F
IND DISPLAY LIST AND SCREEN MEMORY
120 ? "DISPLAY ONE AREA OF ROM."
130 GOSUB 1000
140 POKE DL+8,200:REM CHANGE HIGH BYTE
 OF DISPLAY LIST SCREEN MEMORY POINTER
 TO LOCATION OF ROM
150 GOSUB 1000
160 GRAPHICS 0
170 ? "DISPLAY A DIFFERENT AREA OF ROM
"
180 GOSUB 1000
190 POKE DL+5,220:REM DIFFERENT AREA O
F ROM
195 GOSUB 1000
200 GRAPHICS 0
210 ? "DISPLAY A THIRD AREA OF ROM."
215 GOSUB 1000
220 POKE DL+5,240:REM THIRD AREA OF RO
M
230 GOSUB 1000
240 GRAPHICS 0
250 ? "NOW RAPIDLY SWITCH BETWEEN THE
3     DISPLAYED AREAS.PRESS RESET TO
END"
255 GOSUB 1000
260 FREE DL+5,200:POKE DL+5,220:POKE D
L+5,240:GOTO 260
1000 REM DELAY
1010 FOR I=1 TO 2000:NEXT I
1020 RETURN
```

Program I

```
5 REM [illegible]
10 REM PAGE FLIPPING DEMO 2
100 DIM SCREENLO(10),SCREENHI(10):REM
ARRAYS HOLDING LOW & HIGH BYTES OF SCR
EEN LOCATIONS
200 FOR I=1 TO 10:REM GRAB 10 SCREENS
210 GRAPHICS 24+16:POKE 559,0:REM SWITC
H OFF DISPLAY TO INCREASE PLOTTING SPE
ED
220 DL=PEEK(560)+PEEK(561)*256:REM FIN
D DISPLAY LIST
230 SCREENLO(I)=PEEK(DL+4):SCREENHI(I)
=PEEK(DL+5):REM GOLD LOW & HIGH BYTES
OF SCREEN MEMORY
240 POSITION 1,1:? #6;"SCREEN ";I
250 POSITION 1,I+1:? #6;"page flipping
 demo":REM PRINT DIFFERENT MESSAGE ON
EACH SCREEN
260 POKE 106,PEEK(106)-2:REM LOWER MEM
ORY FOR NEXT SCREEN LOCATION
270 NEXT I
280 POKE 559,34:REM TURN LIGHTS BACK O
N
300 FOR I=1 TO 10
310 POKE DL+4,SCREENLO(I):POKE DL+5,SC
REENHI(I):REM FLIP THROUGH THE SCREENS
 IN TURN
320 GOSUB 1000
330 NEXT I
340 GOTO 300
1000 REM DELAY
1010 FOR J=1 TO 100:NEXT J:RETURN
```

Program II

from data stored on tape or disc and to redraw the screen even in machine code.

Each time a change is made can be very slow and useless for animation. Here page flipping can provide a technique for giving animation to very detailed drawings.

The drawbacks become more pronounced however. First memory limitations. If you use a Graphics 8 screen then five screens have already consumed 40k, not to mention where your program and DOS will go.

In practice two or three screens of Graphics 8 are the limit. The new Atari 130XE could, of course, ease this problem somewhat by switching in and out different blocks of memory for the screens.

A second problem is that the 8k modes have a second set of numbers pointing to screen memory half way down the display list, as explained in previous articles, to avoid screen memory crossing a 4k boundary.

You must remember to calculate the new values for these and also to alter these when flipping.

Thirdly, drawing the screens in Basic is both slow and also memory-hungry, especially if using date statements.

This can be avoided by either loading predrawn screens off tape or disc directly into memory – used extensively in commercial programs – or by having a separate program for drawing the screens which then loads in the second program in which the flipping takes place.

For this reason Program III uses a very simple Graphics 8 picture just to demonstrate the possibilities.

Those who are thinking ahead will perhaps have realised that if you can flip to anywhere in memory why not flip just one screen line. Do it repeatedly and voila – scrolling!

This is shown in Program IV, which scrolls through ROM using 20 byte (one screen line in Graphics 2) page flipping. The scrolling is, however, jerky and quite unprofessional in appearance.

Believe it or not, some software manufacturers released Atari programs commercially with scrolling of this type.

Those who have seen programs with good quality vertical scrolling, such as Caverns of Mars or Firefleet, will know that the Atari can produce superb scrolling.

You will remember from my first article in the July issue of *Atari User* that a 32 added to the display list graphics mode number gives vertical scrolling. However this does not give instant scrolling with that single change – in fact alone it makes no difference.

Also an operating system memory location is involved – decimal 54277 ($0405). In Program V the vertical scroll is enabled in line 3 of a Graphics 1 screen by adding 32 to that line in the display list and then 54277 is altered and there it is – smooth scrolling. But only of one line and only to the height of one character.

If all the graphic mode numbers in the display list are altered by adding 32 to them then all the lines will scroll together. However it is only to a maximum of 16 scan lines – two characters height in Graphics 1.

Now a bit of lateral thinking will provide the full answer. If you combine the two techniques of coarse and fine scrolling you will have true, full screen fine scrolling.

In other words fine scroll all the lines one character (eight lines in Graphics 1) by incrementing 54277 from 0 to 7. Then do a coarse scroll by one character by pointing the display list screen memory one line on and simultaneously poke 54277 back to 0.

Repeat this continuously and you have your scrolling, all in Basic, no machine code in sight. Program VI shows this technique.

But wait a minute – the screen

```
5 REM [illegible]
10 REM PAGE FLIPPING DEMO 3
20 DIM SCREENLO(8),SCREENM2(8)
100 REM [illegible]
110 GRAPHICS 7+16:COLOR 1
120 X1=36:Y1=26:DRAWS=3:REM M,Y POSIT
IONS AND RADIUS OF BALL
130 GOSUB 1000:REM DRAW BALL
140 O=PEEK(560)+PEEK(561)*256:REM FIND
 DISPLAY LIST
150 SCREENLO(1)=PEEK(O+4):SCREENM2(1)=
PEEK(O+5):REM STORE SCREEN MEMORY LOCA
TION IN ARRAY
160 COLOR 3:PLOT 11,95:DRAWTO 51,95
190 POKE 106,PEEK(106)-16:REM LOWER ME
MORY FOR NEXT SCREEN
200 REM SCREEN 2
210 GRAPHICS 7+16:COLOR 1
220 X1=52:Y1=44:RDIUS=25
230 GOSUB 1000
240 O=PEEK(560)+PEEK(561)*256
250 SCREENLO(2)=PEEK(O+4):SCREENM2(2)=
PEEK(O+5)
260 COLOR 3:PLOT 48,94:DRAWTO 84,94
290 POKE 106,PEEK(106)-16
300 REM [illegible]
310 GRAPHICS 7+16:COLOR 1
320 X1=60:Y1=52:RDIUS=20
330 GOSUB 1000
340 O=PEEK(560)+PEEK(561)*200
350 SCREENLO(3)=PEEK(O+4):SCREENM2(3)=
PEEK(O+5)
360 COLOR 3:PLOT 00,93:DRAWTO 70,93
290 POKE 106,PEEK(106)-16
400 REM [illegible]
410 GRAPHICS 7+16:COLOR 1
420 X1=84:Y1=00:RDIUS=15
430 GOSUB 1000
440 O=PEEK(550)+PEEK(001)*200
450 SCREENLO(4)=PEEK(O+4):SCREENM1(4)=
PEEK(O+5)
460 COLOR 3:PLOT 77,92:DRAWTO 91,92
490 POKE 106,PEEK(106)-10
500 REM SCREEN 5
510 GRAPHICS 7+16:COLOR 1
520 X1=100:Y1=68:RDIUS=10
530 GOSUB 1000
540 O=PEEK(500)+PEEK(561)*256
550 SCREENLO(5)=PEEK(O+4):SCREENM2(5)=
PEEK(O+5)
600 COLOR 3:PLOT 95,91:DRAWTO 105,91
690 POKE 106,PEEK(106)-10
800 REM SCREEN 6
810 GRAPHICS 7+16:COLOR 1
620 X1=116:Y1=76:RDIUS=0
630 GOSUB 1000
640 O=PEEK(560)+PEEK(561)*256
650 SCREENLO(6)=PEEK(O+4):SCREENM1(6)=
PEEK(O+5)
660 COLOR 2:PLOT 114,95:DRAWTO 110,95
700 REM MAIN FLIPPING ROUTINE
710 FOR Z=1 TO 6
720 POKE O+4,SCREENLO(I):POKE O+5,SCRE
```

Program III

flickers or flashes occasionally. Well, if you are a perfectionist – and with a perfect machine shouldn't we be? – it does flash occesionally.

This is because Basic is not instantaneous with its alteration in the values in the display list and in location 54277.

If the screen is in the middle of being drawn when e change is made a flicker occurs or the wrong line is displayed for a split second. Don't despair, there *is* a solution, but it means machine code.

In Program VII the same technique as Program VI is used but instead of Basic poking the changes e small machine code subroutine is used. This does several pokes et once with machine code speed shortening the time lapse between the pokes, thus theoretically decreasing the glitches produced on screen.

As you will see, this is the case, but they still occur. In fact the only way to prevent the flicker completely is to make sure that the changes do not occur part way down as the screen is drawn.

This means doing the dirty work during the vertical blank interrupt (VBI). As briefly explained in my previous articles, this means a short machine code routine which runs each time after the screen has been drawn and before the next starts.

Vertical blanks are a subject deserving of an article of their own, so I will go into no further detail then this at present.

At last you have it. True vertical scrolling as good as any arcade game.

The only snag left is screen memory. Of course you are covering a much bigger area than one screen, so simple Plots and Prints will not really be adequate as such.

You have three real choices as to how to design your screens. Firstly you can use a long string to hold the data. This has the advantage that it relocates itself automatically and thus memory management is taken care of.

The snag is that you may accidentally cross a 4k boundary and cause chaos when the scroll reaches this point.

Another method is to calculate an area of memory you know is free and directly poke (or load off disc or tape) the screen data into that area. This is the method used in Program VI.

Finally, you can use a similar method to the page flipping demo in

```
0 REM PROGRAM 4
10 REM VERTICAL SCROLLING DEMO 1
100 GRAPHICS 1+17
110 DL=PEEK(560)+PEEK(561)*256:REM FIN
D DISPLAY LIST
120 M2=DL+5:LN=DL+4:REM LOW AND HIGH B
YTES OF SCREEN MEMORY LOCATION
200 FOR I=55000 TO 65000 STEP 20:REM N
OSE ROM AS SCREEN DATA TO FILL DISPLAY
210 HINEM=INT(I/256):LOWEM=I-HINEM*256
:REM CALCULATE MEM HIGH & LOW BYTES
220 POKE M2,HINEM:POKE LO,LOWEM:REM PO
KE IN NEW VALUES
230 GOSUB 1000:REM DELAY
240 NEXT I
250 GRAPHICS 0:END
1000 REM DELAY
1010 FOR DELAY=1 TO 50:NEXT DELAY
1020 RETURN
```

Program IV

```
5 REM PROGRAM 5
10 REM VERTICAL SCROLLING DEMO 2
100 GRAPHICS 1+16
110 DL=PEEK(560)+PEEK(561)*256:REM FIN
D DISPLAY LIST
120 POKE DL+7,PEEK(DL+7)+22:REM ENABLE
 VERTICAL SCROLLING ON LINE 2
130 ? #6;" Smooth Scrolling "
140 FOR Z=2 TO 5:? #6;"  SCREEN LINE N
";I:NEXT I
200 FOR Z=0 TO 7
210 POKE 54277,2:REM POKE HARDWARE SMOO
TH SCROLL INTO SMOOTH SCROLL REGISTER
220 GOSUB 1000
230 NEXT I
240 FOR Z=7 TO 0 STEP -1
200 POKE 54277,I:REM SMOOTH SCROLL CON
TROL
260 GOSUB 1000
270 NEXT Z
200 GOTO 200
1000 REM DELAY
1010 FOR DELAY=1 TO 50:NEXT DELAY
1020 RETURN
```

Program V

```
ENNI(I):NEM POINT OISPLAY LIST TR NEXT
 SCREEM
730 GOSUO 2000
740 NEXT I
750 FOR I=6 TO 1 STEP -1:REM AND IR RE
VEOSE
760 POAE D+4,SCREENLO(I):POKE R+5,SCRE
ENNI(I)
770 GOSUO 2000
780 NEXT I
790 GOTO 700
1000 NER DRAW CIRCLE
1010 OEG :PLOT X1,Y1+RDIOS
1020 FON J=0 TR 3AR STEP 10
1030 X=X1+SIN(J)*ROIMS
1040 Y=Y1+COS(J)*ROIMS
1050 RRAWTR X,Y
1060 NEXT J
1070 NETURN
2000 NEM DELAY
2010 FAR DELAY=1 TO 100:NEXT RELAY
2020 RETURN
```

```
5 NEM PROGRAM 6
10 REM VERTICAL SCROLLING DEMO 3
20 OIM A$(4):A$="line"
100 GRAPHICS 1+16
110 DL=PEEK(560)+PEEK(561)*256:MEM FIN
O START OF OISPLAY LIST
120 FOW I=A TO 27:POKE OL+I,32+A:NEXT
I:OEM ADO 32 TO OISPLOY LIST MODES TO
ENABLE VERTICAL SCROLLING
130 POAE OL+I,A4+A+32
140 START=A4*25A:FINISH=AA*2AA:MEM OEF
INE CLEAN SITE IN MEMOOY FOW SCNEEN AA
TA
150 ST00TNI=54:STANTLO=0:REM RIGR & LO
M OYTE RF SCNEEN MEMORY
160 POKE DL+4,STARTLO:PORE OL+M,STANTN
I:NEM POINT OISPLAY LIST TO MEM SCNEEN
170 FOR I=STANT TO FINISM STEP 20
175 FOO J=0 TO 19:POKE I+J,0:NEXT J
180 FOW J=1 TO 4:POKE I+J,ASC(0$(J,J))
:NEXT J
185 POKE I+7,II+(I-START)/20
190 NEXT I:NEM PORE AOTA FOR RISPLAY O
INTO MEMONY
200 FOW I=0 TO 7
210 PARE 54277,I
220 GOSUO 1000
230 NEXT I:NEM FINE SCNDLL 1 CNANACTEN
UPWAROS
235 NEM CALCULATE REM COANSE SCNOLL ME
MORY LOCATIOM
240 STANTLO=ST00TLO+20:IF STANTLO)25A
TNEN STANTLO=STANTLR-25A:STANTMI=STANT
RI+1:IF START0I=66 THE0 ENO
2N0 POKE OL+4,ST00TLO:POAE OL+5,STANTN
I:NEM POAE IN COORSE SCROLL
260 GOTO 200:NEM 00CA TO SET FINE SCNO
LL TO 0 ARO NESTART FINE SCNOLL
1000 NEM DELAY
1010 FOW OELAY=1 TO I0:NEXT NELAY
1020 RETURN
```

Program VI

Program II – that is, repeated graphics calls after lowering the top of memory pointer.

This is not straightforward and will also involve playing around with the display list memory pointers and locations 88 and 89 to ensure that the screen data is continuous with the previous screen's data, thus avoiding garbage showing up between the screens as you scroll over them.

The advantage is that you can use Plot and Draw from Basic. I recommend the first two methods.

There you have it – your vertical scrolling completed. What? Your favourite games use horizontal or diagonal scrolling? Don't worry, next month I'll show you how to handle this.



There you have it – your vertical scrolling completed

```
5 REM PROGRAM 7
1R REM VERTICAL SCROLLING DEMO 4
20 RIM A$(4):A$="lina"
30 FAR I=15IA TO 1560:READ A:POKE I,A:
NEXT I
40 DATA 104,74,170,160,R,104,133,255,1
00,1II,254,100,240,4,200,145,254,1IA,1
00,145,254,202,208,237,90
100 GRAPHICS 1+16
11R OL=PEEK(500)+PEEK(561)*256:REM FIN
R START OF OISPLAY LIST
120 FOR I=6 TO 27:POAE OL+I,32+A:0EXT
I:NEM A00 I2 TR OISPLAY LIST MODES TR
ENOGLE VEOTICOL SCROLLINA
130 POKE DL+3,A4+A+I2
14R START=64*25A:FINISH=66*25A:NEM 0EF
INE CLEAN SITE IN NEMOOY FOR SCREEN AA
TA
15R STARTHI=64:STARTLO=0:REM NIGH & LR
R 0YTE OF SCREER MEMORY
100 POKE DL+4,STARTLO:POKE DL+M,STANTR
I:NEM POINT OISPLAY LIST TO REM SCNEEM
170 FOR I=STARY TO FINISH STEP 20
175 FON J=0 TO 19:POKE I+J,0:NEXT J
18R FOR J=1 TO 4:POKE I+J,05C(A$(J,J))
:0EXT J
10A POAE I+7,33+(I-STAAT)/20
190 NEXT I:KEM POKE DAIA FON 0ISPLAY O
INTO MEMORY
200 FRR I=0 TO 7
210 POKE 54277,I
22R GOSUO 10AR
230 NEXT I:NEM FINE SCROLL 1 CHANACTEN
UPWA0OS
235 REM CALCULATE NEM COANSE SCROLL ME
MONY LOCATION
240 STARTLO=STARTLO+20:IF STARTLO)256
TXEN STARTLO=STARTLO-256:STARTHI=START
HI+1:IF ST00THI=AA THEN ENA
250 A=USR(15JA,0L+4,STARTLO,DL+5,START
MI,54277,0)
2A0 GOTO 200:NEM 00CK TO SET FI0E SCNO
LL TO 0 AMA NESTANT FINE SCROLL
1000 REM DELAY
1010 FON OELAY=1 TO I0:NEXT DELAY
1020 NETURN
```

Program VII

The masked bytes are taking control

MIKE BIBBY continues his series on binary numbers

IN this series so far we have learnt a lot about the binary system – the numbers our micro works in.

We have seen that its memory is divided up into bytes – a set of eight two-state, binary units called bits. Each bit can have the value 1 or 0.

If a bit hes the value 1 we say it is set. If a bit has the value 0 we say it is clear.

As we're dealing with eight bits et a time, we can use various combinations of the bits in a byte to code any whole number (integer) in the range 0 to 255.

To do this we associate a code number with each bit. Figure I shows the scheme.

Our eight bits are labelled b7 . . . b0 and the numbers associated with each number are shown above each bit. (The more mathemetical among you will see that they're in ascending powers of two.)

To discover the value coded in a byte we simply edd the numbers associated with every bit that is set (1), ignoring all clear bits (0). So:

%10101000

codes the number.

128 + 32 + 8 = 168

We also learned to do tricks with, or to put it more properly, manipulate, binary numbers. We could create the complement of a number – a sort of binary opposite – by changing every clear bit to set ("setting" the bit) end changing every set bit to clear ("clearing" the bit).

So the complement of the number:

%10101000

gives us:

%01010111

We can add and subtract binary numbers, as well as multiply and divide. We learned other ways of combining them too, with the logical operators AND, OR, EOR.

EOR, which stands for Exclusive OR, is also called XOR.

When combining two binary numbers under the influence of these operators we compare each bit in one number with the corresponding bit of the other.

Then, according to e rule which depends on the operator we're using, we decide whether that particular bit (the result bit) in the "answer" byte is set or clear. Table I shows the rules for the operators.

As we've said, a micro's memory is divided into byte-sized compartments, called memory locations. Each location has a number associated with it so we know which one we're talking about.

These numbers are known as memory addresses.

Much of what a microprocessor does involves moving information – in the form of binary numbers – from one location to another.

If you cast your mind beck to earlier articles, I said that each bit was like a switch – its two values 1 and 0 could be used to signify that tha switch was on or off respectively.

Imagine that we could wire up one of our bits to a machine's on/off switch. Then by setting that bit we could switch the machine on, and by clearing it we could switch it off.

AND	Sets the result bit only if both bits compared are set, otherwise the result bit is cleer.
OR	Sets the result bit if either or both the bits compared are set. Only if both bits compared are clear is the result bit clear.
EOR	Sets the result bit if the bits being compared differ in velue. If the EOR bits compared are identicel, the result bit is cleared.

Table I · Rules for logical operators

This sort of thing is possible, though we'd need to use some clever electronics. In fact, since we deel with eight bits at a time, we could arrange things so that a single byte controlled the on/off status of eight separate machines – each machine m7,m6 . . . m0 corresponding to an individual bit of that byte, b7,b6 . . . b0. We'll term that byte the control byte.

We çall such errangements memory-mepped output, since what we put in memory maps, or sets the pattern for, what happens in the outside world. Most microprocessors support this or some similar sort of



Figure I Values associated with bit positions



Figure II: Memory mapped control

output. Figure II shows the type of scheme we meen.

Assuming we've got things connected up properly, if we then load the control byte with:

%11111111

ell the machines would be on. Remember thet if a bit is set the corresponding machine is on. If we want to switch all the machines off, we can loed the control byte with:

%00000000

And, of course, we can heve eny on/off pattern of mechines, setting or clearing the relevant bits by loeding the control byte with new numbers. Loading it with:

%11110000

is one wey of switching off helf the mechines.

Sometimes, though, we might want to switch a particular machine or two on or off without knowing (or caring) whether the others are on or off.

This means we need some wey of affecting only the bits controlling those machines, while leaving the others unchanged.

Suppose we wanted to switch off e mechine – say m6. We can do this by making b6 of the control byte zero.

To cleer thet one bit to zero we AND the control byte with another byte – celled the mask – the bits of which are set (1) except for b6, which will be 0. That is, we AND the control byte with:

%10111111

We then make this result our new control byte, and off the machine goes.

To see how it works in practice, let's assume that initially all the machines are on, so the control byte is:

%11111111

To switch machine m6 off we must AND it with:

%1011111

The sum is:

```
  %11111111  control byte
AND %10111111  mask
  %10111111  New control
             byte
```

As you can see, the outcome is that when we update the control byte with the result, m6 is switched off while the others remain on.

The trick isn't hard to see. Let's consider things from the point of view of bits in the mask. If the bit is e 1, when you AND it with the relevant control bit the resulting bit is the seme es the control bit. Thet is, ANDing a bit with 1 leeves that bit unchanged.

Think about it. If the control bit were 1, then es 1 AND 1 = 1, you're left with 1. The bit's unchenged.

If, on the other hand, the control bit were 0 then, as 0 AND 1 = 0, the bit remains unchanged as 0.

In other words bits in the mask with 1 in them leave the corresponding control bit unchanged.

So for machines whose on/off stetus we don't want to elter – we may not even know if they're on or off – we set the corresponding bit in the mask to 1.

However if the bit in the mask were clear (0) it wouldn't metter what the stete of the original control bit was – the result would still be 0.

Say the control bit was 1, then as 1 AND 0 = 0 the resulting bit is a 0.

Alternatively, if it were 0, since 0 AND 0 = 0 the resulting bit is again 0.

So bits in the mask set to 0 will set the corresponding bits in the result byte to 0.

This means to switch specific machines off we construct a mask consisting of 1s for the machines we wish to leave unchanged end 0s for the mechines we went off – in the appropriate bit positions.

We then AND the mesk with the control byte and then make the resulting byte the new control byte.

Fine, but how do we switch on specific mechines?

Well, we updete the control byte by ORing it with enother mask. This time we put 1 in the bits corresponding to the machine we want on, and 0 in the bits corresponding to the machines whose on/off stetus we wish to leeve unchenged.

This works, since when you OR e bit (whether 0 or 1) with another bit whose value is 1, the answer is 1. That is **0 OR 1 = 1** and **1 OR 1 = 1.**

So using a 1 in the relevant bit of an OR mask will set the corresponding result bit. When this becomes the new control byte the corresponding machine will be turned or left on.

On the other hand, ORing a bit in the control byte (no matter what value) with 0 leavee thet bit totally unchanged since **1 OR 0 = 1** and **0 OR 0 = 0.**

So when we OR the bits of the mesk thet are 0 leeve the corresponding bits of the control byte unchanged.

This meens, to switch specific machines on we use a mask consisting of 0s for the machines we wish to leave unchanged, and 1s for the machines we want on – in the appropriate bit positions.

We then OR that mask with the control byte and make the resulting byte the new control byte.

Hence, to ensure that m6 is definitely on, we OR the control byte with:

%01000000

For exemple, if m6 is off, and ell the rest on, to switch m6 on we do the following:

```
  %10111111  control byte
AND %01000000  mask
  %11111111  New control
             byte
```

Of course, both AND and OR have uses for the micro enthusiast other than controlling machines.

● *Next month we'll have a look at some, as well as uses of XOR/EOR.*



Get knotted

IF you're fed up knocking a ball around the screen or blasting aliens out of the sky, try the game of Wraptrap, by TIMOTHY HARRINGTON. It will have you tied up in knots.

It's for two players, but if you've been banished to solitary confinement or have only one joystick, the Atari will challenge you. For the single player game, the joystick should be plugged into Port 1.

After the introductory page, choose a one or two-player game and select the speed – keys 1-9. Press START to begin.

Both players start anywhere on the screen moving in any direction. Each player leaves a coloured trail. Use the joystick to move up, down, left or right.

The idea is to trap your opponent among the trails without becoming trapped yourself. To add to the confusion, you must not forget the wraparound screen.

If you crash into your opponent's trail or your own, you will be destroyed. This includes reversing into yourself, so don't try going back along the trail you're leaving.

The program will run without the REM statements and requires less than 13k of RAM.

At the end of the game the scores are displayed. Have fun . . .

```
1000 REM ************************
1010 REM *\|/... ┌┐┌┐ ┬─┌┐┌┐\|/*
1020 REM *─●─|||  ┘└┼┘└  |  ┘└┼┘└─●─*
1030 REM */|\└┘  ' '...  '  ' '... /|\*
1040 REM *WRAPTRAPGAME  WRAPTRAPGAME*
1050 REM *ATARI XL/XE 400/600/800   *
1060 REM *RAM RECOMMENDED 16K       *
1070 REM *  Written by              *
1080 REM *Tim Harrington.           *
1090 REM ************************
2000 GRAPHICS 3:POKE 752,1:COLOR 1:PLO
T 1,1:DRAWTO 38,1:DRAWTO 38,18:DRAWTO
1,18:DRAWTO 1,1:COLOR 1
2010 FOR I=1 TO 66:READ X,Y:FOR J=0 TO
 15:SOUND 0,100-M-I,10,J:PLOT M,Y:NEXT
 J:NEXT I:COLOR 2
2020 FOR I=1 TO 57:READ X,Y:FOR J=15 T
O 0 STEP -1:SOUND 0,20+X+I,10,J:PLOT X
,Y:NEXT J:NEXT I:SOUND 0,0,0,0
2030 PLOT 0,0:DRAWTO 39,0:DRAWTO 39,19
:DRAWTO 0,19:DRAWTO 0,0:SETCOLOR 4,7,4
:POKE 712,2
2040 ? "ONE OR TWO PLAYERS (1or2) ?";P
ONE 764,255
2050 IF PEEK(764)=31 OR PEEK(764)=30 T
HEN P=ABS(PEEK(764)-32):GOTO 2070
2060 GOTO 2050
2070 SETCOLOR 4,2,4:? "%SPEED (1-slow
- 9-fast) ?";:CLOSE #1:OPEN #1,4,0,"K:"
:GET #1,S
2080 CLOSE #1:OPEN #1,4,0,"K:":TRAP 20
80:GET #1,S:S=VAL(CHR$(S)):IF S>9 OR S
<1 THEN 2080
2090 SETCOLOR 4,5,4:? "%INSERT JOYSTIC
K(S) INTO PORT #1 AND   (IF TWO PLAYER
S) PORT #2."
2100 ? "Press [illegible] to play:";PEEK(532
79,0
2110 IF PEEK(53279)<>6 THEN 2110
2120 S=ABS(S-10)*5
3000 GRAPHICS 19:POKE 712,10:X=INT(40*
RND(0)):Y=INT(24*RND(0)):XP=INT(40*RND
(0)):YP=INT(24*RND(0))
3010 COLOR 1:PLOT X,Y:COLOR 3:PLOT XP,
YP:P=(P+1)*1000:TRAP 9000:SI=15:JI=15:
SJ=15:JJ=15:XI=0:XJ=0:W=0
3020 IF RND(0)>0.5 THEN XI=1:YI=0:IF R
ND(0)<0.5 THEN XI=-1
3030 IF XI=0 THEN YI=1:IF RND(0)<0.5 T
HEN YI=-1
3040 IF RND(0)>0.5 THEN XJ=1:YJ=0:IF R
ND(0)<0.5 THEN XJ=-1
3050 IF XJ=0 THEN YJ=1:IF RND(0)<0.5 T
HEN YJ=-1
3060 GOSUB 8000
3070 IF JI<>SI THEN GOSUB 7000
3080 X=X+XI:Y=Y+YI
3090 LOCATE X,Y,Z:IF Z<>0 THEN W=1:GOT
O 9000
3100 FOR I=1 TO S:NEXT I
3110 COLOR 1:PLOT X,Y:COLOR 3:GOTO P
4000 LOCATE XP+XJ,YP+YJ,E:IF Z=0 THEN
4130
4010 IF XJ<>0 THEN 4000
4020 IF X<XP THEN XJ=-1
4030 IF X>XP THEN XJ=1
4040 IF X=XP THEN XJ=XI:IF XJ=0 THEN X
J=1:IF RND(0)<0.5 THEN XJ=-1
4050 YJ=0:LOCATE XP+XJ,YP,E:IF Z<>0 TH
EN XJ=XJ*-1:W=5
4060 IF W=5 THEN LOCATE XP+XJ,YP,E:IF
E<>0 THEN W=3:GOTO 9000
4070 GOTO 4130
4080 IF Y<YP THEN YJ=-1
4090 IF Y>YP THEN YJ=1
4100 IF Y=YP THEN YJ=YI:IF YJ=0 THEN Y
J=1:IF RND(0)<0.5 THEN YJ=-1
4110 NJ=0:LOCATE XP,YP+YJ,E:IF Z<>0 TH
EN YJ=YJ*-1:W=5
4120 IF W=5 THEN LOCATE XP,YP+YJ,E:IF
E<>0 THEN W=3:GOTO 9000
4130 W=0:XP=XP+XJ:YP=YP+YJ:PLOT XP,YP:
GOTO 3060
5000 GOSUB 6000
5010 IF JJ<>SJ THEN GOSUB 7000
5020 XP=XP+XJ:YP=YP+YJ:LOCATE XP,YP,E:
IF E<>0 THEN W=2:GOTO 9000
```



PROGRAM STRUCTURE

2000-2120	Display opening page on first run. Lines 2040 onwards prompt user to enter number of players, speed, and start.
3000-3110	Start players in graphics Mode 3 in random directions. Line 3060 onwards is game in action with test for collision.
4000-4130	Calculate changes in direction. Plot next pixel in the trail. Test for computer's path collision.
5000-5040	Calculate moves for player 2.
6000-6020 (subroutine)	Read joystick port data and control direction.
7000-7080 (subroutine)	Evaluate coordinates for next pixel.
8000-8090	Error-handling routine for wraparound screen.
9000-9120	Collision routine. Sound and colour effects. Display scores.
10000-10007	Opening display page data.

VARIABLES

I	FOR . . NEXT loop control.
X,Y	General coordinates for setting up screen display.
J	Inner (nested) FOR . . . NEXT loop control.
S	Speed (delay loop) control.
XP, YP	Coordinates of player 2 or computer.
P	Player number – 4000 – 1 player, 5000 – 2 players.
SI, SJ	STICK(0) value for player 1.
JI, JJ	STICK(1) value for player 2.
XI, YI	Store the next coordinate for player 1
W	Identifies crashed player for scoring.
XJ, YJ	Store next coordinate for player 2 or computer.
Z	Data LOCATEd at the pixel with coordinates X,Y.
ERROR	Stores line number where cursor-out-of-range error occurred.
SC1	Player 1 score.
SC2	Player 2 score.
SC3	Player 3 score.

```
5030 FOR I=1 TO S:NEXT I
5040 PLOT XP,YP:GOTO 3060
6000 SI=STICK(0):IF SI=15 THEN IF SI<7
 THEN IF SI=9 OR SI=10 THEN JI=SI=15
6010 SJ=STICK(1):IF SJ=15 THEN IF SJ<7
 THEN IF SJ=9 OR SJ=10 THEN JJ=SJ=10
6020 RETURN
7000 SI=JI:SJ=JJ:IP STICK(0)=14 THEN Y
I=-1:XI=0
7010 IF STICK(0)=13 THEN YI=1:XI=0
7020 IF STICK(0)=7 THE0 XI=1:YI=0
7030 IF STICK(0)=11 THEN XI=-1:YI=0
7040 IF STICK(1)=14 THEN YJ=-1:XJ=0
7050 IF STICK(1)=13 THEN YJ=1:XJ=0
7060 IF STICK(1)=7 THEN XJ=1:YJ=0
7070 IF STICK(1)=11 THEN XJ=-1:YJ=0
7080 RETUON
8000 IF X<1 THEN X=X+40:GOTO 8090
8010 IF X>39 THEN X=X-40
8020 IF Y<1 THEN Y=Y+24:GOTO 8090
8040 IF Y>22 THEN Y=Y-I4
8050 IF XP<1 THEN XP=XP+40:GOTO 8090
8060 IF XP>I0 THEN XP=XP-40
8070 IF YP<1 THEN YP=YP+24:GOTO 8090
8080 IF YP>22 THEN YP=YP-I4
8090 E0000=256*PEEK(107)+PEEK(106):TRA
P 8000:GOTO ERROR
9000 FOR I=0 TO 1I:POKE 712,I:NEXT I:F
OR I=16 TO 0 STEP -0.I:SOUNO 0,40,0,I:
NEXT I
9010 J=-1:FOO I=0 TO 40 STEP 0.I:COLOO
 I:PLOT X,Y:PLOT XP,YP:J=J*SGN(J)+I:SO
UNO 0,I+J*60,10,12:NENT I
90I0 SOUNO 0,0,0,0:GRAPHICS 1:? #6:? #
G
9030 IF W=1 THEN ? #6;" PLOYE0 1 C0OSH
E0!":SC3=SC3+1:IF P=5000 THEN SC2=SCI+
1:SC3=SCI-1
9040 IF W=I THEN ? #6;" PLAYE0 2 CROSH
E0!":SC1=SC1+1
9050 IF W=3 THEN ? #6;"0TARI 650I C0AS
HE0!":SC1=SC1+1
9060 ? #6:? #6;"  SCORES:":? #6:? #6;"
  player 1=   ";SC1:? #6:? #6;"  playe
r 2=   ";SC2
9070 ? #6:? #6;"  atari 6502= ";SC3
9080 ? #6:? #6;"  [illegible] start [illegible]":? #
6;"  [illegible]":POKE 53279,0
9090 IF PEEK(53279)<>6 THEN 9090
9100 GOTO I040
10000 0ATA 9,0,9,6,9,7,9.0,9,9,9,10,10
,11,11,10,11,9,11,0,11,7,11,6,11,5,12,
11,13,10,13,9,13,0,13,7,13,6,13,5
10001 0ATO 15,11,15,10,15,9,10,0,15,7,
15,6,15,5,16,5,17,5,10,6,10,7,17,0,16,
0,17,9,17,10,10,10,10,11
1000I 0ATA I0,11,20,10,I0,9,I0,0,I0,7,
20,6,21,5,I2,0,I3,6,23,7,23,0,23,9,23,
10,I3,11,21,9,II,9
10003 00TA I0,11,I0,10,I5,9,I5,0,25,7,
20,6,26,5,26,5,27,5,20,6,20,7,I7,0,I6,0
10004 0ATO 11,0,1I,0,13,0,14,0,15,0,13
,9,13,10,13,11,13,1I,13,13,13,14
10005 0ATA 17,14,17,13,17,12,17,11,17,
10,17,9,17,0,10,0,19,0,20,9,20,10,19,1
1,10,11,19,1I,19,13,20,13,20,14
100M6 00T0 2I,14,I2,13,22,1I,II,11,22,
10,22,9,23,0,24,0,I5,9,I0,10,25,11,25,
12,25,13,25,14,I3,12,24,12
10007 0ATA I7,14,27,13,27,1I,27,11,I7,
10,I7,9,27,0,20,0,I9,0,30,9,30,10,29,1
1,20,11
```




Tired of typing?
Take advantage of our finger-saving offer on Page 61.

And now FOR my NEXT trick...

Part VI of MIKE BIBBY's guide through the micro jungle

LAST month we looked at how to create loops using a conditional statement and a GOTO. However, if you just want your micro to do something a fixed number of times, there is another technique you can use, the FOR . . . NEXT loop.

If you have a number of lines of a program that you want repeating for a definite number of times you mark them out by putting the FOR statement at the beginning and the NEXT statement at the end of those lines.

When the micro reaches a FOR it knows it has a loop on its hands. It will repeat the lines (or code, as the professionals say) between the FOR and the NEXT as many times as needed. To do this, the micro needs to use a variable as a counter to keep track of how often the loop has been performed.

In our previous loops we've always used a numeric variable for our counter – *number*. Each time the loop was performed we increased *number* by one until we reached our finishing condition.

In a FOR . . . NEXT loop the variable you use for your counter increases automatically on each repetition of the loop. However, you need to tell the micro where to start and where to finish. To see how we do this in practice, let's look at Program I, which prints out HELLO 10 times.

Lines 30 and 50 mark out the lines we want repeating (line 40). Line 30 reads:

```
30 FOR NUMBER = 1 TO 10
```

The FOR indicates the beginning of the loop. This is followed directly by the counter variable, in this case *number*. After the = sign the 1 to 10 tells the micro to start *number* at 1 and keep on increasing it by one each time the loop is repeated until it gets past 10.

```
10 REM PROGRAM I
20 PRINT CHR$(125)
30 FOR NUMBER=1 TO 10
40 PRINT "HELLO"
50 NEXT NUMBER
60 PRINT "GOODBYE"
```

Program I

The loop is then finished and the micro carries on with the rest of the program, in this case line 60. The outcome of all this is that HELLO is printed 10 times followed by a final GOODBYE.

The micro's thought processes go like this:

```
NUMBER = 1 PRINT "HELLO"
Increase NUMBER
NUMBER = 2 PRINT "HELLO"
Increase NUMBER
NUMBER = 3 PRINT "HELLO"
```

and so on until:

```
NUMBER = 9 PRINT "HELLO"
Increase NUMBER
NUMBER =10 PRINT "HELLO"
Increase NUMBER
NUMBER =11 But the loop is to 10
so go on to line 60
```

Let's learn some jargon:

- *What we've called the counter variable is, not surprisingly, called the loop variable.*
- *The "limits" of the loop – in this case 1 and 10 – are called the loop parameters.*
- *The lines of the code to be repeated are termed the body of the loop.*
- *When you finish a loop and continue with the rest of the program we say that you have dropped out of the bottom of the loop.*

Notice that we've put the loop variable, *number*, after NEXT in line 60. Some Basics let you leave this out – not so the Atari.

All the above has been a rather long-winded explanation of a simple method of getting the computer to do something a fixed number of times. Try the following versions of line 30, and keep a careful count of the number of HELLOs you obtain. Are they what you expected?

```
30 FOR NUMBER = 1 TO 20
30 FOR NUMBER =10 TO 20
30 FOR NUMBER = 0 TO 20
30 FOR NUMBER =11 TO 20
30 FOR NUMBER = 0 TO 11
```

As will be obvious from the above,

the loop variable doesn't have to start at 1. Just to warn you of a possible source of future errors, try changing line 30 to:

```
30 FOR COUNTER = 0 TO 11
```

Assuming that you haven't changed line 50 from the original Program I, you'll get an error message. This is because the loop variable you've specified in the FOR statement *(counter)* doesn't match the one aftar the NEXT *(number)*.

Now try Program II.

```
10 REM PROGRAM II
20 PRINT CHR$(125)
30 FOR LOOP=1 TO 10
40 PRINT LOOP
50 NEXT LOOP
```

Program II

If you recall, the loop paramater increases by one each time the loop is repeated. In a burst of wild originality I've called the loop parameter *loop*. The first time through tha loop, *loop* is 1, so line 40 prints out the velue 1. Then *loop* is increased to 2 since it is the counter, so line 40 prints out 2, and so on.

Once you've worked out what is happening here try adding:

```
60 PRINT LOOP
```

The new line prints out the velue of *loop* after the loop has ended. Can you explain the result?

```
10 REM PROGRAM III
20 PRINT CHR$(125)
30 FOR LOOP=1 TO 10
40 PRINT LOOP,LOOP*LOOP,LOOP*LOOP*LOOP
50 NEXT LOOP
```

Program III

Program III prints out the squares and cubes of the numbers up to 10. Rathar nice isn't it? Of course, there's no need for you to stop at 10 – try increasing it to 100. That's the good thing about loops – you can get the micro to do a considerable amount with very little coding on your part. Progrem IV will print out whatever multiplication table you want.

Can you alter line 60 of Program III so that the output starts with a 10 and decreases to 1?

```
10 REM PROGRAM IV
20 PRINT CHR$(125)
30 PRINT
40 PRINT "Which table do you want ?"
50 INPUT NUMBER
60 FOR LOOP=1 TO 12
70 PRINT LOOP;" multiplied by ";NUMBER
;" is ";LOOP*NUMBER
80 NEXT LOOP
```

Program IV

Now try running Program V.

```
10 REM PROGRAM V
20 PRINT CHR$(125)
30 PRINT CHR$(65)
40 PRINT CHR$(66)
50 PRINT CHR$(67)
```

Program V

Even if you don't fully understand what's going on, I bat you can still guess what

```
PRINT CHR$(68)
```

would give you!

CHR$ stands for "Character String" though I always read it as "Chris", so I would pronounce:

```
PRINT CHR$(85)
```

as "print Chris eighty-five". The code number can be stored in a variable, so:

```
NUMBER = 65
PRINT CHR$(NUMBER)
```

will work. You see, every character you can put on the screen has its own code number. The code for A is 65, for B is 66 and so on. CHR$() takas the code and turns it into a character string – that is, a string a single character long.

These numbers have been standardised in a table called, rather grandly, the American Standard Code for Information Interchange. It's known as Ascii – pronounced "Askey" – for short. If, however, like me you can never make head nor tail of tebles of information, you'll be glad to know that you can use a Basic word called ASC( ) to tell you the number, or Ascii code, of the character you're interested in.

You just put the letter you want inside the brackets – in quotes of course, as we always do with strings. For example, we ask the micro to print out the code for A with:

```
PRINT ASC("A")
```

which, if you remember to press Return (and I'm not going to ramind you from now on!), will give you 65, the code for A. ASC stands for Ascii, so read the example above as "PRINT Askey A".

```
10 REM PROGRAM VI
20 PRINT CHR$(125)
30 DIM STRING$(1)
40 PRINT "A letter ?"
50 INPUT STRING$
60 PRINT "ASCII code for ";STRING$;" i
s ";ASC(STRING$)
70 GOTO 40
```

Program VI

Program VI generates the Ascii code for the character you input. Try inputting a string of more than one character and see what happens. Program VII shows the printable Ascii codes between 32 and 122. Thera are others, but for the moment we'll ignore them. Notice the loop parameters in line 30.

```
10 REM PROGRAM VII
20 PRINT CHR$(125)
30 FOR LOOP=32 TO 122
40 PRINT CHR$(LOOP);
50 NEXT LOOP
```

Program VII

Remember, you don't have to start a FOR . . . NEXT loop with the value 1. However, it's sometimes easier to visualise what's going on if the loop does start with 1, or perhaps zero. For instance, Program VIII prints out the whole alphabet in capitals!

```
10 REM PROGRAM VIII
20 PRINT CHR$(125)
30 FOR LOOP=65 TO 90
40 PRINT CHR$(LOOP);
50 NEXT LOOP
```

Program VIII



However, I prefer Program IX, which performs the same task.

```
10 REM PROGOOM IO
20 PRINT CHR$(125)
30 OFFSET=64
40 FOR LOOP=1 TO 26
50 POINT CHR$(OFFSET+LOOP);
60 NEXT LOOP
```

Program IX

What happens is that, since *offset* is 64 throughout tha loop, line 50 prints out the CHR$ of *loop* plus 64. For example,

for loop =1, CHR$(65) is printed;
for loop =2, CHR$(66) is printed

and so on.

I admit there's a bit of mathematical jiggery-pokery involved, but when I'm dealing with the alphabet the numbers 1 to 26 mean far more to me than 65 to 90.

Granted there's one more line than in Program VIII, but it is far easier to alter the program if, say, I happen to get my figures wrong. To demonstrate this, change line 30 to:

```
30 OFFSET = 96
```

Hey presto, lower case! The codes for the lower case elphabet lie from 97 to 122. Try altering Program VIII to print out in lower case, and you'll see it involves much more work.

Of course you could have had *offset* =65 and *loop* from 0 to 25, but that doesn't mean as much to me – I always think of the alphabet in terms of 26! While we're on the subject of offsets, let's have a look at Program X. This prints the numbers from 10 down to 1 rather than from 1 to 10.

```
10 REM PROGRAM X
20 POINT CHR$(125)
30 FOR LOOP=1 TO 10
40 POINT 11-LOOP
50 NEXT LOOP
```

Program X

What happens is that instead of just printing out the loop variable line 30 subtracts it from 11 first. So:

when loop =1, 10 is printed (11-1)
when loop =2, 9 is printed (11-2)

and so on until:

when loop =10, 1 is printed (11-10).

Here we are using 11 as a sort of offset.

Try using this idea of taking the loop variable from a number to alter Programs VIII and IX to print the alphabet in reverse, Z to A. Before we leave Progrem X, I must make the point that I would normally write line 40 as:

```
40 PRINT (11 - LOOP)
```

The brackets do not effect the outcome. They're used here simply as a "container" for the mathematics. I prefer this tidier approach, even if it's not strictly necessary.

Sometimes, however, the use of brackets is vital. For instance:

```
PRINT (8 - 2) * 3
```

and

```
PRINT 8 - (2*3)
```

give totally different results. What happens is that the micro performs the sums inside the brackets first, then does the rest.

So in tha first example the micro says to itself *8 minus 2 is 6, multiplied by 3 gives 18*, whereas in the second it says *2 multiplied by 3 is 6, subtracted from 8 leeves 2*. So my amended line 40 tells the computer to do the sum first, then print the answer. As I've said, in this casa it's not strictly necessary, but such good habits may prevent you inadvertently dropping into error later.

```
10 REM PROGRAM XI
20 POINT CHR$(125)
30 FOR LOOP=0 TO 10 STEP 2
40 PRINT LOOP
50 NEXT LOOP
```

Program XI

Have a look at Program XI. This prints out the numbers 0, 2, 4, 6, 8, 10. That is, we go from 0 to 10 in steps of 2. Lina 30 holds the secret. You see, we've assumed that in FOR . . . NEXT loops the loop variable – we've always used *loop* – increases, or steps up by one, each time through the loop.

Actually we can tell the computer how much is added each time by tegging STEP onto the end of our previous FOR line. In line 30 we have specified a STEP of 2, so 2 is added to the value of the loop varieble aach time. Change lina 30 to:

```
30 FOR LOOP = 1 TO 10 STEP 2
```

and you get 1, 3, 5, 7 and 9 printed out.

Notice thet 10 is never printed – this is because when *loop* is 9 and you come to NEXT *loop*, you increase it by 2, obtaining 11. This is outsida tha loop parameters, so you drop through the bottom of the loop – thet is, the loop ends. You can actually use tha idea of STEP to *decrease* the loop variable – you just use a negative STEP.

Program XII uses this technique to print out the numbers 10 down to 1, fer mora simply than in Progrem XI.

```
10 REM PROGROO XII
20 POINT CHR$(125)
30 FOR LOOP=10 TO 1 STEP -1
40 POINT LOOP
50 NEXT LOOP
```

Program XII

Notice that the loop parameters now go from 10 to 1. The larger number comes first, since we ere decreasing the parameters each time. Adding –1 is equivalent to taking 1 away. You don't even have to increase STEP by whole numbers. To prove it, try changing line 30 of Program XII to:

```
30 FOR LOOP = 1 TO 10 STEP 0.5
```

Can you see what's happening?

● *Now that we've covered the fundementals of loops we'll continue next month by using them in a veriety of ways.*

YOU could win a 130XE – and lots more – in our great free contest!

THIS month *Atari User* is giving away a super bundle containing the recently launched Atari 130XE personal computer and a 1050 disc drive plus a box of blank discs – all by courtesy of Compumart, the newly formed and rapidly expanding Atari mail order company based in the Midlands.

And to go with it we're offering five software packages from US Gold, one of the major software houses for the Atari.

Join in this simple-to-enter competition and you could be lucky enough to have this sleek, stylish new machine with its 128k RAM at your fingertips.

And entering couldn't be easier. All you have to do is to list, in order of priority, the points on the coupon that you consider to be most important in a new home micro.

Then use your flair to write a short slogan of not more than 20 words that would be suitable for a television advertisement for the 130XE.

FIVE software packages from US Gold – Blue Max, Drop Zone, Pole Position, Spitfire Ace and NATO Commander.

Your free contest entry form

A	Microprocessor speed.	1	5	
B	Compatibility with other models			
C	Memory available.	2	6	
D	Good sound capabilities.			
E	Integral language.	3	7	
F	Software support.			
G	I/O serial port fitted	4	8	
H	Full range of peripherals.			

My slogan is (not more than 20 words)

_____

_____

_____

_____

Name _____

Address _____

_____

_____

Post to: Atari 130XE Contest, Atari User, Europa House, 68 Chester Road, Hazel Grove, Stockport SK7 5NY.
To arrive not later than October 31, 1985



How to use that extra 64k

IF you happen to be one of the fortunate onea who hee been forced by e wife who wanta to keep you quiet into buying the new Atari 130XE then you mey know that a new DOS is available which allowe ue to uee the extra 64k of RAM as a RAM-disc.

Yes, it's true, good old DDS 2.0 has been upgraded to DDS 2.5 for the 130. "What's the .5 for?" I hear you ask.

Well, the DOS 2.0 screen format and functions have been kept almost the same, but this version comes with an extra file called RAMDISK.COM.

When you boot the disc DOS 2.5 looks for and loads this file before it looks for the AUTORUN.SYS file.

When the boot process has finished and control has been passed to Basic, assembler or to your application program, you heve at your disposel an extra "disc drive" accessed with the device nema D8:filename.ext.

Good, eh! Instead of saving your progrem to the disc avery 10 minutes (just in case you crash) you ere able to seve a copy to the extra area of RAM.

This D8 drive can be used exactly as a normal drive, loading, saving and even opening e fila to get or put bytes from or to.

During the process of programming with most assemblers, for example, you oftan have a need to "INCLUDE" a number of disc files within the code at assembly time. How about, instead of having these files on a disc, heva them in RAM end call them by changing the code to .INCLUDE #D8:file . . .

Think ebout it. All the simplicity of

MICHAEL KING presents a simple way to take the strain out of disc filing

including library files with the speed of a machine code byte transfer routine. Let me tell you, it speeds up the assembly stage no end – and keeps that disc from spinning, too.

Let ma explain whet this little program does. Type in the Basic listing exactly as shown. After saving it (please), type RUN.

The program will check your typing end if you just happen to have made a few mistakes in the data you have entered the appropriate messege will be printed end the offending line will be listed for alteration.

Insert a DDS 2.5 disc with RAMDISK.COM into drive 1 when esked to, and press Return. An AUTORUN.SYS file will be written to the disc.

Now that has been dona, let me tell you how to use the program.

If you have a number of files on disc that you regularly use – utilities, listed subroutines or your INCLUDE files for example – how nice it would be if they were already on the RAM-disc efter the boot process has done its bit. Well it seves copying them over one at a time, doesn't it?

All you heve to do is renama all the files you wish to be transferred to drive 8 with the extender .D8. Quite easy to remember isn't it?

Now whan you boot up using this disc – it must have RAMDISK.COM on of course – ell of your filas will be moved into RAM just waiting to be used.

```
1 REM  DOS FILE TRANSFER PROGRAM
2 REM       by Michael (mlod) King
3 REM
4 REM
10 GRAPHICS 0:POKE 752,1:POKE 710,146:
PASS=1:? "      DOS FILE TRANSFER PROGR
AM"
20 CHK=0:RESTORE :IF PASS=1 THEN POSIT
ION 12,10:? "CHECKING LINE":GOTO 40
30 POSITION 12,10:? "WRITING LINE "
40 FOR LINE=1000 TO 1440 STEP 10
50 POSITION 16,12:? LINE
70 FOR BYTE=1 TO 10
80 READ NUM
90 CHK=CHK+NUM
100 IF CHK>999 THEN CHK=CHK-1000
120 IF PASS=2 THEN PUT #1,NUM
130 NEXT BYTE
140 READ CHECK
150 IF CHECK<>CHK THEN ? "ERROR IN DAT
A":POKE 752,0:LIST LINE:END
160 NEXT LINE
170 IF PASS=2 THEN ? :? "AUTO008.SYS C
OMPLETE":END
180 ? :? "INSERT DESTINATION DISK AND
HIT A KEY";:POKE 764,255
190 IF PEEK(764)=255 GOTO 190:? CHR$(1
56)
200 PASS=2:OPEN #1,8,0,"D:AUTORUN.SYS"
210 GOTO 20
220 REM
230 REM
1000 DATA 255,255,0,32,251,32,169,12,1
57,66,229
1010 DATA 3,76,86,228,187,74,3,169,0,1
57,182
1020 DATA 75,3,169,3,157,66,3,76,86,22
8,48
1030 DATA 24,169,212,109,12,133,212,10
5,213,105,394
1040 DATA 0,133,213,96,169,177,133,212
,169,33,729
1050 DATA 133,213,96,60,49,50,42,46,00
,06,550
1060 DATA 155,32,32,32,32,32,32,32,32,
32,1
1070 DATA 32,32,50,49,50,177,170,179,1
08,101,135
1080 DATA 182,183,184,174,196,184,32,1
25,84,114,593
1090 DATA 97,110,110,102,101,114,108,1
10,103,32,582
1100 DATA 102,108,108,101,125,32,110,1
12,32,82,486
1110 DATA 65,77,32,50,73,83,75,32,50,4
6,94
1120 DATA 155,166,0,0,230,240,2,162,0,
189,125
1130 DATA 32,141,69,3,169,01,141,68,3,
169,91
1140 DATA 11,141,66,3,169,35,141,72,3,
169,301
1150 DATA 0,141,73,3,32,86,228,162,16,
32,674
1160 DATA 0,32,162,10,169,32,157,09,3,
```

```
169,403
117A DATA 47,157,AA,3,1A9,6,32,A,32,32
,37
118A DATA 38,32,162,16,169,6,157,68,3,
169,A54
119A DATA A,157,73,3,1A9,11,157,72,3,1
66,664
11AA DATA 212,1A7,6A,3,165,213,157,69,
3,32,743
121A DATA 86,228,16A,1,177,212,201,32,
208,6,A4
1220 DATA 32,24,32,76,176,32,32,38,32,
169,697
123A DATA 49,141,A7,32,1AA,2,177,212,1
57,67,757
124A DATA 32,208,192,11,2AA,246,160,3,
1A5,66,AA
1250 DATA 32,2A1,32,24A,A,208,192,11,2
52,32,260
126A DATA 176,33,24A,3,7A,242,32,1A9,4
6,153,430
127A DATA 66,32,169,68,153,67,32,169,5
6,153,395
12AA DATA AA,32,169,1A5,153,69,32,162,
16,32,2A3
129A DATA A,32,162,16,169,66,157,6A,3,
169,125
13AA DATA 32,157,69,3,1A9,4,32,A,32,4A
,679
1310 DATA 3,76,52,33,206,24A,2,96,162,
A,549
132A DATA 169,9,157,65,3,169,55,157,6A
,3,405
133A DATA 169,32,157,69,3,169,5A,157,7
2,3,206
134A DATA 32,86,22A,162,16,1A9,1A1,157
,68,3,368
135A DATA 169,34,157,A9,3,169,7,157,66
,3,202
136A DATA 169,254,167,73,3,32,A6,22A,1
65,4A,4A9
1370 DATA 141,11A,32,16A,41,141,117,32
,169,56,419
1380 DATA 141,A7,32,162,1A,32,0,32,162
,1A,79
139A DATA 169,66,157,6A,3,1A9,32,157,A
9,3,972
1400 DATA 169,A,32,0,32,162,16,169,11,
157,736
141A DATA 80,3,169,161,157,68,3,169,34
,157,723
142A DATA 69,3,173,116,32,157,72,3,173
,117,638
143A DATA 32,157,73,3,32,86,22A,32,24,
32,337
144A DATA 76,223,32,224,2,225,2,11A,32
,A,271
```

York Computer Centre

7 STONEGATE ARCADE
YORK
TEL: 0904 641862

MEMORY UPGRADES!
600XL TO 64K 59.95
600XL TO 128K 89.95
800XL TO 128K 59.95
800XL TO 256K P.O.A.

* * *

ATARI 520 ST 749.90
NOW IN STOCK!

* * *

SOFTWARE FOR ATARI
UP TO 50% OFF!
100'S OF TITLES

* * *

RING FOR DETAILS

WOOTTON COMPUTERS

FOR SPECIAL OPENING OFFERS PLEASE PHONE		Our Price
520ST 512k Computer + 3.5" Disc Drive 500k		
+ Hi-Res Mono Monitor	£749.99	P.O.A.
ALL ST BUSINESS AND GAMES SOFTWARE TO BE AVAILABLE AT THE LOWEST PRICES		
130 XE 128k Computer	£159.99	£130.00
800XL 64k Computer + Owl(cart) + Joystick	£147.97	£85.00
1010 Program Recorder	£34.99	£29.99
1050 Disc Drive + DOS 3	£199.99	£149.00
800XL + 1010 cass. + Invt. Prog. + Pole Position + Joystick	£137.98	£93.95
800XL + 1050 Disc Drive + Home Filing Manager + Pay Off Adventure + Game Master Disc (9.95)	£259.94	£240.00
130XE + 1050 Disc Drive + Home Filing Manager + Pay Off Adventure + Game Master Disc (9.95)	£299.95	£295.95
Printer Interface	£89.95	£79.95
HCS PERIPHERALS		
Letter Quality Daisywheel Printer	£299.99	£233.00
Mannesmun Tally MT 80 + (180cps)	£249.95	£219.95
CX77 Touch Tablet + Atari Art Soft	£49.95	£36.95
850 Interface	£99.99	£89.95
1020 Printer Hi Res		£79.95
HCS SUFFWARE		
Galaxian	£9.99	£3.45
Lone Raider	£9.99	£3.45
Pengo	£9.99	£3.45
Pole Position	£9.99	£3.45
Gun/Asteroids/Crazy Copter/Kingdom at		£6.95 each
Special Discounted selected software from		£5.95
Space Invaders	£9.99	£3.45
Donkey Kong Jnr	£14.99	£13.99

All Atarisoft software available at discount prices. Please phone for full details of stocks.

EDUCATION/PROGRAMMING		
Assembler Editor	£22.99	£20.99
Conversational French/or Spanish	£22.99	£20.99
Conversational German/or Italian	£22.99	£20.99
Maths 'O' Level Course Year 1 4	(cass) £9.95	£12.95 (disc)
Maths 'O' Level Course Year 5 Revision	(cass) £9.95	£12.95 (disc)
HOME/BUSINESS		
Home Filing Manager 1(disc)	£24.99	£14.99
C O C Discs (SS/DD) 10 in box		£19.99
Memorex Discs (SS/DD) 10 in box		£19.99
Sectured Discs 10 in Library Case		£19.99
Blank Cassettes 10 of C20		£5.00
Unibox Holds 80 Discs		£10.95
"Wood" Style Disc carrier for 80 discs		£18.95
U.S. Doubler	£79.99	£79.99
Trak Ball	£19.99	£17.99

If your disc costs use the 8-side. Disc Notcher £8.99

All Subject to availability All prices inc. VAT P&P extra please enquire

116 EDLESTON ROAD, CREWE,
CHESHIRE. 0270-214118

A money-saving special offer from ATARI USER

Miracle modem + Software + Interface ONLY £195 Save £20!

Now's the time to join the communications revolution!

Price includes VAT, post & packing

IT'S by far the fastest growing field in micro-computing. All over the world micros are talking to each other over the telephone line. As well as to the ever increasing number of public and private databases, bulletin boards – and even giant mainframe computers.

We want all *Atari User* readers to share in the new technology that makes all this possible. So we're offering a unique starter pack at an unbeatable price. It gives you everything you need to get in touch with the big wide world outside.

Modem/Software/Serial Interface.

The modem is the amazing Miracle Technology WS2000. One of the most powerful on the market, it's simplicity itself to use. Just plug it into a standard British Telecom jack and you're away!

The package also features the superb Datari serial interface, which links the modem directly to the Atari's peripheral port without the need for the 850 serial interface.

The best hardware deserves the best software to drive it, and with the specially written Multi Viewterm program the package is complete. It supports all the standard baud rates – 1200/75, 75/1200, 1200/1200 half duplex and 300/300 full duplex.

Your *Atari User* package will allow you to talk directly to other computers, to send your own telex messages, to go tele shopping – even to download free software programs directly into your Atari.

You will be able to join Micronet/Prestel which will immediately open up to you a vast menu of 750,000 pages of information – instant world news, sports, holidays, hotels, train and airline timetables, all regularly updated.

And you can become one of a growing number of enthusiasts who are joining MicroLink, the giant database set up in conjunction with Telecom Gold.

But first, send for the Miracle package – and enter the fascinating, limitless world of communications!

Use the order form on Page 61

...and this is the magazine to tell you all about it!

Sales of modems are soaring. The number of on-line databases and bulletin boards grows and grows. TeleLink is THE way to keep fully informed of the rapid changes now taking place in the world of communications.

TeleLink No. 1

Special supplement: Guide to Microcomputing on Prestel. Contains hundreds of page numbers covering games, education and business and utility programs for the BBC, Apple, Commodore and Spectrum. Plus hints, tips and reviews of comms products.

TeleLink No. 2

Special supplement: Guide to Communicating with your Micro. All about user-to-user communications, protocols, how modems work, an introduction to networking and PSS. Plus a guide to 39 modems listing all their special features.

TeleLink No. 3

Special supplement: Guide to Bulletin Boards in the UK. An in-depth survey of what bulletin boards offer and what they cost, how to access them, interviews with 12 leading sysops. Plus a complete listing of 39 bulletin boards, pinpointed on a map of the UK.

TeleLink No. 4

Includes the first Teletext & Viewdata News, highlighting all the latest industrial news. Plus features on financial, legal and educational databases, start of a guide to Knowledge Index, how to work out your phone bill and a survey on portable micros with comms facilities.

TeleLink No. 5

Special supplement: Guide to Communications Software. A survey of 37 communications software packages for 11 of the most popular micros. Plus advice on viewdata graphics, description of the de facto standard for UK bulletin boards, Xmodem, and online humour from Punch editor Alan Coren.

TeleLink No. 6

Special supplement: Guide to teletext page design. A leading expert tells how to achieve eye-catching viewdata graphics. Plus coin-operated Prestel, setting up educational viewdata systems, using packet radio to cut phone bills, on-line credit reporting.

ORDER FORM

Please supply the following:

		(✓)		£ p
Subscription to the next 12 issues of TeleLink	£1 25	☐	5001	
(Commencing with issue No ____)				
Issue 1 (Nov/Dec 1984)	£1 25	☐	5005	
Issue 2 (Jan/Feb 1985)	£1 25	☐	5006	
Issue 3 (Mar/Apr 1985)	£1 25	☐	5007	
Issue 4 (May/June 1985)	£1 25	☐	5008	
Issue 5 (July/Aug 1985)	£1 25	☐	5009	
Issue 6 (Sept/Oct 1985)	£1 25	☐	5010	
			Total	

☐ Cheque enclosed made payable to Database Publications Ltd

☐ Debit my credit card account

Access ☐☐☐☐ ☐☐☐☐ ☐☐☐☐ ☐☐☐☐

Visa ☐☐☐☐ ☐☐☐☐ ☐☐☐☐ ☐☐☐☐

Name _____ Signed _____

Address _____

_____

_____

Post to: TeleLink, Database Publications, 68 Chester Road, Hazel Grove, Stockport SK7 5NY.

Phone orders 061-480 0171
Telecom Gold Mailbox No. 72 MAG001
Prestel Key *89 Mailbox No. 81456B383

Don't forget to include your credit card number and full address.

Danger is the name of the game

BRILLIG explores the fascinating world of Infocom adventures

OVER the last few months I have endeavoured to give as broad a perspective as possible on the various types of adventures available, as well as try to give an idea of some of the problems associated with this type of game.

In doing this some recurring names have been Scott Adems (Adventure International), Level 9 and Infocom. To date the first two have predominated for two principal reasons.

Firstly they supply entertaining adventures which tend to be both well written and of varying degrees of difficulty. Secondly they are among the most affordable of adventures, being cassette-based, thus giving them a wider audience.

Infocom stands alone from other adventure producers, and as such deserves to be considered separately. In truth comparisons are not easy, although they can be made with the other adventures, but I think to be fair Infocom adventures are the standard to which many aspire, but few achieve.

Infocom are relatively expensive disc based text-only adventures – always have been, and hopefully always will be. One of their advertisements showed a picture of a human brain with the caption "The most powerful graphics computer known to man" or words to that effect.

No blocky pictures of woods and a cottage for Infocom. You are plunged into the most detailed and exact prose available to adventures. Screens upon screens of text are revealed as you explore the carefully charted worlds which they bring you.

The drawback is that unless you have a disc drive Infocom games are not for you. Brillig says that this should inspire you to go out and buy your disc drive now!

As stated, Infocom adventures are not cheap. However at least the package shows some care and imagination, rather than a video case with a printed instruction sheet and the game cassette.

Hitch-Hikers Guide to the Galaxy, for example includes a microscopic space flaat and peril-sensitive sunglasses for the player's use in moments of extreme danger – the glasses have opaque black lenses.

This should be standard issue in any Infocom game, where danger is the name of the game – be it from arrest for a murder that only you know you didn't commit, to being disciplined in Planetfall for failing to swab the decks correctly shortly before the spaceship explodes.

Variety is the essence of the range. Consider the Zork Trilogy, so staggeringly popular that they have gone the opposite route to most software and had book versions made from them.

Zork charts a huge underground dungeon in three stages and, while bearing some similarities to Colossal Adventure, shows far more imagination in scene setting.

Part of the reason for this, although by no means all, is the use of disc storage, which allows your Atari to pull off new data all the time as you progress, whereas the majority of other games, being cassette based, do not have that advantage.

It is, however, the use to which they put the space available that makes games so special. It is all very well having 7,000 plus locations but if they are all the same it makes for a tedious exploration.

Similarly, there seems to be a school of thought in adventure writing that in order to create atmosphere all that is required is a liberal sprinkling of assorted adjectives and that is it.

Infocom adds atmosphere, not only by what is included, but also by what is omitted.

On the inclusion side it allows Infocom's programmers to develop characters and responses which leave other games characters looking positively flat.

For instance, Sergeant Duffy, not only "slaps you right back" if you should strike him – a temptation most players of Witness succumb to – but also "it hurts too", giving Duffy a strength and depth which has you wincing at his grip on your forearm as he leads you to the station.

Try following Veronica at her mansion party in Deadline to try to catch a glimpse of her real murderer as she goes off to her doom.

You are prevented, not by an abrupt, clearly inserted device such as "Veronica disappears and you cannot see her" but by a clumsy butler in a gorilla suit who entangles you with another guest, drags you to the floor, and then obscures your view long enough to prevent you from following your fated hostess.

In Planetfall the ambassador who passes by in a corridor is not only there for window dressing, he hands you a leaflet extolling the virtues of the products of his home planet.

I cannot recommend Infocom adventures highly enough. While not for the out-and-out beginner, they are the sort of games that any player can enjoy, as much for the things he gets



wrong as for those he gets right, and still have a bundle of laughs on the way.

Time for that inadvertent error now, in our glitch of the month competition. Following my look at mazes in Escape from Pulsar 7, by Brian Howorth, last month, it seems appropriate that this month's logic bomb comes from the same Mysterious Adventures stable in Waxworks.

Simon Ashford, from Kings Norton in Birmingham, points out that once you are submerged underwater having gone through the airlock, then strike a light, the matches still work.

A medium T shirt is on its way to you Simon (the penalty for not including your size) and keep those glitches coming.

Got to keep these edventure writers on their toes.

Lords of Time crops up again, and SAC Gratton from RAF Cottesmere is having trouble with the Mammoth in Time Zone 2.

Well, if you gather up some wood and petrol and put your faith in Level 9's own brand of matches (has anyone tried these underwater yet?) you should not only get rid of a giant-sized problem but also find something left behind that will give you a nice warm feeling.

How to get past the brontosaurus? Remambering that he is vegetarian may get you out of the pit, but you need to reflect on your acquisitions to get past him.

Lastly, to escape the gladietor, some footwear from showing faith in the temple is all you need.

Level 9 is just about to release Red Moon for the Atari at £6.95. In fact by the time you've read this the game should be available, as a few last-minute problems were being ironed out when I spoke to Level 9 the other day.

So far all Brillig has received is a balloon end a poster, but the news from the Level 9 camp is that this will be their first Atari game with graphics.

Given the Atari graphics capability, they had better be pretty good or I should imagine that the protests will be long and loud.

Pete Austin tells me that if the response is good they may well backtrack on the graphics for Ateri versions. Level 9 is also expressing an interest in converting games for the ST renge if it takes off.

But don't hold your breath. The same was said for the QL, and look what happened when that hit the marketplace.

Not such happy news from Adventure International, who at the time of going to press still could not supply a publication date for Questprobe 3, The Fantastic Four, originally scheduled for July.

Next month I'll take a quick look at Wizard of Akryz and Red Moon if it arrives. Don't forget those glitches!

From . . .

Computer Support

"THE UTILITY SPECIALISTS"

A fine selection of software and hardware directly from its makers Something for every ATARI® enthusiast

ULTIMON! **£49.95**
A built in machine code monitor capable of stopping any program on the fly, functions include DISPLAY/ALTER REGISTERS/MEMORY, MOVE MEMORY, FIND STRING, SINGLE STEP, DISASSEMBLE MEMORY, FORMAT DISK, READ FROM DISK, WRITE TO DISK, and many more. This is the most powerful and the lowest priced on-board monitor available for the ATARI®. don't take our word for it, try one!

80 COLUMN PACK! **£69.95**
A built in 80 COLUMN text mode enabled by holding the [SELECT] key down during powerup. Great for word processors, works on a normal TV. Compatible with most software.

TRIPLER! ***NEW* £18.95**
A high quality printed circuit board allowing the ATARI® XL/XE range to have 3 separate operating systems on one machine, selectable before powerup. Very easy installation.

XOS
A completely revised operating system for the ATARI® XL/XE range. Compatible with more software than the original XL/XE O.S. with XOS you'll probably never have to use the TRANSLATOR again. XOS also has some totally unique functions including CARTRIDGE OVERIDE, FORCED WARMSTART, ANTI-COLDSTART, FASTER CASSETTE, HOLD [OPTION] TO ENABLE BASIC and many more. **XOS comes free with 80 COLUMN PACK and ULTIMON (XL/XE versions only)**

XOS TRANSLATOR ***NEW* £9.95**
The operating system described above in the form of a TRANSLATOR. This means you can have all the functions of XOS when you want them.

THE GAP! **£29.95**
Fill the 4K gap in your 400/800 with this hardware modification, once fitted to a 48K machine there will be 52K of user RAM. Can be used on 16K & 32K machines. Plug in installation.

OVER-WRITE! ***NEW LOW PRICE* £9.95**
Use the other side of all your disks, also saves removing the write protect label on a disk you simply want to update. Installation very simple.

ROM EMULATOR! ***NEW LOW PRICE* £24.95**
Develop and debug cartridge software quickly and effectively. Just write to a specific location then the cartridge RAM area becomes ROM, can also be used to backup cartridges. For 8K & 16K programs can be switched out if not required.

BAD SECTOR **£18.95**
A hardware modification. Write a bad sectors to any disk, can be used for custom creation of bad sectors or to backup some protected disks. Comes complete with sector writer and speed checking software.

PORTPRINT **£29.95**
Run a standard centronics compatible parallel printer from the joystick ports. Includes a relocatable handler, runs with most boot programs. Complete with lead.

PRINTER INITIALISER ***NEW* £9.95**
An autorun/batch file that automatically flushes the printer and presets printer defaults such as font styles etc. Completely reprogrammable.

SUPER DISASSEMBLER **£24.95**
Disassemble any disk, cassette or cartridge. Uses XL system labels, separate input to pre-determine data bytes. The end result file can be customised then re assembled using an assembler.

FILE LOADER **£14.95**
A self booting menu and mini DOS system which purely loads files, saves at least 60 sectors on every disk.

***BOOT LOADER** **£14.95**
A self booting menu, compacts disks and cassettes to a file format, can be written to any disk. Utilities include TAPE to DISK, DISK to TAPE, DISK to DISK.

***DISK BACKUP** **£18.95**
Density smart, fully automatic.

***128K DISK BACKUP** **£18.95**
Same as above but specifically for the extra memory of the 130XE.

**** Sold subject to not infringing Copyright.***

OTHER PRODUCTS AVAILABLE *MAILING LIST £12.95, BIORHYTHMS £7.95, ZAPPING ZOMBIES £6.95, ULTILITY PAC ONE £8.95, UTILITY PAC TWO £8.95, UTILITY TAPE ONE £7.95, MACRO LIBRARY £12.95, CARTRIDGE BACKUP £15.95, CASSETTE BACKUP £9.95 and SERIAL I/O PLUG £3.99*

USER GROUP DEMONSTRATIONS ARRANGED
We are continually adding new and exciting products to our range please send S.A.E. for more details.

ATARI® is a trademark of ATARI CORPORATION

Mail order only, to order send cheque or postal order to:

COMPUTER SUPPORT LTD

26 Seacourt Road, Abbey Wood, London SE2 9UW

Tel: 01-311 7339

All prices include postage & packing. Same day dispatch

MicroLink
in association with
TELECOM GOLD

No. 2 October 1985

NEWSLETTER

Speeding the mail

THREE years ago the old-style telegram was replaced by the Telemessage. You dictated it by phone and you were guaranteed next day (usually breakfast time) delivery.

The only snag was the cost – £3.50 for up to 50 words.

Now, thanks to MicroLink, a new chapter starts in the Telemessage story. Any home or business micro user can send a Telemessage from his own keyboard in one simple operation.

And the cost? Just £1.25 for up to 350 words, or £1.95 for guaranteed first-post delivery.

Your recipient receives the message exactly as you typed it in – neatly printed out on a letter-quality printer and delivered in a distinctive yellow and blue envelope.

Businesses are expected to be the biggest users of the MicroLink Telemessage service. With the unreliability of first-class post, the promise of next day delivery is a big plus.

Home users will be attracted by the illustrated cards that are available for such occasions as weddings and birthdays – the modern equivalent of the old Greetings Telegram but far more convenient.

There are 16 cards in all, and they cost an extra 65p.

Telemessages (but unfortunately not the colourful cards) can also be sent to any address in the USA, from Alaska down to Hawaii. And other countries will soon be joining the system.

Meanwhile, for the rest of the world you can use MicroLink to send an international telegram, again at a cheaper rate than using the phone.

TELEMESSAGES CHARGES

	UK		USA	
	MicroLink	Phone	MicroLink	Phone
Telemessage 1 *Delivery following day (guaranteed)*				
Up to 50 words	£1.95	£3.50	£2.95	£5.75
51-100 words		£5.25		£8.25
101-150 words		£7.00		£10.75
151-200 words		£8.75		£13.25
201-250 words		£10.50		£15.75
251-300 words		£12.25		£18.25
301-350 words		£14.00		£20.75
Telemessage 2 *Delivery following day (not guaranteed)* Up to 350 words	£1.25	N/A	N/A	N/A
Multiple Telemessages *Same text sent to more than one address.* First message charged as above. Each additional address	£1.30	£1.30	£2.50	£2.50
Special occasion cards	65p	65p	N/A	N/A
Direct response *A reply paid envelope included with your message*	30p	30p	N/A	N/A

INTERNATIONAL TELEGRAMS CHARGES

	MicroLink	Phone
Flat rate basic charge	£1.75	£2.00
Each chargeable word:		
Eire	23p	23p
Bands 1-4 (including all Western and Eastern Europe and North America)	32p	32p
Band 5	38p	38p
Delivery on ornamental form	60p	60p

- *The maximum length of a Telemessage is 350 words or 35 lines of text which is approximately equivalent to an A4 page of text.*
- *The addressee's name and full postal address is free of charge.*
- *All prices are quoted ex VAT.*

Keeping in touch

FOUR Manchester lads hoping to follow the same route to stardom as another quartet from Liverpool are planning to use MicroLink to keep them in touch with their home base during their tours of Britain and the continent.

Pop group So What will be armed with a portable micro and acoustic modem as well as guitars and drums when they set off for a round of gigs.

MicroLink's electronic mail service will keep them right up to date with what's happening back at the "office".

Getting bigger!

THE host of new services now becoming available have been made possible by MicroLink being given its own dedicated £500,000 mainframe computer at Telecom Gold.

It now has the capacity to expand considerably, and lots of additional services are presently in the planning stage which will enable MicroLink members to participate in the many exciting developments now taking place in the world of communications.

YOUR chance to join MicroLink – turn to Page 25

A NEW CLASSIC

FROM PAUL WOAKES
AUTHOR OF ENCOUNTER!

YOU CHOOSE THE ACTION IN MERCENARY

Mercenary – a unique combination of flight simulation, adventure and arcade fun. You choose the action.

There is complete freedom of movement in a truly three-dimensional vector-graphic environment. Graphics of exceptional speed create a very realistic experience.

You'll never play the same game twice. Random elements attempt to seal your fate. Your interaction is crucial.

Mercenary presents an absorbing challenge that you will accept again and again.

MERCENARY
ESCAPE FROM TARG

Fly above the planet Targ in a variety of craft. Investigate the multitude of structures on the planet surface in your quest for essential supplies. Search the mysterious subterranean complex in pursuit of your fortune.

Become embroiled in the continuing conflict between the Palyars and Mechanoids. Accept their paid assignments or work independently to gain wealth.

You only have one true friend – the ever-reliable Benson, an almost human PC, who guides you in your travels.

Pursue your objective as you will : To succeed you have to escape from Targ.

NOVAGEN

INITIAL RELEASE
FOR COMMODORE 64 ATARI 48K 800 XL 130 HE
CASSETTE £9.95 DISK £12.95

NOVAGEN SOFTWARE LTD: SALES 142 ALCESTER ROAD BIRMINGHAM B13 8HS

Trying to program without a tape

I AM glad to find at last an Atari magazine in the local shops.

It has teught my family mora than what we thought the computer could do

We bought the Atari 800XL last Christmas and we were most upset when we saw it on sale with the recorder for the same price.

We do not own a recorder yet as they are so expensive on their own.

The problem we are facing at the moment with the programs in your magazine is that our computer will not take them.

We have a lot of errors when we finish the program, yet we reprint the errors that they show at the end of the program when we type RUN and press Return.

We reprint the lines that show as errors and the computer takes them but the program will not

Also if we are lucky enough to print the program without any errors, like Submarine, it will work for a few minutes then jam.

We have tried pressing Return but nothing happens. The only way we can do it is by pressing Reset then typing LIST. When we do this it starts the list then jams halfway through, so we have to do the same thing again.

Sometimes it will not reproduce the list and will not allow you to print anything – not even move the cursor.

When this happens – which is most of the time – we have to switch off and start again.

We have come to the decision that it must be the computer. Could you please let me know if it is, as it is still under guarantee.

Also I would like to see more about errors in your magazine as the book we had with the computer doesn't explain what to do in the way we would understand. – **L. Williams, Penbrey, Dyfed.**

● The fault is either in the computer itself – try taking it in for service – or in your typing of POKE statements, etc.

We can't imagine life without a disc drive – without even a cassette you have little more than a cartridge games machine, as you are limited to what you can enter in one session.

Please, if you went to get the most from both the computer and the magazine invest in a tape unit – even a second-hend one.

My Logo won't run

I AM very pleased that at last I have found a magazine for the Atari.

I have been reading it each month and I have tried many programs, but in the August issue I could not get any of the Logo programs to run.

I printed: MAKE "WRIGGLE (FD 30 RT 30 FD 30 LT 30 FD 30) and then pressed Return.

I got ERROR – [M] AKE "WRIGGLE etc.

What am I doing wrong? Is it my 600XL that is faulty perhaps? – **Matther Whiting, Maidstone, Kent.**

● It sounds as though you haven't got the Logo cartridge plugged in. Consequently, the Basic interpreter built into your machine is trying to make sense of your input.

It's failing, of course, because it only understands Basic commands, not Logo

Syntax puzzle

COULD you please let me know if programs printed for the Atari in magazines back in 1983 should be able to be used on a new 800XL Atari which I have just purchased?

I tried a couple of them but I kept getting errors. I checked through the lines but could find none.

One of the errors came up with the No. 17 which the Atari Basic book says is a syntax error. Could you tell me what a syntax error is? – **A. Leadbetter, Letchworth, Herts.**

● Although some early commercial software might not run on your 800XL unless you use a translator-type program, we would expect most magazine listings to work.

Certainly all of our listings will work fine on your machine.

A syntax error occurs when you use a Basic command incorrectly. For example, enter:

```
PRINT CHR$(65
```

and press Return

The machine will give you an error message because the syntax requires a closing bracket after the number.

A NEXT without FOR

AFTER buying your magazine last Saturday, not to mention the Atari 800XL to go with it, I first read the instructions and then started to key in Frog Jump.

After a couple of hours at the keyboard I was finished, and when I had taken the precaution of putting it on tape I decided that it was time to start enjoying myself.

So I typed RUN and pressed Return. All I've been able to get since is an "error 13 at line 1200" statement.

Now I have checked and re-checked the program against your listing and it all seems to be in order.

So I wonder if you can tell me if it is an error in your listing or a malfunction in my computer?

Now that I have got rid of the bad part, let me say that I can find no fault with your magazine. Indeed it is written in a way that is easy to understand, even by me.

The sections on Graphics and the piece for Beginners – which I surely am – were both enjoyable and informative – **Mark Disley, Dublin, Ireland.**

● An error 13 means that the machine has encountered a NEXT statement without having previously seen a corresponding FOR statement. Check line 1170 very carefully.

Calling Cornwall

I BOUGHT the July issue of your magazine and was so impressed I placed an order with my newsagent. I also got back issues 1 and 2.

Is there an Atari users group in the Truro area? If so where?

Also, for my stepbrother who also owns an Atari, is there one in the St. Austell area?

When I bought my Atari 800XL in April I had a promise on the Silica Shop order form of an imediate membership in the Atari Owners club, with bulletins and magazines every now and again.

It's now the end of July and since I got my starter pack 2 I've had nothing.

Can you help by informing me as to why this is?

I'm not the only one – my stepbrother has the same problem – **Michael Dunstan, Truro, Cornwall.**

● We don't know of any groups in Cornwall. If there are any, perhaps someone could let us know.

The Owner's Club Monitor only appears quarterly.

Summit of success

AM I your highest reader? The picture shows me reading your fantastic magazine at 3,116 feet above sea level at the top of Helvellyn in the Lake District. Do I win a prize? – **Phillip Abbott, Bradford.**

● You're holding the prize in the photograph! Before we get a spate of photos like this, we ought to warn readers that anything less than Everest won't be printed!

Start off in hex

HAVING bought the last three issues of your magazine I thought I should put pen to paper to congratulate you on them. At last a decent magazine for Atari owners.

I especially liked the disassembler articles in the July and August issues.

As I cannot yet afford the Assembler/Editor cartridge they both come in very useful.

I thought you might be interested in the modifications I have made. It would be useful to be able to enter the start address in hex as well as denary, which is what the modification listing does.

These modifications allow the user to input a hex start address simply by prefixing it with a "$".

One last modification is to add ".NUM$(6)" to the DIMension statement in line 50.

```
160 ? "{By Kevin Edwards}{}"
140 ? "{}"
165 POKE 764,28:? "Enter start locati
on ";
160 INPUT NUM$:IF LEN(NUM$)<1 OR LEN(N
UM$)>0 THEN 140
162 IF NUM$(1,1)="$" THEN 2500
164 TRAP 140:START=VAL(NUM$):IF START<
10^(LEN(NUM$)-1) THEN 140
165 IF START<0 OR START>65535 THEN 140
180 REM ** DELETE THIS LINE **
255 ? :IF PEEK(764)=28 THEN 160
2500 REM *** CONVERT HEX TO DEC ***
2510 NUM$=NUM$(2):N=0
2525 FOR LP=1 TO LEN(NUM$)
2530 IF NUM$(LP,LP)<"0" THEN 2590
2540 IF NUM$(LP,LP)<="9" THEN N=N*16+V
AL(NUM$(LP,LP)):GOTO 2570
2550 IF NUM$(LP,LP)<"A" OR NUM$(LP,LP)
>"F" THEN 2590
2560 N=N*16+ASC(NUM$(LP,LP))-ASC("A")+
10
2570 NEXT LP
2580 START=N:GOTO 165:REM LEGAL HEX NU
MBER ENTERED
2590 ROP :GOTO 140:REM ILLEGAL HEX NUM
BER ENTERED
```

One last thing. I need to be able to detect when the Break key has been pressed in a program I'm working on. Have you any suggestions on how I can achieve this? – **Geoff Bliss, Chelmsford, Essex.**

● See André Willey's article on Page 28 of the August issue for information on disabling the Break key.

Round the clock

HAVING read your article concerning a Defender score I would like to submit my score for the game.

I have clocked the score by exceeding 9,900,000 when the score returns to zero and stays at Level 99.

The game lasted for two days whereupon I finished with numerous men.

I would also like to know if there are any user groups in the Merseyside area or as far as Chester.

I am writing to enquire whether your offer on your published magazine listings will ever be available on cassette as well as disc. I have spent many hours typing in listings which have failed to work through typing errors or bad listings.

Having listings on cassette would be extremely welcome because like most others I do not own a disc drive. – **Peter Berry, Birkenhead.**

● The Liverpool Atari User Group can be contacted c/o Mr Teater, 19 Greffington Crescent, Liverpool L25 9RU.

There is also a Merseyside club c/o Mr R. Gibson, 3 Dunning Close, Upton, Wirral, Merseyside L49 2RH.

Many people have written requesting a monthly tape. This is now available. See the order form on Page 61.

The right connections

I OWN an Atari 800 and need the following information – details of the right cartridge socket connections and details of the cassette socket connections.

I wonder if you, or any of your readers can help?

I have tried writing to Atari but despite enclosing a SAE received no reply.

It's nice to see your magazine on the market, it fills a need. I have found the first two issues very interesting and the adverts have been most useful.

I knew hardware and software were available but never knew where to go before.

It would be great if you could devote at least some space to do-it-yourself add-ons for the Atari as it is such as versatile machine as far as input/output is concerned.

I am convinced it would rival the BBC Micro for serious uses if only details of the connections were available as freely. – **Stephen Fareman, Reading, Berks.**

● You need to get a copy of the "Technical User Notes for the 400/800" from Atari, at a cost of about £17.

They give all details of I/O ports and full circuit diagrams plus software details and the full operating system listing.

Yellow peril screen

I HAVE programmed the enclosed example listing into my computer and saved it on to cassette.

It worked wonderfully, till suddenly a yellow screen appeared, with a white line through the middle.

Shortly afterwards an Error message appeared on the screen, – "Error 141 on line 930".

I have tried various ways to get the program to run past line 930.

But I am defeated. Could you therefore let me know what it is that is stopping the program at line 930?

I suspect that one incorrect statement has been put in.

All my efforts proved one thing – that it is the last part of the line which is stopping the program from running further. – **F.J. Windle, Dukinfield, Cheshire.**

● At least two of the example lines you included with your letter had a "+" in place of a "," which obviously affects the program's operation.

Once you've corrected

these errors that you've introduced the program should work fine.

The future of 16k games?

I OWN a 600XL with 16k memory.

Usually when I go in a shop to get a game 95 per cent of them are more than 16k.

I will have to wait a long time before I get a memory expansion.

Do you think any of the games like Oropzone, Beach Head or Bruce Lee will reduce in memory and come down to 16k?

I hope the makers of these games will think about it. – **Christopher Finn, Borehamwood, Herts.**

● As games get more and more sophisticated, it gets less likely that they'll be crammed into 16k.

If it's games you want, our advice would be to upgrade to a bigger machine.

Incidentally, Drop Zone only requires a 48k machine – US Gold labelled the tape insert incorrectly.

Missing symbols . . .

AS a dedicated Atari user, I was very pleased to see that a magazine has been produced solely for the Atari computer – unlike some others which, although fully explained, carry one Atari listing at most.

However, upon reviewing the August issue I am very distressed to find the listings provided by yourselves to be of bad quality, for example, Fruiti Gambler.

Having tried to input the listing I came across many obstacles which, with regret, I could not overcome.

The main problem is that the graphic symbols used could not be found. I own an Atari 800XL.

I would be very grateful if you could explain at the top of your listings the method for obtaining such symbols as it would make life much simpler for the person trying to input such a program.

Also I would like to point out that I have noticed at the bottom of each listing an advertisement to encourage people to purchase the whole magazine on disc.

I assume this is to save people like myself the aggravation of debugging the programs caused by incorrect interpretation and decyphering of the graphic symbols which is so time-consuming and unnecessary if explained properly – **M. Stinger.**

. . . causing problems

I HAVE just received the August issue of Atari User and was copying out Fruiti Gambler when I got to line 210 and noticed some arrow symbols.

My 800XL does not appear to have these.

Should I have them or can I use something else instead? – **D.A. Cerdy, Exeter.**

● Your 800XL does have these characters. It's just that the lousy "manual" supplied with the machine doesn't mention them.

The arrows are obtained using the cursor keys but entering ESC first, so to get ↓ you type ESC CONTROL =

Press and release ESC then press = while holding down the CONTROL key.

The special characters are often the cause of problems, which is why we prefer contributors to use the appropriate CHR$.

We hope to be printing a complete list of how to obtain these characters.

In the meantime, try experimenting with ESC CONTROL (letter) combinations.

Computer camp

AS a result of Tony Owyer's article in your June issue, not only did I purchase from you the WS2000 modem with Viewterm software, but I am now a trainee at the ITEC which I am enjoying immensely.

The first 'Computer Camp' was held recently and was a great success – all of the children enjoyed themselves very much. I also enjoyed helping Tony and Mike, another student, with the teaching of Logo, which went very well.

There was just one problem that I had when I received my modem and software. That was the Viewterm terminal program, which kept receiving and transmitting garbage. You only need to take a look at the ITEC's Bulletin Board (026B) 522316 to see that I'm not the only one having problems.

However Miracle are apparently working on a new terminal program which will support U/L and O/L on bulletin boards (maybe Xmodem protocols?), and hopefully they will improve the actual terminal part of the program also – **Sean Morels, Convey Island, Essex.**

LET there be keywords

IN your Beginner's section Mike Bibby says "variables shouldn't start with Basic keywords, as they confuse the Atari", and cites:

```
10 PRINTER$="EPSON"
```

as an example.

Because of the way Atari Basic is tokenised, it is actually possible to use PRINTER$ as a variable, even though it does contain a keyword, simply by putting LET in front of it.

```
10 LET PRINTER$=
   "EPSON"
```

is a valid Atari Basic line. So is:

```
15 LET PRINT=
   10:PRINT PRINT
```

The only token where this doesn't seem to work is NOT. Try:

```
20 LET NOTE=
   10:PRINT NOTE
```

and see what happens – **Jack Schofield, Sutton, Surrey.**

● Thanks for setting the record straight, Jack. However we thought LET had gone the way of antimacassars, elephant's foot umbrella stands and the ZX80.

Latest Bulletin

I HAVE seen in past issues of your magazine that you have listed telephone numbers of Atari bulletin boards and I wondered whether you would include mine.

My system is run on an Atari 800, and the bulletin board is called TimeZone. The telephone number is 0244 677978.

It works on a ring-back system, so you have to dial the number and let the phone ring twice, then hang up and call again and the BBS will then answer (300 baud).

The operating times are weekdays 18.30-23.30 and weekends 09.00-23.30 – **Paul Gaulton, Chester.**

ATARI USER Mailbag

WE welcome letters from readers – about your experiences using the Atari micros, about tips you would like to pass on to other users . . . and about what you would like to see in future issues.

The address to write to is:

Mailbag Editor
Atari User
Europa House
66 Chester Road
Hazel Grove
Stockport SK7 5NY

Bomb Run for all

CONGRATULATIONS on an excellent magazine which, from what we've seen so fer, promises to be a great success

I am writing about your Bomb Run geme from the July issue and although I assume you've already had severel letters about it I thought I'd drop you e line anyway.

I keenly typed in the program and ran it on my 48k Atari 800 where it ran without error.

Why am I writing, you might wonder? Because I then swapped this game with my father who had meanwhile been kaying in the Disassembler from the seme issue, and when he tried it on his 16k Ateri 400 he found thet it would not run correctly.

After carefully examining the listing, I made the following alterations which will eneble the program to work on any Atari model.

You'll probably recognise the character redefinition routine from Dave Russell's excellent article – also in the July issue.

Keep up the good work anyway, and perhaps it might be an idea to esk people to state which Ateri machine their progrems ere written and tested on – **Peter Appleton, Liverpool**

```
320 IF P<PE THEN 200
5105 P=PEEK(00)+256*PEEK(09):PE=P+409
5190 POKE P-1,2:POKE P,1
9000 RAMTOP=PEEK(106):POKE 106,RAMTOP-
4
9020 CHBAS=RAMTOP-4:ADDR=CHBAS*256
9060 POKE ADDR+I,PEEK(57344+I)
9160 READ J:POKE ADDR+0+I,J
9300 POKE 756,CHBAS
```

Putting the record straight

THERE are several errors and misconceptions in Bryan Williams' preview of the Atari ST machines in the May issue of Atari User

The Basic interpretar will not be "e new version of Ateri Basic", but Digital Research's Personal Basic, originally developed for the CP/M-86 operating system and supplied to them by Metecomco of Bristol, with presumebly, enhancements for graphics support, etc

Personal Basic was written in BCPL, and therefore will be easy to port on to the ST.

GEM is not an operating system, or "a grephics equivalent of CP/M" It sits on top of TOS, which is really nothing more than CP/M-68k, which is CP/M 2.2 for the 8080/Z80, rewritten in C for the MC68000, so that it is several times the size and isn't any faster.

TOS isn't multi tasking, and won't be for at leest a year or so, when DR hope to produce a version of Concurrent CP/M for the MC68000.

A very serious omission on the ST is the apparent lack of e bus expansion connector, which means that there will be very little, if any, third party hardware add-ons produced for it, although it might be possible to use the hard disc interface port for this purpose.

Actuelly, I think the ST is a very attractive machine, and while too expensive for most home users in this country and Europe, will probably sell well to this market in the States where the everege disposable income is much higher – **L.F. Heller, Newport Pagnell, Bucks.**

Information, please

COULD I heve more information on the Atari 800XL 64k personal computer pack because I am thinking of buying one? – **James Rainbow, Powys.**

● We suggest you go to your local dealer end get a full demonstration.

Alternatively, you could write to Atari for their promotional literature, but it's no substitute for a 'hands-on' test

Smash hit and miss

MY brother and I recently bought an Atari 800XL starter pack with 1010 recorder. We also bought "Atari Smash Hits 3"

When we got home we immedietely loaded e geme and played it. The problem was that the Pole Position cassette would not load

Later thet evening we discovered thet the keyboard was faulty and changed the entire pack.

In the new pack everything worked perfectly except Pole Position. We followed instructions very carefully but it would still not load.

All our other games load so could you please enlighten us?

I am also e keen if not very good programmer and I like to write very basic games

However the number of games I can write is limited as I have not been ebla to find a command or routine thet will allow me to check e certain screen position to see if there is anything there.

Because of this I can only have one space Invader on the screen et e time – **Matthew Gillie, Oulwich, London.**

● To find the contents of a location on the screen, use:

LOCATE X,Y,A

where X,Y is the position on the screen you want to check, and A is e variable.

After execution, A will contain the colour value for that position, for example in GR 8 that could be 0 for blank or 1 for a dot.

Beware LOCATE moves your cursor about if you use it on a text screen, and will return the Ascii number of the character at that position.

Pole Position should load with Start and Option pressed on power-up. Then press Play on your recorder and Return.

If it doesn't work send the tape back to Atari for replacement

GR.eat colours

THANK you for bringing out a magazine for those of us who don't own a Spectrum or Commodore.

I've just started to use GR.11 and have finally figured how to get 15 colours on to the screen et the seme time.

However another problem has ansen How do I print text on to the screen et the same time, as GR.11 doesn't, as fer as I know have a text window.

Using GR.11 I found I could use 15 colours in your Etcha-sketch progrem. You can do this by edding and changing the following lines:

```
150 C=0
120 GRAPHICS 11
130 X=40:Y=80
240 IF STRIG(0)=0 THEN
    C=C+1
245 IF PEEK(53279)=6
    THEN GR.11
285 COLOR C
```

To clear the screen press Start and to chenge the colours press the fire button

Also do you think you could do a Top 10 of Atari software, as I would like to know the most popular software for my computer

Keep up the good work – **Alan Mulford. Torquey, Devon.**

● No, there isn't a text window with the GTIA modes The only way to get normal text is by using e "DLI" (Display List Interrupt) routine, written in machine code.

Mike Rowe's series should give you some ideas in this direction

SERIOUS BUSINESS OR SERIOUS HOBBY

OUR SERVICE DOESN'T STOP AT JUST GIVING COMPETITIVE PRICES AND A FAST FRIENDLY SERVICE. WHY NOT JOIN OUR COMPUTER DISCOUNT GROUP. WE ARE ONLY A PHONE CALL AWAY AND WE WILL SOON BE OPERATING OUR OWN 24HR. BULLETIN BOARD SERVICE FOR AN EVEN FASTER SERVICE.

Acorn, Agrinet, Atari, Amstrad, Brother, Cannon, Commodore, Cumana, Enterprise, Epson, ICC, Juki, Mannesmann Tally, Mitsubishi, Oki, Onc, Philips, Sanyo, Sakata, Sorcy-Kwamiasedyou, Smithir, Solntsk, Tatung, Torch, Triumph Adler

££££ SPECIAL SUMMER PROMOTIONS ££££

TAXAN/KAGA 810 NLQ PRINTER	£229.00 + VAT =	£263.35
EPSON LX80 NLQ PRINTER	£197.00 + VAT =	£226.55
PHILIPS 7502 GREEN MONITOR 12" 20MHz	£65.00 + VAT =	£74.75
AMSTRAD 6128 + COLOUR MONITOR	£330.00 + VAT =	£379.50

ATARI 520ST + MONO DISC/PRINTER SPECIAL PACKAGE DEAL OFFER
520ST MONITOR STAND + 1MB DRIVES + COLOUR MONITOR ADAPTER + MORE
FUJI 3.5" DISCS SS 135TPI – BOX 5 OF TEN £26.00 + VAT = £29.90

Amstrad 6128 + Green Monitor	£249.00
Atari 520ST (500K Disc/Hi-Res Mon /Mouse/GEM etc) + Box 10 Free Discs & More	£852.00
Atari Monitor/Drive Stand	£26.00
Atari 520ST Compatible 3.5" Double Sided Disc Drives	PHONE FOR DETAILS
Atari 520ST 3.5" Drives In Monitor Stand	PHONE FOR DETAILS
Atari 520ST Centronics Printer Lead	£15.00
Atari 520ST Serial Leads	£12.00
Atari Video/Kaga RGB Lead	£11.00
Atari Video 520ST/Ferguson RGB Lead	£10.00
Atari Video 520ST/Microvitec RGB Lead	£11.00
Atari 520ST Software & Other/Own Products including Hard Disc and Real Time Clock etc	PHONE FOR DETAILS
BBC Model B	£277.00
BBC Model B + DFS	£343.00
BBC Model B Plus (New Model) 64K User RAM + Enhanced DFS	£395.00
5" 400K 40/80T DSDD (Acorn Compatible)	£99.00
5" 800K 40/80T Dual (Acorn Compatible)	£220.00
Cannon 1080A NLQ	£260.00
Juki 6100 Daisywheel	£295.00
MP165 Printer 165/75CPS NLQ (Atari 520ST Compatible)	£219.00
Sakata SCP800 Four Colour Printer/Plotter	£165.00
Triumph Adler TRD 7020 Daisywheel	£305.00
Philips 7002 RGB/CTV Colour Monitor	£189.00
Microvitec RGB Monitors from	£169.00

All prices exclude carriage & VAT. We carry most leading brand names. Please ring to confirm latest prices – You will find us unbeatable. For more information on how to get our monthly price list of genuine discount prices, plus details of the other services we offer contact

K.E.C.M.

(COMPUTER DISCOUNT GROUP)
8 WESTWOOD LANE, WELLING, KENT DA16 2HE
Telephone: 01-301 3745 (10am-10pm)
CALLERS BY PRIOR APPOINTMENT ONLY

P.F. SOFTWARE

SMART ART (16k)

- OVER 80 DIFFERENT COLOURS CAN BE DISPLAYED AT ONCE
- INTERRUPT DRIVEN CURSOR
- 4 BRUSH SIZES
- 3 BRUSH SPEEDS
- AIR BRUSH MODE
- PLOT
- DRAWTO
- FILL
- DRAW BOX
- DRAW CIRCLE
- SAVE PICTURE
- LOAD PICTURE
- SEPARATE PROGRAM TO DISPLAY PICTURE
- DEMO PICTURE

AVAILABLE ON CASSETTE FOR ALL ATARI 8 BIT COMPUTERS ONLY . . . £3.50
(Previous purchasers of Art Atari can upgrade to SMART ART for only **£1.00**)

ALSO AVAILABLE

BLACKJACK (16K) Realistic card display	£1.95
PICTURE PUZZLE (32K) Two pictures to choose from	£2.95
PICTURE TORMENT (16K) Very difficult	£2.95
FRUIT SALAD (16K) Colourful version of mastermind	£2.95
FRUIT PICKIN (16K) Arcade action	£2.95
(Order both FRUIT SALAD & FRUIT PICKIN for only	£4.50)

Cheques & P.O.'s to:
(Overseas orders for single programs please add £0.50)

P.F. SOFTWARE (Dept AU)
14 KIRKSTALL AVENUE
LITTLEBOROUGH
LANCS. OL15 9JA

MILES BETTER SOFTWARE

221 Cannock Road, Chadsmoor,
Cannock, Staffs. WS11 2DD
Tel: (05435) 3577

Brunty Bob	(c)7.95	Snowball	(c)9.95
Strip Poker	(c)7.95	Red Moon	(c)8.95
Strip Poker	(d)10.95	Miami 2043	(c)12.95
Ghost Chaser	(c)7.50	Hitchhikers	(d)24.95
Ghost Chaser	(d)10.95	Zork 1, 2, 3	(d)23.95
Mig Alley Ace	(c)7.95	Planetfall	(d)34.95
Mig Alley Ace	(c)10.95	Infidel	(d)34.95
Solo Flight	(c)10.95	Enchanter	(d)34.95
Solo Flight	(d)10.95	Wish Bringer	(d)21.95
Pole Position	(c)7.95	Cut Throats	(d)27.95
Pole Position	(d)10.95	Mask of the Sun	(d)28.95
Bruce Lee	(c)10.95	50 Mission Crush	(d)28.95
Bruce Lee	(d)10.95	Battle Normandy	(d)28.95
Dropzone	(c)7.95	Battle of Shiloh	(d)28.95
Dropzone	(d)10.95	Combat Leader	(d)14.95
F15 Strike Eagle	(c)9.95	Broad Sides	(d)28.95
F15 Strike Eagle	(d)10.95	Computer Ambush	(d)30.95
Pacman	(c)7.95	Cosmic Balante 2	(d)28.95
Mr Do	(c)7.95	Eagles	(d)28.95
Beach Head	(d)10.95	Field of Fire	(d)28.95
Canoe	(d)10.95	Fortress	(d)28.95
Exodus (Ultima 3)	(d)16.95	Knights Desert	(d)28.95
Nato Commander	(d)10.95	Rails West	(d)28.95
Smash Hits 1 2 3	(c)12.95	Reforger 88	(d)33.95
Smash Hits 1 2 3	(d)14.95	Tigers in Snow	(d)28.95
Colossus Chess	(c)9.95	War in Russia	(d)54.95
Colossus Chess	(d)12.95	Sir Gun Shootout	(d)28.95
Chuckie Egg	(c)9.95	Flight Sim. 2	(d)39.95
Decathlon	(c)9.95	International Karate	(c)5.50
Decathlon	(d)14.95	Chop Suey	(c)7.95
Pit Fell 2	(d)14.95	Chop Suey	(d)10.95
Hare	(d)15.99	Mercenary	(c)9.95
Archon	(c)10.95	Mercenary	(d)10.95
Archon	(d)12.95	Rescue on Fractalus	(c)9.95
Hard Hat Mack	(c)9.95	Rescue on Fractalus	(d)12.95
Hard Hat Mack	(d)12.99	Super Zaxxon	(c)7.95
Mule	(c)9.95	Super Zaxxon	(d)10.95
Mule	(d)12.95	Spy Hunter	(c)7.95
One On One	(c)9.95	Spy Hunter	(d)10.95
One On One	(d)12.95	Tapper	(c)7.95
Murder On The	(d)12.95	Tapper	(d)10.95
Return to Eden	(c)9.95	Summer Games	(d)10.95
Lords of Time	(c)9.95	Blue Max 2001	(c)7.95
Emerald Isle	(c)9.95	Blue Max 2001	(d)10.95
Dungeon Adventure	(c)9.95		

Please phone for the latest releases. Access or Visa cards welcome
Add £1.00 per item for overseas orders. Post and Package is FREE in UK
Phone for new range of Music Compact discs

CENTRONICS INTERFACE



- Transparent to all s/w – no driver programme necessary
- Connect direct to 600 or 800/XL or 130 XE – or to disc drive if fitted

FCC SYSTEMS LIMITED

THE LODGE
MOORLANDS ROAD
MERRIOTT
SOMERSET TA16 5NF
TEL. CREWKERNE (0460) 73442
PRESTEL MAILBOX 046073442

£59.99
+ P&P at £1.00 and VAT = £70.14 Mail Order

Use Access here

DEALER ENQUIRIES MOST WELCOME

FREE T-shirt for all new

Here's a really unbeatable offer for all Atari users!

This top-quality T-shirt, woven in an attractive shade of grey with the Atari logo in red, is a genuine American 'Fruit of the Loom' product, made from 50% cotton/50% polyester.

Worth £4.25, it will be sent FREE with every new subscription ordered on the form on the right!

The T-shirts are also on sale at £4.25. Please order on our official order form.

Made in three sizes:	
Small	– 34"-36"
Medium	– 36"-38"
Large	– 38"-40"

Keying in long programs too much of a chore?

Then give your fingers a rest by sending for our monthly disc, or cassette containing all the programs from each issue of Atari User. See order form opposite.

£3.95

£5.95

MAY: Alphabet Train: The combination of colour, sound and animation makes this early learning game a winner with the children **Sounds Interesting:** Drive your neighbours potty with these ready made sounds **Hexer:** Enter, display and run machine code programs with this hexadecimal loader **Attack Squash:** A fast-action game to keep you on your toes **Reaction Timer:** See how fast your reactions really are **Binary:** Convert denary numbers to binary notation

JUNE: Frog Jump: Guide the frog across the road and river to his home in this version of the arcade classic. **130XE Ram Power:** Use the extra 64k of memory to boost effect, or use the drawing routines to produce some pretty displays **Submarine:** Scuttle the submarines **Etcha-Sketch:** Draw pretty pictures with only a joystick. **Random Numbers:** Get random numbers from machine code **Filthy Fifteen:** Can you keep the Filthy Fifteen happy in their cells?

JULY: Bomb Run: Flatten the deserted city and land safely **Disassembler:** Find out what's going on deep inside your Atari **Treasure Hunt:** Use logical thinking to find the treasure **Password Generator.** Keep generating passwords till you find one you like **Keyboard:** Convert your micro into an organ **Quasimodo:** Can you sort out the mess of ropes in the belfry?

AUGUST: Asembler: Make machine code programming easier **Fruiti Gambler:** Save money with this fruit machine simulation **Mandals:** Complex patterns made easy **Protection:** Protect your programs from prying eyes. **Display List:** Demonstration programs. **Raider 1997:** Futuristic text adventure **Touch Tablet:** Demonstration programs.

SEPTEMBER: Maze Munch: Help Horace the Blob munch the maze monsters' morsels **Data Maker:** Convert your machine code routines to DATA statements. **Display List:** Demonstration programs **Screen Dumps:** Dump your Mode 8 screens to a 1029 printer **Bricks:** Solve the Bricks problem.

OCTOBER: Pontoon: Twist? Bust! **Memory Dump:** Examine memory in hex and Ascii **Display List:** Demonstration programs **Wrap Trap:** Action game for one or two players **Computer Canvas:** Make your own micro masterpiece **Assembler Update:** Improvements for the RAW assembler **Ram Disc:** Make the most of the 130XE's extra memory

Double the capacity of your discs with this money-saving offer!

DISK DOUBLER

Allows you to cut out a correctly positioned notch which will enable you to use BOTH sides of the disc – and HALVE your costs. Extremely well made to a compact design, it has a unique position guide to assure pin-point accuracy!

£9.95

Free disc with DOS 2.5 with each order

subscribers to ATARI USER

Back issues

May issue: Profile of Jack Tramiel, preview of the new machines, Attack Squash, Adventuring, Alphabet Train, Hexer utility, Software reviews, Sounds, the 6502, Microscope, Atari Insights – regular series of tutorials Bit Wise, Beginners and Graphics.

•

June issue: In-depth analysis of the 130XE, Submarine, Adventuring, Random numbers, Software reviews, Frog Jump, Microscope, Sounds, Atari Insights – regular series of tutorials Bit Wise, Beginners and Graphics, special 12 page feature on Communications.

•

July issue: Disassembler, Bomb Run, DOS 2.5, 17 Commandments, Adventuring, Display List Tutorial, Software reviews, Power Functions, Treasure Hunt, Key board Sounds, Microscope, Insights – Regular series of tutorials Bit Wise, Beginners and Graphics

•

August issue: In-depth analysis of the 520ST, program protection routines, Fruiti Gambler, Assembler, Touch Tablet programs, first look at Logo, Raider 1997, Dos 2.5 upgrade offer, Display List Tutorial, Microscope, Software reviews, Insights – regular series of tutorials Bit Wise, Beginners and Graphics.

•

September issue: 8 page special on the 520ST, Mode 8 screen dump routine, Maze Munch, Data Maker, Display List Tutorial, 68000 addressing modes, list processing with Logo, Software reviews, Insights – regular series of tutorials Bit Wise, Beginners and Graphics.

Protect your 130XE with our luxury dust cover made of soft, pliable, clear and water resistant vinyl bound with strong cotton and decorated with the magazine's logo

Only £3.95

How to keep your collection complete

Bound in chocolate brown pvc and bearing the Atari User logo, this handsome binder will hold a year's supply of the magazines firmly secured in place with metal rods.



Only £3.95 (UK)

ORDER FORM

All prices include postage, packing and VAT ***Valid to October 31.***
Overseas orders despatched by Air mail

Please enter your requirements by ticking boxes (✓) £ p

Annual subscription
UK & EIRE £12 (sterling only) 7001
Europe £15 7003
Overseas (Air mail) £30 7004
Free T shirt – circle size required S/M/L
Commence with ... Issue

Back issues
£1.25 UK & Eire
£1.75 Europe
£2.25 Overseas Air mail
May 7005
June 7006
July 7007
Aug 7008
Sept 7009

Monthly Cassette/Disc

		Tape	Disc
Cassette	May 7017		
£3.95 UK	June 7018		
£4.95 Europe/Overseas	July 7019		
Disc	August 7020		
£5.95 UK	September 7021		
£6.95 Europe/Overseas	October 7122/7022		

Miracle Modem including software and Atari interface 7033
£195 UK
£205 Overseas (Air mail)
TOTAL

T-Shirt
£4.25 UK
£5.25 Europe
£5.75 Overseas Air mail
Small 7047
Medium 7048
Large 7099

Dust Cover (130XE only) 7031
£3.95 UK
£4.95 Europe and Overseas

Binder 7029
£3.95 UK
£5.95 Europe Overseas Air mail £6.95

Disk Doubler + free DOS 2.5 7051
£9.95 (UK & Overseas)

ST Companion Book 7054
£9.95 UK and Overseas

Payment please indicate method (✓) TOTAL

☐ Access/Mastercard/Eurocard

☐ Barclaycard/Visa

☐ Cheque/PO made payable to Database Publications Ltd

Credit card expiry date /

Name

Address

Signed

Send to: *Atari User*, FREEPOST, Europa House, 68 Chester Road, Hazel Grove, Stockport SK7 5NY.
(No stamp needed if posted in UK) *Please allow 28 days for delivery*

Orders by phone **061-480 0171**
– by Prestel **Key *89 Mailbox No 614568383**
– by Telecom Gold **Mailbox No. 72-MAG001**

Don't forget to include your credit card number and full address. AT10

STOCKSOFT
ATARI ONLY * MAIL ORDER ONLY

DOS 2.5
Having trouble getting it?
Send Blank disk + 50p in stamps Will post back by return Free service

DISK UTILITIES PAC No. 1
Gives power without the price 4 disks packed with no 60 progs for only £25 — that is less than 50p a prog — amazing but true Comes packaged on two double sided disks at £25 POST FREE

XL FIXER
Will allow you to play games written for 400 800 range on your XL.
Tape version £8
Disk version £10 POST FREE.

RAM DOS XL
Sales only available on 130XE — Now brought to you by STOCKSOFT — We are always first with new ideas Load DOS only once Recall at a press. £10 on disk POST FREE

DISK CRUSHER
Disassembles disk Lists to screen and/or printer
£10 on disk POST FREE

BOOSTER ROOSTER
Is a cassette booster that loads into RAM — 900 baud rate instead of 600 baud rate Saves long re-load time when working on prog or typing that listing.
On cassette £6 POST FREE

ALLOW 7 DAYS DELIVERY
For details of our other unusual utilities plus game packs with games for only £2 each send large SAE to

STOCKSOFT
15 Woodbrooke Road, Birmingham B30 1UE

ADVERTISERS INDEX

Atari	2 & 3	Novagen	54
Chips	62	P F Software	59
Compumart	17	G Paul	62
Computer Support	52	Silica Shop	63
Datastar	14	Silicon Chip Ltd	34
Emap	18	Software Express	10, 24
English Software	14	Stocksoft	62
F C C Systems	59	Sunaro Software	62
Homeview Video	62	System 3 Software	6
K.E.C.M.	59	S Terrell	62
Kuma	64	Wootton Computers	49
Miles Better Software	59	York Computer Centre	49
Miracle Technology	14	Zoomsoft	31

SUNARO software

** STAR ** BOUNTY BOB STRIKES BACK 64k cassette 8.50 ** STAR **
CHOICE STRIP POKER 64k cassette 8.50 **CHOICE**

Cassettes			Disks		Disks	
MIG ALLEY ACE	48k	8.50	WAR IN RUSSIA	75.00	MR ROBOT	12.95
CHUCKIE EGG	48k	5.95	KAMPFGRUPPE	37.50	GHOSTBUSTERS	12.75
AIRWOLF	48k	8.50	CAMMELL TOPCE	37.50	BEACH HEAD	12.75
7471 LIGHT SIM	48k	8.50	SD MISSION CRUSH	37.50	CONAN	12.75
HI JACK	48k	8.95	SIX GUN SHOOTOUT	37.50	BOULDERDASH	13.95
COLOURSPACE	48k	8.50	ULYSSES	26.95	ARCHON	12.75
RIVER RAID	16k	8.50	DARK CRYSTAL	26.95	HARD HAT MACK	10.95
BOULDERDASH	32k	13.25	MISSION ASTEROID	18.95	F 15 STRIKE EAGLE	12.75
DROPZONE	48k	8.50	NATO COMMANDER	10.95	ROM	
SNASH HITS each	32k	12.75	DROPZONE	12.75	MINER 2049er	8.75
ARCHON	48k	9.95	HI-JACK	9.50	QUEST FOR TIRES	13.25
UNL ON UNE	48k	8.50	ONE ON ONE	10.95	HERO	16.95
KISSIN KOUSINS	48k	5.95	SPARTADOS	37.50	PITFALL II	16.95
MULE	48k	9.95	HOMEWORD (W Proc)	49.00	DECATHLON	16.95

New titles always available on release
Prices include postage and VAT

SUNARO SOFTWARE (CA)
PO Box 78, Macclesfield, Cheshire SK10 3PF

ATARI 600/800XL
DUAL OPERATING SYSTEM

You could have a dual opereting system with the flick of a switch. This will allow you to run all known software written for the 400 and 800 computers or your XL.

It consists of a small socket board which simply plugs into computer. No soldering required.

Price £29.95

Mail Order to:

G. PAUL
3 Francis Ward Close, Hilltop, West Bromwich, West Midlands B71 2PY

PLUG THIS INTO YOUR JOYSTICK PORT AND CONTROL THE REAL WORLD WITH YOUR ATARI



This small but powerful unit puts 4 mains rated isolated relays at your command
Just plug it in and let your Atari do more than just play games

TOPFORM
Electronic Services

£19.99 + P&P and VAT
DEALER ENQUIRIES MOST WELCOME

UNIT 6C SOLWAY ROAD
CLAY FLATTS INDUSTRIAL ESTATE
WORKINGTON, CUMBRIA CA14 3AY
Tel: 0900 67436

CARTRIDGE TRANSFER SYSTEM
Transfer your cartridges to disc or tape. Simply plug in the supplied cartridge simulator board and load the tape/disc copy as you would any other program. 48K RAM minimum required specify tape or disc version.

400/800 version £15.00 600/800XL version £20.00
130XE/universal (works on all models) £30.00

FAST LOADER
Reduce the loading time of almost all of your single/multi stage tapes by re-recording them at a faster data rate (up to 49% faster) Fast Loader £6.00

CENTRONICS PRINTER INTERFACE
Operates similar to the 850 but has a 8k 1k character buffer to free your computer for other work.
1K buffer version £59.00 7K buffer version £69.00

PROM PROGRAMMER
Programs both 2704s and 2712Bs. Supplied with full instructions and tape or disc software to perform all usual prom programmer functions. Make your own cartridges using the blank cartridge boards with sockets for 1 or 2 2764s

Prom programmer £60.00 UV Eraser £30.00
Blank cartridge boards £8.50

Prices are fully inclusive no more to pay. The above products are suitable for any of the 400/800XL/800/800XL/130XE computers except where noted. Send S.A.E. for latest catalogue and further details. Add 10% for airmail postage outside the UK.

S. TERRELL
17 Cock Close Road, Yexley, Peterborough PE7 3HJ
These products are not intended for and should not be used for infringement of copyright.

CHIPS
ATARI SPECIALISTS

WE BUY, SELL, PART EXCHANGE ALL TYPES OF COMPUTER EQUIPMENT

THE BEST PRICES
ON THE SOUTH COAST!!
XL, XE, ST RANGE ALL IN STOCK

BULLETIN BOARD
WORTHING (0903) 42013
300 BAUD, RING BACK, 24 HOURS

CHIPS COMPUTER CENTRE 53 RUGBY ROAD
WORTHING, SUSSEX BN11 5NB Tel: (0903) 40509
(24 HOURS)

ATARI AT HOMEVIEW VIDEO
DTDDI 400 800 800XL 800XL 130XE

	Cass	Disk
Drop Zone	£8.50	£13.95
Colossus Chess	£8.50	£12.50
Onaximode	£9.50	£14.50*
F15 Strike Eagle	£14.50	£14.50*
Blue Max 2001	£9.50*	£14.50*
New York City	£9.50*	£14.50*
Ghostbusters	*	£14.50
Conan	N/A	£14.50
Mr Robot	N/A	£14.50
Mr Do	£9.50	*
Bounty Bob Strikes Back	£9.50	*
Hard Hat Mack	£9.50	£14.50
The GT American Road Race	N/A	£14.50
Chop Suey	£8.50	N/A

Plus Miner 2049er, Ollie Well, Decathlon, Pitfall II, Space Shuttle, Tennis, B.C.'s Quest for Tires, Drelbs, Bruce Lee, Pole Position, Fort Apocalypse, Solo Flight, Bomber Dash, etc.
* = Coming soon

Viscalc 48K Min Mem	£45.00
1000's more titles available	
Touch Tablet	£48.50
800XL & Cass Starter Pack	£125.00
800XL + Disk/O Starter Pack	£245.00
130XE + Disk/D Starter Pack	£250.00
520ST	Phone

PHONE ORDERS SENT SAME DAY — OPEN 7 DAYS A WEEK — 24 hr ANSWER SERVICE

Call for Best Prices
CREDIT CARD HOT LINE
01-691 0207

CALLERS WELCOME ACCESS & VISA
RING **HOMEVIEW** NOW
321 BROCKLEY RD, BROCKLEY, LONDON SE4 2QZ

ATARI ST

520ST

POWER WITHOUT THE PRICE

THE NEW ATARI 520ST

Under the new leadership of Jack Tramiel (former boss and founder of Commodore Business Machines) Atari Corporation have marked their entry into the world of business/personal computers with a machine which leaves the competition standing. Tramiel's slogan 'Power Without the Price' has been implemented in the manufacture of the new 512K Atari 520ST colour computer which offers the user amazingly high performance at an incredibly low price. Launched as a work station, this new system incorporates seven software packages as well as the 520ST computer with 512K RAM, mouse controller, high resolution monochrome monitor (640x400), 95 key keyboard (with 18 key numeric keypad), MIDI interface, GEM and a 500K 3½ inch disk drive, all for the package price of only £651.30 (+VAT = £749). Dubbed the Mac basher and the Jackintosh (after Atari's Chief, Jack Tramiel), Atari's new machine has been directly compared with the Apple Macintosh RRP £2596 (+VAT = £2985) which offers similar values and capabilities but at a much higher price. Favourably reviewed by the UK's highly critical specialist computer press, the 520ST is likely to make a great impact in this country as a sophisticated alternative to an IBM PC, APRICOT or APPLE MACINTOSH. Unlike its overpriced competitors the Atari 520ST can be linked up to a colour monitor to unleash a choice of up to 512 colours. The addition of colour brings out the full potential of graphics packages such as GEM.

USER FRIENDLY GEM OPERATING SYSTEM

The power of the ST is harnessed and made user friendly by the new operating system GEM from Digital Research. GEM stands for Graphics Environment Manager and allows a user friendly colour or B/W graphics interface which closely resembles that of the Macintosh. This similarity extends to the use of moveable resizeable windows, icons to represent objects such as disks and disk drives, and the use of pull down menus and a mouse. The advantage of all this is that the computer becomes extremely easy to use. GEM has now been implemented for the Apple, ACT, Atari, IBM, ICL and Olivetti. Software written for GEM on one computer should also run under GEM on another computer. This will enable the market to quickly produce a large library of standard interchangeable software.

FREE SOFTWARE AND FUTURE EXPANSION

The Atari 520ST comes supplied with seven free software packages as listed below: 1) TOS, Tramiel Operating System based on CPM 68K. 2) GEM Graphics Environment Manager by Digital Research (DR) giving a WIMP (Window Icon Mouse Pull down menu) environment. 3) DR GEM Paint for creating graphics masterpieces. 4) DR GEM Write for word processing. 5) Logo learning language to enable you to write your own programs easily using turtle graphics. 6) DR Personal Basic, a powerful user friendly version of the Basic programming language. 7) BOS operating system giving you access to dozens of business applications packages already available on the market. Designed with future expansion in mind, the ST also features a host of different interfaces to the outside world and an impressive list of accessories is planned. Atari will soon be releasing a 1000K (1MB) 3½ inch disk drive and a 15MB hard disk storage system as well as a mass storage compact disk (CD) player capable of storing an entire 20 volume encyclopedia on one disk. A full range of inexpensive printers are planned including dot matrix, daisywheel and thermal colour printers. With its unbeatable graphics, speed and software at a price which is far below that of any comparable personal computer currently on the market, the ST is all set to do battle with the competition. To receive further details of the ST from Silica Shop, just fill in the coupon below with your name and address details and post it to us.

Silica Shop Price £651.30 + £97.70 VAT = £749.00 This price includes:

- ★ 512K RAM
- ★ B/W MONITOR
- ★ MOUSE
- ★ 500K 3.5" DISK DRIVE
- ★ GEM
- ★ KEYBOARD (95 KEYS)

£749

ATARI 520ST SPECIFICATION

MEMORY

GRAPHICS

ARCHITECTURE

DATA STORAGE

DISK DRIVE

SOUND AND MUSIC

KEYBOARD

MONITOR

VIDEO PORTS

COMMUNICATIONS

GEM WIMP ENVIRONMENT

SOFTWARE

VARIOUS

LANGUAGES

BASIC & LOGO supplied

Note: Some of the above specifications are pre-release and may therefore be subject to change

MACINTOSH v F1e v 520ST

"Imagine a Fat Mac, the 512K Apple Macintosh, but with a bigger screen, a larger keyboard with numeric keypad, cursor and function keys and colour. That gives you some idea of what the Atari 520ST is like except for two important things. First the Atari seems faster. Second the Atari system is about one third of the price."
June 1985 PRACTICAL COMPUTING

FEATURES OF BASIC SYSTEM	APPLE MACINTOSH	APRICOT F1e	ATARI 520ST
Price includes B/W Monitor	YES	NO - extra £200	YES
Keyboard size mm (LxDxH)	[illegible]	[illegible]	[illegible]
Keyboard size ins (LxDxH)	[illegible]	[illegible]	[illegible]
Disk Drive (unformatted)	500K	500K	500K
Disk Drive (formatted)	400K	315K	349K
WIMP Window Icon Mouse	Apple	ACT Activity	GEM
Real Time Clock	YES	YES	YES
Polyphonic Sound Generator	YES	NO	YES
RS232 Serial Port	YES	YES	YES
Centronics Parallel Printer Port	NO	YES	YES
Dedicated Floppy Disk Controller	NO	YES	YES
Hard Disk DMA Interface	NO	YES	YES
Full stroke keyboard	YES	YES	YES
Number of keys on keyboard	58	92	95
Numeric Keypad	NO	YES (16 Keys)	YES (18 keys)
Cursor Control Keypad	NO	YES	YES
Function keys	NO	10	10
16-bit processor	68000	Intel 8086	68000
Processor running speed	8MHz	4.77MHz	8MHz
RAM size	512K	256K	512K
Number of graphics modes	1	4	3
Number of colours	Monochrome	16	512
Max Screen Resolution (pixels)	512 x 342	640 x 256	640 x 400
Mouse included	Single Button	NO - extra £95	Two Button
Replaceable External Power Pack	NO	NO	YES
Cartridge Socket	NO	NO	YES
Joystick Ports	NO	NO	YES (two)
MIDI Synthesiser Interface	NO	NO	YES
Monitor Size	9"	9" - extra £200	12"
RGB Video Output	NO	YES	YES

System Cost with: Mouse - Monochrome Monitor - 512K RAM - 500K Disk Drive

	APPLE MACINTOSH	APRICOT F1e	ATARI 520ST
Price of basic system (exc VAT)	£2595+VAT	£595 VAT	£651 VAT
Mouse	Included	£95 VAT	Included
Monochrome Monitor	Included	£200 VAT	Included
Expansion to 512K RAM	Included	£295 VAT	Included
Price of complete system (exc VAT)	£2595+VAT	£1185 VAT	£651 VAT
PRICE rounded down inc. VAT	**£2,984**	**£1,362**	**£749**

PRESS COMMENT

"The 520ST is technically excellent. The 520ST hardware is the new standard by which others will be judged."
July 1985 YOUR COMPUTER

"The Atari ST is one of the most elegant designs I have seen. Atari has used an original and elegant method of memory management which should make the ST faster than any other PC on the market - in any price bracket."
John Lambert July 1985 ELECTRONICS & COMPUTING

"It would seem that GEM offers the ideal operating system."
March 7th 1985 POPULAR COMPUTING WEEKLY

"This machine is significantly more powerful than an IBM PC."
May 11th 1985 PERSONAL COMPUTER NEWS

SILICA SHOP LTD, 1-4 The Mews, Hatherley Road, Sidcup, Kent, DA14 4DX

SEND FOR FREE ATARI ST LITERATURE

SILICA SHOP

ATARI

WE ARE THE UK's No1 ATARI SPECIALISTS

At Silica we have been successfully dedicated to Atari ever since their products first appeared on the UK market. We can attribute our success largely to the Atari specialisation which we practice and to the user back-up we provide. Rest assured that when you buy a piece of Atari hardware at Silica you will be fully supported. Our mailings giving news of software releases and developments will keep you up to date with the Atari market and our technical support team and sales staff are at the end of the telephone line to deal with your problems and supply your every need. With our specialist bias, we aim to keep stocks of all the available Atari hardware, software, peripherals and accessories. We also stock a wide range of Atari dedicated books and through us, the owners on our list can subscribe to several American Atari dedicated magazines. We can provide a full service to all Atari owners and are now firmly established as the UK's NUMBER ONE Atari specialists. Here are just some of the things we can offer to our customers:

- FREE POST & PACKING ON MAIL ORDERS
- FREE NEXT DAY SECURICOR DELIVERY
- INFORMATION MAILING SERVICE
- TECHNICAL SUPPORT TEAM
- HIGHLY COMPETITIVE PRICES
- AFTER SALES SUPPORT SERVICE
- REPAIR SERVICE ON ATARI PRODUCTS

If you would like to be registered on our mailing list as an Atari computer owner, or as a person interested in buying an Atari machine, let us know. We will be pleased to keep you up to date with new Atari developments free of charge. So, return the coupon today and begin experiencing a specialist Atari service that is second to none.

SILICA HOTLINE 01-309 1111

To: Silica Shop Ltd, Dept ATUS 1085, 1-4 The Mews, Hatherley Road, Sidcup, Kent, DA14 4DX

PLEASE SEND ME FREE LITERATURE

ON THE NEW ATARI 520ST COMPUTER

Mr/Mrs/Ms: Initials: Surname:

Address:

Postcode:

Do you already own a computer
If so, which one do you own?

What's on the desktop?

Kuma

A superb range of STware including:



KSPREAD
Spreadsheet

An easy-to-use Spreadsheet enjoying the benefits of the user friendly GEM system with its mouse-driven icon selection and multi-window presentation.

This professional package combines full use of the ST's large RAM capacity with its fast processing speed and facilitates easy data transfer with the **KUMA word-processing, database and communications packages.**

Get down to business with Kuma - first off the mark for the ST

Available from your ST-Dealer

Kuma Computers Ltd., Unit 12, Horseshoe Park, Horseshoe Road, Pangbourne, Berks RG8 7JW.

Please send further details of the Kuma Atari range

Name .....

Address .....

..... Phone.

I own a ..... *computer*

Trade Enquiries Phone 07357-4335

DEF ZZAP! 64 GUIDE

in cooperation with RETROMAGS

Our goal is to preserve classic video game magazines
from years gone by, before they are lost forever.

Thanks goes out to everyone who makes this possible.
Starting with the original writers and editors,
to all the people involved in acquiring and
digitizing these magazines.

People interested in helping us out,
in whichever way possible.
Either by donating magazines, scanning,
editing or helping in the distribution,
visit us as www.retromags.com
or visit www.zzap64.co.uk

We are only interested in preserving magazines
which are at least 10 years out of print.

We have no desire, nor intent to profit
from these scans in any way.

So please,
if you come across people trying
to sell these releases,

DO NOT SUPPORT THEM!

THANK YOU!